


JANUARY 1941

50th
ANNIVERSARY
YEAR

ARCHITECTURAL



To Prevent Seepage — Use Anaconda Through-Wall Flashing



New Administration Building (inset) of the Muhlenburg Hospital, Plainfield, N. J. Architects: Crow, Lewis & Wick, New York. General Contractors: A. L. Hartridge & Co., New York. Sheet Metal Contractor: Conrad Jacobson & Son, Inc., Plainfield, N. J.

Scientifically designed copper flashing provides complete drainage control—efficiently, economically!


Seepage is common in masonry walls because of their porous nature and the possible development of hair cracks. Unless adequate drainage is provided, this seepage begins to stain outside walls and, what's worse, to damage interiors.

Anaconda Through-Wall Flashing provides the easiest, least expensive and most positive method

of drainage control. So designed as to drain itself dry on a level bed, this copper flashing has also been constructed to prevent lateral movement in any direction.

These and many more interesting details concerning Anaconda Through-Wall Flashing are to be found in Bulletin C-28. Ask for a copy.

INSIDE CORNER FLASHING



Standard inside corner flashing unit. Dam on inside, drains out.

OUTSIDE CORNER FLASHING



Standard outside corner flashing unit. Dam on outside, drains in.

These unique one piece corner flashings are installed after straight flashings are in place. Lapping the straight flashings by two corrugations, the corner piece fits snug and secure.

Anaconda Through-Wall Flashing is made of 16-oz. copper in 8 foot lengths. A range of standard and special widths, also various selvages, readily adapt it to practically every brick or masonry condition.

ANACONDA
from mine to customer

Anaconda Copper

THE AMERICAN BRASS COMPANY, General Offices: Waterbury, Connecticut
In Canada: Anaconda American Brass Ltd., New Toronto, Ont. • Subsidiary of Anaconda Copper Mining Company

ARCHITECTURAL RECORD

COMBINED WITH AMERICAN ARCHITECT AND ARCHITECTURE

C O N T E N T S

NEXT MONTH

NUMBER TWO of the RECORD's Golden Jubilee issues will, in many ways, be an extension of the one you're now reading. Perhaps we should have thrown publishing convention to the winds to present a gigantic "January-February Number." For in February the special-paper-ink-and-color section of January is continued as a feature of at least 80 pages.

We're using the same "flash-back" method of contrasting today's design solutions with those of 50 years ago and the same type of open layout. As concerns subject matter, February will continue where this issue stops; and you can look forward to a visually dramatic chart of design progress of such buildings as Schools and Colleges, Churches and Libraries, Hospitals, Theaters, and Office Buildings—to name a few.

Probable future developments in technical fields of the building art will be discussed by the same group of M.I.T. experts who, in this issue, have mapped the course of scientific developments which have made our buildings what they are today. In February they'll project current trend lines and give us a glimpse of what we may be living and working with in years to come.

Building Types for February will deal with Retail Stores. With Time-Saver Standards and characteristically authoritative text and illustrations, it will be a working document that ought to be particularly welcome right now as building volume figures go soaring to new highs.

VOLUME 89

JANUARY 1941

NUMBER 1

COVER DRAWING BY HUGH FERRISS

"MAKE NO LITTLE PLANS—" . . . an editorial 37

WIDER OPPORTUNITIES FOR INCREASED PROFESSIONAL SERVICE
By Edwin Bergstrom, President, The American Institute of Architects 38

AMERICAN ARCHITECTURE 1891-1941: PART I 41

CONTRIBUTIONS OF SCIENCE AND TECHNOLOGY TO BUILDING: 42
A symposium by L. B. Anderson, C. H. Blake, J. E. Burchard, F. G. Fassett, Jr., E. N. Gelotte, E. R. Gilliland, James Holt, Parry M. Moon, P. M. Morse, and John Wulff

HOTELS 58

APARTMENTS 68

MULTI-FAMILY HOUSING 79

TWO-FAMILY HOUSES 83

SINGLE-FAMILY HOUSES 88

COMMERCIAL 113

RAILROAD STATIONS 133

BUILDING TYPES...FACTORY DESIGN 137

FACTORY DESIGN Offers a Challenge to Every Architect 138

Industrial Practice Disciplines the Architect
by Frederick J. Woodbridge, A.I.A. 138

Flow Lines Fit Typical Construction 140

Expansion Can Be Planned in Advance 141

Recent Trends Aid the Factory Designer
by Albert S. Low, Vice Pres., The Austin Co. 142

Ohio Steel Foundry Co., Albert Kahn, Inc., Archts. 144

New Techniques Meet Changed Conditions Economically
by H. K. Ferguson, Pres., H. K. Ferguson Co. 146

Four Factories Designed by Smith, Hinchman & Grylls 148

Preparation for ARP Expands Factory Design to New Fields
by Konrad F. Wittman, Archt. 150

TIME-SAVER STANDARDS 155

Thermal Expansion—Factory Buildings 155

Factory Toilets and Locker Rooms 157

BEHIND THE RECORD 7

WITH RECORD READERS 10

TRENDS IN BRIEF 16

THE LEGAL SIDE OF ARCHITECTURE 22

REVIEWS OF CURRENT LITERATURE 24

IN MEMORIAM: TRUMAN SPENCER MORGAN 33

NEWS OF MATERIALS AND EQUIPMENT 160

LOOKING OVER FENCES, by Jule Robert Von Sternberg 166

INDEX TO ADVERTISEMENTS 198

ARCHITECTURAL RECORD INDEX, VOLUMES 87 AND 88 201

Copyright, 1941, by F. W. Dodge Corp. All rights reserved.

Editorial Director: Thomas S. Holden. Editorial Consultant: Michael A. Mikkelsen. Editors: Roger Wade Sherman (Managing), James M. Fitch, Jr. Associate Editors: Elisabeth Kendall, Frank G. Lopez, Jr., George A. Sanderson. Art Director: Gene Hawley. Desk Editor: John W. Ragsdale.

Architectural RECORD (combined with *American Architect and Architecture*) is published monthly by F. W. DODGE CORPORATION, 115-119 West 40th Street, New York. Truman S. Morgan, Pres.; Howard J. Barringer, Vice Pres. and Treas.; Irving W. Hadsell, Vice Pres.; Thomas S. Holden, Vice Pres.; Michael A. Mikkelsen, Vice Pres.; H. Judd Payne, Vice Pres.; Chauncey L. Williams, Vice Pres.; Sanford D. Stockton, Jr., Secy.; Walter F. De Saix, Asst. Treas.; Edwin H. Freed, Asst. Treas. Member Audit Bureau of Circulations and Associated Business Papers, Inc. Architectural RECORD is indexed in Reader's Guide, Art Index, and Industrial Arts Index.

Subscription rates: United States and Possessions, Canada, Cuba, Mexico, Central and South America, \$3 the year, \$5 for two years, \$6 for three years; elsewhere, \$5 the year; single copy, \$1. Circulation Manager: Robert C. MacDougall.

Manuscripts, photographs, and drawings which conform to RECORD'S editorial aims are welcomed. Every effort will be made to return material (if accompanied by stamped, addressed envelopes); but the editors will not be responsible for losses.

Other Dodge Services: REAL ESTATE RECORD, SWEET'S CATALOG FILES, HOME OWNERS' CATALOGS, DODGE REPORTS, and DODGE STATISTICAL RESEARCH SERVICE.

THIS IS THE *Headline News*
YOU ARCHITECTS, ENGINEERS
ARTISTS and DRAFTSMEN
HAVE BEEN WAITING FOR



THE HOUSE OF
A. W. FABER

proudly announces its new
American-made **DRAWING PENCIL**

WINNER *Techno-TONE*



Pencil craftsmen throughout the country have grown to depend upon A. W. Faber for the finest drawing pencils.

A. W. Faber, the world's most famous name in pencils, crosses a new frontier in pencilcraft with WINNER Techno-TONE. What makes WINNER Techno-TONE outstanding is the fact that it possesses the uniform gradation, the grit-free flowing smoothness and the deep richness of black that you expect only in A. W. Faber pencils.

Architects, Engineers, Artists, Designers and Draftsmen — many of you foremost men in your field — know that the A. W. Faber name on a drawing pencil is a gilt-edge guarantee of quality, performance and value. You know that A. W. Faber has a priceless heritage of integrity

— a tradition that goes back 180 years. In the spirit of this traditional relationship, we respectfully ask all of our friends to buy and try WINNER Techno-TONE . . . strictly on our recommendation. We will gladly send you samples. Please mention degrees desired.

WINNER *Techno-TONE*

17 Degrees — 6B to 9H

"It has the A. W. FABER
name on it."

A. W. FABER *Inc.* NEWARK, N. J.

BEHIND THE RECORD

This New Year is a pretty special one for all of us on the RECORD. As you probably know from the cover, 1941 is the RECORD's 50th Anniversary year. Because such a period comes but once in any kind of a lifetime we thought it called for some sort of recognition. So, instead of marking the RECORD's birthday with a special issue we've planned an editorial celebration that will continue throughout the year. In each issue during 1941 there'll be at least one "Golden Jubilee Feature"—and for some idea of what we mean by that, turn to pages 41 to 136 inclusive in this number. Each feature will be different, of course; but judging by those now in actual preparation, all will be equally interesting and valuable as contributions to the design vocabularies of practicing architects and engineers.

Speaking of features, the special-paper-and-ink section this month was, as they say in the bond business, "oversubscribed." We were swamped with excellent photographs and drawings of fresh, stimulating design from all over the country. We couldn't get it all in January. But your contributions in this issue and the next constitute a truly dramatic parade of building progress—proof positive that America's architects rate top honors for their technical competence and their creative ability in design.

You've heard it before but a paragraph in a recent copy of the R.I.B.A. magazine prompts us to repeat it: buildings today are increasingly appraised on the basis of *performance*.

The English journal, in an article dealing with the war-time uses of architecture, asks for a higher performance standard in buildings and explains why. "In a second-rate hospital," the article states, "patients are cured more slowly than in a good hospital; in a second-rate warehouse, goods are handled more slowly." The point is further emphasized by the remark that a doctor working under

second-rate conditions can treat only ten cases while the doctor under first-rate conditions can handle twelve.

This is precisely what we mean when we say the RECORD stands for *better buildings*—in peace time as well as war. We hope it gives point to the fact that our prime objective is constantly to deliver information that will help readers produce better buildings.

The architectural profession can ill afford to lose any recognized means of training its future members. Thus the recently announced news that New York University's School of Architecture and Applied Arts is to be officially discontinued at the close of the present school year cannot be taken lightly. According to the Council's statement, "The decision is based on no dissatisfaction with the work of the School or with its record. It is based purely upon financial con-

siderations." Somewhere there must exist the means of relieving the strain upon the University's resources so that the school's excellent record of accomplishment can be maintained without interruption; it is earnestly to be hoped that they may be discovered soon.

A brand new society has just been organized in Washington, D. C. It's called the American Society of Architectural Hardware Consultants, and is officered by Howard MacCarthy, Jr. of Baltimore, Md., as President, and Carl D. Hines of Dayton, Ohio, as Secretary-Treasurer. ASAHC's chief job will be to aid in establishing definite standards and in further development of more adequate specifications: two objectives that can do lots toward leading hardware—too often the stepchild of architectural design—into the more abundant life of better buildings.



We succeeded in completely recapturing the 17th century—in the oil burner we use only whale oil.

—Drawn for the RECORD by Alan Dunn



*we're rootin'
for Aluminum Windows*

STUDENTS living in Ohio State University's new men's dormitory have a good outlook on their campus world. All windows in the four upper floors are Aluminum Windows.

It doesn't require a student of architecture to recognize the extra value offered by Aluminum Windows. The greater glass area they provide, their easy opening and closing, weather-tightness and freedom from annoying rattles; these things add to the joy of living with Aluminum Windows.

The building maintenance-man adds his reasons for liking Aluminum Windows: Made of extruded Alcoa Aluminum shapes, there's no rusting or rotting to require expensive replacements of parts. No warping or swelling to require frequent adjustments and refitting. They never need painting.

The book, "Windows of Alcoa Aluminum," lists the manufacturers and pictures many of their windows. For a copy, write Aluminum Company of America, 2167 Gulf Building, Pittsburgh, Pennsylvania.





ALCOA ALUMINUM

DEFENSE COMES FIRST

To meet the needs of the National Defense Program, plus the normal demands of peace, a vast expansion of our already greatly increased production capacity is being speeded. When the emergency is past, there will be more Aluminum available than ever before.

Meanwhile, if you can't get all the Aluminum you want when you want it, remember Aluminum is helping you by helping to meet the National emergency.

WITH RECORD READERS

Maryland Society of Architects Holds First State-Wide Exhibit

ENTHUSIASTIC RESPONSE from architects and interested reception by the public, according to Exhibit Chairman *V. T. H. Bien*, rewarded the recent enterprise of the Maryland Society of Architects in conducting the first state-wide exhibit of contemporary work by members of the profession in Maryland. Over 250 photographs were submitted, showing interior details, as well as exterior details and elevations, of buildings ranging categorically from public to miscellaneous; material was arranged in a display which lasted for over three weeks at the Municipal Museum in Baltimore.

Committee members assisting Mr. Bien were: *Arthur L. Blakeslee*, *Amos J. Klinkhart*, *William T. Malone*, and *Lawrence P. Sangston*. Judges for the exhibit were: *William Dewey Foster*, AIA, Washington; *Edmond Purves*, AIA, Philadelphia; and *Reah de B. Robinson*, AIA, Wilmington.

Regional awards and honorable mentions were given for each of five

CALENDAR OF EVENTS

- **January 1-March 1**—Receipt of proposals of candidates for Edward Langley Scholarships. AIA National Headquarters, 1741 New York Avenue, Washington, D. C.
- **January 27-29**—47th Annual Meeting, American Society of Heating and Ventilating Engineers. Hotel Muehlebach, Kansas City, Mo.
- **February 3**—Opening of Spring Semester. School of Design in Chicago, L. Moholy-Nagy, Director. 247-257 East Ontario Street, Chicago, Ill.

regions into which the state was divided for exhibit purposes. From the regional awards were selected subjects for state award.

Architects whose designs won recognition (in addition to those pictured below) were: *V. T. H. Bien*, one honorable mention; *V. T. H. Bien* and *Ronald Lensman*, one regional award; *Edwin Wilson Booth*, one regional; *Henry Powell Hopkins*, two regional, one mention; *Henry Powell Hopkins* and *Lawrence Hall Fowler*, two state awards, one regional, one mention; *Lawrence A. Menejee*, one regional; *Malone & Williams*, one mention; *Schreier & Patterson*, one regional, three men-

tions; and *John Walton*, one mention.

Additional awards won by the architects cited below: *Douglas Gordon Braik*, three mentions and one state (for the doorway detail of the D'Oench residence, *Bruno L. Zimm*, sculptor); *Amos J. Klinkhart*, two regional and two mentions; *Palmer & Lamdin*, one state, one regional, and two mentions.

First Pacific Northwest Regional AIA Meeting Held in Seattle

SIGNALIZING November 23 and 24 on the Pacific Northwestern professional calendar was the first regional AIA meeting to be held in that area, with the Oregon Chapter, the newly formed Spokane Chapter, and the Washington Chapter convening on those dates in Seattle.

Saturday the 23rd, afternoon and evening, was for the most part given over to divertimento—a tour of Seattle, Producer's Council cocktail party, banqueting and such. "High point of the evening," according to the Washington Chapter's *Monthly Bulletin* account of the proceedings, "and something to which we had all looked forward for months was *Arthur Loveless'* pictures of Burma."

Concentration on business matters and discussion of Institute affairs came Sunday morning after breakfast. *Floyd A. Naramore*, president of the Washington Chapter, opened the session by calling on *Glenn Stanton*, Oregon Chapter president, who spoke on "the intrusion of building organizations into the field of architecture." In conclusion to his suggestions for better publicity among laymen as one means of meeting the problem, Mr. Stanton stressed: "Along with advertising we have to justify our message, and if our services are not superior to those of the people we are trying to supplant, all the educational program is worthless. If we can make our services better

(Continued on page 12)



WINNERS OF STATE AWARDS in the Maryland Society of Architects' Exhibit. Above, left: H. B. Hooper residence, Hagerstown, Md.; A. J. Klinkhart, Architect. Above, right: Russell B. D'Oench residence, Chestertown, Md.; Douglas Gordon Braik, Architect. Below, left: Cambridge Yacht Club, Cambridge, Md.; designed by Samuel E. and Victorine Homsey. Below, right: Professional Building, Baltimore; Palmer & Lamdin, Architects.




HELPFUL DATA

on modern flush valve installation practice in INDUSTRIAL PLANTS


SPEED is so important in the selection of every item for present day industrial plant work that we have developed this brief summary of installation practice on flush valves. These combinations have been widely used by well known industrial organiza-

tions in recent plants after careful study by the architectural firms, contractors and industrial executives responsible. We believe that you, too, can be safely guided by this data in selecting flush valves for both office and factory toilet fixtures in industrial plants.




MOST POPULAR closet combination is that for top spud bowls. Neat in appearance. Moderate in cost. Watrous combinations of this type used by plants of General Motors, Northrop Aircraft, Tuthill Pump, T.V.A. and others.

Specify: Watrous Comb. M-532-VB (for diaphragm type valves); Comb. M-632-VB (for piston type valves). These combinations include vacuum breakers; meet all code requirements.




LOW UNIT COST and wide adaptability make this combination for rear spud bowls popular for industrial plants. Watrous combinations of this type used by such prominent industrials as Eastman Kodak, International Shoe, Imperial Tobacco, Kraft Phenix Cheese.

Specify: Watrous Comb. M-533-VB (for diaphragm type valves); Comb. M-633-VB (for piston type valves). These combinations include vacuum breakers; meet all code requirements.




FOR MEN'S URINALS this combination offers many advantages. A real water-saver. Low in cost. Fits either wall hung or stall urinals. Phelps Dodge, Northrop Aircraft, Eastman Kodak, Frankford Arsenal are users of Watrous combinations of this type.

Specify: Watrous Comb. M-549 (for diaphragm type valves); Comb. M-649 (for piston type valves). Usually used without vacuum breaker.




TAMPER-PROOF, attractive and easy to keep clean is a concealed flush valve installation of this type. Nothing but push button exposed—and button is high above floor to prevent damage from kicking. Recommended for industrial plants.

Specify: Watrous Comb. M-548-VB (for diaphragm type valves); Comb. M-648-VB (for piston type valves). These combinations include vacuum breakers; meet all code requirements.




CONCEALED and out of the way of any tampering or abuse is this combination. Nothing exposed except lever for operating. Makes a very attractive installation. This Watrous combination used by General Electric for new Chicago plant.

Specify: Watrous Comb. M-539-VB (for diaphragm type valves); Comb. M-639-VB (for piston type valves). These combinations include vacuum breakers; meet all code requirements.



NON-KICKABLE and convenient is this high combination. Flushing handle is about 38" above floor. This eliminates possibility of damage due to kicking. This Watrous combination selected by Cincinnati Milling Machine, Corn Products Refining and others.

Specify: Watrous Comb. M-553-VB (for diaphragm type valves); Comb. M-653-VB (for piston type valves). These combinations include vacuum breakers; meet all code requirements.



SHOWER OPERATION in industrial plants can be controlled in no more efficient way than by this new Watrous Shower Head Combination. A push on the button and water flows a given length of time. No possibility of anyone leaving shower running. Pays for itself quickly in savings.

Specify: Watrous Comb. M-666 (Shower head and concealed piping not included). No vacuum breaker required.



HERE ARE TWO REASONS WHY WATROUS FLUSH VALVES

- 1. SAVE WATER.** A simple adjustment makes it possible to regulate any Watrous valve so minimum amount of water will be used for each fixture.
- 2. ELIMINATE MAINTENANCE TROUBLES.** By-pass has patented, mechanically operated self-cleaning device which prevents clogging—keeps valve working properly.




FOR ADMINISTRATION BLDGS., and offices where silent operation is desirable, the use of Watrous SILENT-ACTION Flush Valves is recommended. To specify, simply add words "SILENT-ACTION" after combination number.

THE IMPERIAL BRASS MFG. CO., 1240 W. Harrison St., Chicago, Ill.

Watrous Flush Valves


THEY PAY FOR THEMSELVES IN THE WATER THEY SAVE



LUCKE LEAK-PROOF BATH TUB HANGERS

End leaky, messy, dirty breaks between tub-wall-floor. Guaranteed permanent and leak-proof. Adjustable to all types of built-in tubs.

- No settling
- No water seepage
- No damage to property
- No repair expense
- Quick and easy to install
- Reasonably priced



THE ONLY HANGER GUARANTEED LEAK-PROOF

Because it holds the tub in a steel trough for its entire length—not just at studs. Wall separation at tub rim is impossible, and exclusive patented watersealing makes seepage and leaks impossible. The original and only watersealed Hanger.

Distributed by
Leading Plumbers

Write for free
Catalog. Tells
how to overcome
drippy bathrooms.



LUCKE LEAK-PROOF BATH TUB HANGERS

Wilmette - Illinois

"If it isn't Lucke it isn't Leak-Proof"

WITH RECORD READERS

(Continued from page 10)

than those of untrained and unqualified people, this is our best line."

Harold Whitehouse, president of the Spokane Chapter, speaking next, clinched the need for an educational program by citing an example to show that laymen in the main are amazed to find out what an architect really does for them: "An architect in Spokane was asked to give a talk to women of the A. A. U. W. in the Art Section, and, thinking that this was a chance to educate a few people in how an architect works, he took with him the entire outline of a residence design, from the inception to the finish, and including pencil sketches, detail drawings. He strung these around three sides of the lecture room, and then described how an architect works. There wasn't a woman there with any . . . realization of how thoroughly such a job was done . . . When they realized how minutely an architect considers each small part of each detail, they asked 'Is that why it's so satisfying, then?'"

Committee Appointed to Relate Architectural Graduates to Defense Program

ANXIOUS FOR the special qualifications and abilities of architectural graduates subject to the Selective Service Act to be utilized with utmost advantage in National Defense, the Association of Collegiate Schools of Architecture announces the appointment of "A Special Committee for the Defense Program". Composed of Leopold Arnaud, Columbia University, Sherley W. Morgan (Chairman), Princeton, and George Young, Jr., Cornell, the committee is desirous of co-operating in every possible way with the Government toward achieving this objective. Chairman Morgan writes: "Our problem has two angles: one, the decision as to which, if any, of such especially trained groups should be exempt from military service; and two, the assignment of those who are called to branches where they can be of most value.

"Our Committee has volunteered

its co-operation and received a courteous acknowledgment from Mr. Dykstra, Director of Selective Service, but nothing definite has yet developed. We solicit the assistance of all readers of THE ARCHITECTURAL RECORD in suggesting further lines on which we could be of use, contacts which should be made, and sources of information with which we should co-operate."

Marcel Breuer Appointed Judge for Museum of Modern Art Competitions

ACCORDING TO RECENT word from the Museum of Modern Art, New York City, Marcel Breuer, associate professor of architecture at Harvard University, has been appointed to serve in place of Alvar Aalto as a judge in the Industrial Design Competitions for Home Furnishings which the Museum is sponsoring (see AR, 10/40, p. 12).

Mr. Aalto, internationally famous as a modern architect and furniture designer, has been called back to Finland and does not expect to return for some time. His successor, Mr. Breuer, is also widely known for his work in modern architecture and furniture design.

American Academy in Rome Offers Cash Prizes Totaling \$5,000

ROSCOE GUERNSEY, Executive Secretary of the American Academy in Rome, announces that because of the European situation no fellowships for study in Rome are to be awarded next spring. Instead, the Academy will conduct in 1941 a series of special competitions for money prizes totaling \$5,000. A cash prize of \$1,000 will be awarded in architecture, landscape architecture, musical composition, painting, and sculpture.

The competitions are open to unmarried male citizens of the United States not over 30 years of age. Any person desiring to compete may write

(Continued on page 14)

44 YEARS OF PROGRESSIVE GROWTH



AN INDICATION OF WORK WELL DONE

44 YEARS ago The Raymond Concrete Pile Company began its business career. Today, over 8900 contracts have been successfully handled—primarily because the Raymond organization has the ability, experience and methods to place the type of foundation best suited to meet the particular situation at the lowest cost. That's why engineers, architects and owners have learned to rely on Raymond Methods with a comfortable feeling of security. • When you have a foundation problem let us tell you about Raymond Methods and services.

THE SCOPE OF RAYMOND'S ACTIVITIES

includes every recognized type of pile foundation, concrete, composite, precast, steel pipe and wood piles. Also borings for soil investigation, caissons and construction involving shore protection, ship building facilities, harbor and river improvements.

RAYMOND

CONCRETE PILE COMPANY



Branch Offices in Principal Cities

140 CEDAR STREET • NEW YORK, N. Y.

Air Conditioning in Walt Disney Studios...

Comprehensive Temperature Control

by **JOHNSON**



Johnson worked for months, installing automatic temperature and air conditioning control equipment in the new buildings for Walt Disney Productions, Burbank, California. Hundreds of thermostats, valves, dampers, and damper motors were assigned to the important job of maintaining correct conditions in the various rooms in this great group of buildings. Many of the smaller buildings and projection rooms are incased completely in sound-proof walls, insuring complete elimination of noise... In the larger buildings, distribution of air is influenced by the type of occupancy. Ingenious control apparatus insures accurate temperatures and humidities... How important is the **WHOLE SYSTEM!** How important, too, is the *complete service* offered by Johnson! **ASK FOR BULLETINS** describing Johnson automatic control for air conditioning.



Upper left: Walt Disney (right) and Chief Engineer William E. Garity inspect the Johnson central control panel in the Camera Building. Above: Johnson valves on hot water heating mains in the Central Heating Plant.

JOHNSON

Automatic TEMPERATURE AND AIR CONDITIONING *Control*

JOHNSON SERVICE COMPANY, MILWAUKEE, WIS. & BRANCHES IN PRINCIPAL CITIES

WITH RECORD READERS

(Continued from page 12)

for particulars, stating the subject in which he is interested, to the Executive Secretary, 101 Park Avenue, New York City. Applications must be filed not later than March 1st, 1941.

Jury Named for Bridge Design Competition

RECENTLY APPOINTED as jurymen for the Thirteenth Annual Students' Bridge Design Competition, being conducted currently by the American Institute of Steel Construction (see AR, 10/40, p. 14), were: *John T. Briggs*, Architect; *Matthew W. Del Gaudio*, Architect; *Dr. Shortridge Hardesty*, Consulting Engineer; *Theodore Reed Kendall*, Engineering Editor, "The American City Magazine"; and *Walter H. Weiskopf*, Consulting Engineer. All members are from New York City.

The jury will meet to make selections and awards on February 19 at the Institute headquarters, 101 Park Avenue, New York City.

New Addresses

THE RECORD publishes changed and new addresses only on submission, making no attempt to keep a day-by-day account. The only organization in the country with facilities for doing this is *Sweet's Catalog Service*, whose painstakingly maintained list undergoes an average revision of 23 changes for every working day in the year. Below are the new addresses recently brought to our attention:




JAMES BLAUVELT & ASSOCIATES, Designers of Interiors, announce that *Rebecca Leggett Baker* has joined their organization, 38 E. 57th St., New York City... *Joseph Norman Hettel*, Architect, has moved his office to 501 Cooper St., Camden, N. J.... The new offices of *G. Adolph Johnson*, Architect, are at 390 Main St., Slater Building, Worcester, Mass.... *Francis R. MacLeay*, Consulting Engineer, has joined the Corbetta Construction Co., 220 E. 42nd St., New York City, as Chief Engineer. Mr. MacLeay's consulting office will continue at 415 Lexington Ave., New York City, under the name of MacLeay Associates, and will be headed by *Chester Cronquist*.

Finish floors look better, wear better when sub-floors are made of **PLYSCORD**

Douglas Fir Plywood Sheathing




WOOD FLOORS Plyscord is a perfect base for hard or softwood flooring. Its laminated construction keeps it from cupping, warping, shrinking or squeaking . . . holds nails more firmly. Its large size (it comes in big 4' x 8' panels) reduces the lineal footage of joints in the sub-floor . . . enables Plyscord to be laid in less than half the time of conventional board sub-floors. Guide lines on 16" centers show where joists are . . . speed nailing of both Plyscord and finish floor. Photograph at left shows the living room in the beautiful "House in the Sun," North Hollywood, Calif. Parquet floor was laid over Plyscord. Sumner Spaulding, architect.



CARPET No board marks show through wall-to-wall carpet when it's laid over Douglas Fir Plywood sheathing. The big, smooth panels minimize joints . . . never cup or warp . . . keep clients satisfied. For better results always specify Plyscord sub-floors.


Below is the master bedroom in "The House in the Sun." The carpet will keep its good looks longer and wear better because of the Plyscord under it.



LINOLEUM

Plyscord is a better base for linoleum and rubber tile. The smooth plywood surfaces assure permanently smooth linoleum. Plyscord builds a warmer and more rigid floor, too.

Above: One of the bathrooms in "The House in the Sun." Plyscord was specified under all linoleum. This attractive home was built by Kersey Kinsey and furnished by Bullock's Dept. Store.



Save the above diagrams for future reference.

All progressive lumber dealers stock Plyscord in 4 convenient thicknesses. Inspect them today. Use them on your next job. For more information, consult Sweet's Catalog or write Douglas Fir Plywood Association, Tacoma Bldg., Tacoma, Wn.



SPECIFY DOUGLAS FIR PLYWOOD BY THESE "GRADE TRADE-MARKS"

PLYPANEL D.F.P.A.
TRADE MARK REG. U. S. PAT. OFF.

EXT.-D.F.P.A.
TRADE MARK REG. U. S. PAT. OFF.



TRENDS IN BRIEF

VALUE OF TOTAL CONSTRUCTION CONTRACTS - 37 EASTERN STATES
PRIVATE vs PUBLIC OWNERSHIP

YEAR	NON-RESID.		RESIDENTIAL		PUB.WKS. & UTIL.		TOTAL CONSTRUCTION					
	PUB.	PRIV.	PUB.	PRIV.	PUB.	PRIV.	PUBLIC		PRIVATE		TOTAL	
	WILL. \$	WILL. \$	WILL. \$	WILL. \$	WILL. \$	WILL. \$	WILL. \$	%	WILL. \$	%	WILL. \$	%
1934	234	317	40	210	701	41	975	63	568	37	1543	100
1935	324	357	39	439	644	41	1007	55	837	45	1844	100
1936	409	550	81	721	844	70	1334	50	1341	50	2675	100
1937	393	764	59	846	700	151	1152	40	1761	60	2913	100
1938	572	500	86	900	1047	92	1705	53	1492	47	3197	100
1939	417	549	190	1144	1101	149	1708	48	1842	52	3550	100
1940	450	750	260	1270	970	150	1680	44	2170	56	3850	100
1941 Est.	550	850	550	1150	1100	200	2200	50	2200	50	4400	100

*Based on ten months data

VALUE OF TOTAL CONSTRUCTION CONTRACTS
37 EASTERN STATES

CLASSIFICATION	1941 ESTIMATE	
	MILLIONS OF DOLLARS	% CHANGE FROM 1940 EST.
Commercial Buildings	370	+16
Manufacturing Buildings	440	+16
Educational Buildings	160	+10
Hospital & Institutional	90	+20
Public Buildings	95	+12
Religious Buildings	45	+0
Social & Recreational	80	+14
Misc. Non-Residential	120	+50
TOTAL NON-RESIDENTIAL	1400	+17
Public	550	+22
Private	850	+13
Apartments, Hotels & Dorms	350	+9
1 & 2 Family Houses	1200	+6
Other Shelter	150	+87
TOTAL RESIDENTIAL	1700	+11
Public	550	+112
Private	1150	-8
PUBLIC WORKS & UTILITIES	1300	+16
Public	1100	+13
Private	200	+33
TOTAL CONSTRUCTION	4400	+14
Public	2200	+31
Private	2200	+1

OUTLOOK GOOD FOR 1941 CONSTRUCTION

Construction forecast shows building volumes up with increased opportunities for architects in private practice.

—by THOMAS S. HOLDEN

CURRENT EMPHASIS on defense construction tends to obscure the possibilities of continued large private construction demand in 1941—a demand that directly involves the architect's professional services. The national defense program has been superimposed upon the largest physical volume of industrial production which this country has ever had and the largest private construction volume of post-depression years. Not only is there in progress at this time a huge new public works program (primarily of military character) but also the creation of a new industry, armaments, with all that creation of a new industry implies in terms of general economic expansion. Thus a basis exists for increased activity in privately owned and financed construction, in the development of which the architect has traditionally played a part of major importance.

The Federal Reserve Board's revised industrial production index averaged 108 in the year 1939 and 121 in 1940. In December 1940, it stood at 135 and is expected to average close to the latter figure through the coming years. This will mean increased employment, purchasing power, and national income. National income, estimated at \$69,000,000,000 for 1939 and \$75,000,000,000 in

1940, is expected to reach \$81,000,000,000 in 1941.

In such an industrially active and generally prosperous year, there would ordinarily be an increased demand for private industrial, commercial, and residential building and electric utility construction. Translation of this potentiality into active demands would depend principally upon two factors:

(1) Whether the construction industry has adequate facilities for carrying on a much enlarged program of public and private work.

(2) Whether building costs will increase to the extent of curtailing the demand for moderate-priced private buildings.

Most elements of the construction industry—which has not been employed to full capacity at any time during the past 10 years—are undoubtedly prepared to handle a much larger volume of business during 1941 than existed in 1940. Only with respect to labor does there exist the chance of significant competition between public and private construction markets. Cantonment projects have not only drawn upon existing union membership of the urban centers but also upon previously non-union-building labor customarily engaged in small-house work in suburban

areas and small towns. There appears to be little in the present building picture to justify a fear of shortages of competent building labor other than of local and temporary character. To date, excellent co-operation by the building trade unions in facilitating an adequate supply of labor for defense projects has met the situation very well. Available and potential supplies of essential building materials also appear to be adequate to meet a considerably enlarged demand, though some difficulty may be encountered in making quick deliveries in particular instances.

If it were possible to arrange orderly time schedules for letting contracts on all public and private work, the construction industry probably could handle, in 1941, a 25 to 33% increase over the 1940 volume of construction activity. It may be necessary for some private projects to wait during the rush period of cantonment building. But any need for a drastic priority regulation requiring a certificate of necessity for a private construction project seems re-

(Continued on page 18)

MAKE THIS TEST - *Prove* **BRIXMENT** is BEST!



1

The photograph above shows a cylinder of Brixment mortar (left) and a cylinder of mortar made with portland cement and lime (right). Both specimens were made at the same time, and subjected to exactly the same treatment. After curing for 30 days, $\frac{1}{4}$ " of water was put into the tray and the



2

cylinders were alternately frozen and thawed 15 times. Note in photo 2 that the Brixment mortar remains intact, whereas the other mortar has crumbled badly. This simple test can be made in any ice-manufacturing plant, or in the freezing unit of a domestic mechanical refrigerator.


BRIXMENT Mortar is More DURABLE!

FOR permanent strength and beauty, mortar must be *durable*—must be able to withstand the alternate freezing and thawing to which it is subjected many times each winter.

Brixment mortar is *more durable*. This greater durability is due partly to the strength and soundness of Brixment mortar, and partly to the fact that Brixment is waterproofed during manufacture. This waterproofing helps prevent excessive moisture from entering the hardened mortar—hence helps prevent scaling and spalling when the Brixment mortar is frozen.

Walls built with Brixment mortar therefore *retain* their original strength and appearance. Even in

parapet walls and chimneys, where exposure is particularly severe, Brixment mortar will never require re-pointing.



BRIXMENT

For Mortar and Stucco

TRENDS IN BRIEF

OUTLOOK GOOD FOR 1941

(Continued from page 16)

mote—at least during the 12 months of 1941.

The second factor, building costs, is the really critical one in the situation. Aside from new manufacturing plants and plant extensions required for defense production, the potential private demand is for low-priced structures. The building material price index of the U. S. Bureau of Labor Statistics moved upward from 93.1 in mid-August, last year, to 99.2 in mid-December. During the same period, the cost index for frame houses rose 7½%. Non-union building labor, rapidly acquiring union membership in connection with cantonment jobs, is now being paid at higher rates than previously. This may quite possibly encourage the unions to demand increases as May 1 approaches, if there should be a peak volume of public and private work at that time.

These highly critical price trends will be very closely watched by the public, by agencies of government, and by the building industry. Upon the maintenance of a sound relation-

ship between building costs, rents, and cost of living, will depend the extent of the private building market during and after the peak load of defense construction. Maintenance of a private building market—as long as it can be done consistently with adequate defense construction—is of vital importance not only to our present defense economy, but also to our future post-emergency economy as well. Fortunately, those building cost increases that have already taken place have not, apparently, reduced the healthy volume of private construction. As witness, the Federal Housing Administration's figures for small-house mortgages selected for appraisal and accepted for insurance continued to run well ahead of the previous year right up to the end of 1940.

Common sense, however, recognizes the many uncertainties that exist in the present situation; and consideration of these has prompted conservative advance estimates for 1941 by F. W. Dodge Corporation, as indicated in the tables on page 16. The figures indicate that private construction will probably be approximately equal in total value to the anticipated

record volume of public construction. Particularly noteworthy is the fact that only a slight increase over 1940 in private activity is required to achieve this result.

Architects in private practice have not thus far participated to any great degree in defense construction projects. This has been partly due to the nature of certain military and naval projects, for which plans were made in advance by technicians in the War and Navy Departments. In part it has been also due to the political reasons which caused the placing of considerable responsibility for defense housing projects on the Public Buildings Administration, an agency which is accustomed to using its own planning staff.

As the defense program proceeds, there is likely to be an effort to spread all kinds of defense orders, including construction design and construction contracts, in order to utilize talents and capacities not mobilized in the early stages. It seems possible that later developments in the defense housing program will utilize governmental agencies accustomed to working with private archi-

(Continued on page 20)



Smyser-Royer Veranda Design No. 101
as used by Robert Rodes McGoodwin,
Architect, Tohopeka, Chestnut Hill,
Philadelphia, Pa.

SMYSER-ROYER CAST IRON VERANDAS

Write for our new complete catalogue.

SMYSER-ROYER COMPANY, YORK, PA.


Philadelphia Office: 1717 Sansom Street

SMYSER-ROYER COMPANY

Specify Carey BUILT-UP ROOFS


Whatever the climate, construction, or however complicated the design, the requirements may be met by one of the three basic types, covering 26 specifications, of CAREY Built-Up Roofing.

Industrial Rayon Corporation—Painesville, Ohio. Architects: Wilbur Watson & Associates.
Contractors: Hunkin-Conkey Construction Co.—Geo. A. Rutherford Company.




SLAG OR GRAVEL SURFACE

12 specifications to meet requirements for 15- or 20-year roofs over any type of deck construction. Recommended primarily for flat roofs or those with a comparatively slight slope.



WHITE CERAMIC GRANULE SURFACE

4 specifications for 10- and 15-year roofs, for any type of construction. This type of roof is particularly recommended for hot climates and for steep slopes.



SMOOTH ASPHALT SURFACE

10 specifications for 10- and 20-year roofs for all types of deck construction. For climates of mild temperature, for steep slopes and recommended as a base for tile-covered flat-roofed areas.

FOR BETTER PERFORMANCE

By basing their roof specifications on the balanced consideration of climate, construction and costs — each a vital element in the roof design of industrial buildings — architects throughout the nation have been getting better roof performance.

Climate Satisfactory roof performance largely depends on ability to withstand climatic conditions. Prolonged, intense heat of the sun, extreme dryness, wide temperature fluctuations, the prevalence of corrosive fumes in the atmosphere—all these, unless provided for, affect economical roof life. Roofs don't just wear out; they also dry out. The materials lose their elasticity, and crack with expansion and contraction.

Factory roofs are usually subjected to severe exposures and should be selected with care. A CAREY built-up roof specification is available to meet every climatic condition.

Construction The specification of a factory roof will vary according to the character of its roof deck—both slope and construction being important. The versatility of built-up roofing application makes it particularly adaptable to saw tooth and similar types of factory roof construction where flat and steep surfaces are combined. However, because some types of roofing materials tend to soften easily in the sun and therefore flow on steep inclines, a careful study of roof characteristics is advised. The deck surfaces, also—whether wood, concrete, gypsum or steel—must be properly prepared and the roofing material expertly laid if a long, trouble-free life is to be expected.

Cost The money available often becomes the governing factor. Nevertheless, if the climate and the construction of the deck have been duly considered, a built-up roof of guaranteed performance can always be obtained within the limitations of any reasonable budget. A bonded roof, guaranteed for a life of 10, 15 or 20 years does not imply a difference in product quality—it is merely an expression of the reputable manufacturer's experience that a certain quantity of his product, properly applied, will not fail within the time limits specified.

BONDED FOR PERFORMANCE

The materials that go into a CAREY Built-Up Roof are "Bonded for Performance." Layer on layer, each roof is built up of superior, quality products to rigid specifications evolved from years of research. CAREY Roofs retain their elasticity through the severest weather—they will not melt under the sun's heat, nor will they crack in zero temperatures. CAREY'S 67 years of progressive manufacturing skill, and the invaluable experience of thousands of roofs successfully installed, are at your service. Our Engineering Department invites your inquiries.



Send for this book of Specifications—address Dept. 21.




See our Catalog in Sweet's

THE PHILIP CAREY COMPANY • LOCKLAND • CINCINNATI, OHIO

Dependable Products Since 1873

IN CANADA: THE PHILIP CAREY COMPANY, LTD. Office and Factory: LENNOXVILLE, P.Q.



ONE SPECIFICATION—house heating equipment—can make *so much difference*. Streamlined gas-fired PAYNE Furnaces include all the discoveries of modern heating and ventilating science that make for reliable, economical, safe warmth—year after year. ¶ Styles and sizes for any job—bungalow to mansion. Join many of the Nation's leading architects in specifying PAYNE quality and style, at PAYNE's moderate cost.

***Lasting Client Satisfaction**

Complete information at your Dealer or Gas Company. Or write us.



PAYNE Duplex Furnace

- Forced Air Units
- Modern Consoles
- Floor Furnaces
- Duplex Furnaces
- Zoneair Units
- Gravity Furnaces



PAYNEHEAT
Payne FURNACE & SUPPLY CO., INC.
— BEVERLY HILLS • CALIFORNIA —

TRENDS IN BRIEF

(Continued from page 18)

fects. That eventuality and the subsequent necessity of decentralizing activities incident to planning and design may bring private architects more and more into the picture.

Entirely beyond any construction program associated with current defense activities there will exist, in 1941, excellent opportunities for large business volume for architects in private industrial, commercial, and residential building. Industrial projects thus far have tended to large size and to concentration of planning effort in a relatively small number of designing offices, but decentralization of defense production is likely to stimulate large numbers of smaller industrial projects as the year progresses. Commercial and residential building tend

to be widespread. While a moderate decrease is estimated for private residential building, this would be likely to take place, if at all, in the field of small-house development projects rather than in single houses built for owners' occupancy.

Even on the basis of the very conservative estimates of private building activity here shown, the total volume of private architects' business should increase in 1941. It is entirely possible that, as the critical first half of the year progresses, private building demand will accelerate faster than these estimates indicate, unless new defense appropriations that the incoming Congress may make should provide for a vastly enlarged volume of defense construction.

WASHINGTON NEWS ON DEFENSE ACTIVITIES

Deferment likely for nondefense projects. Stabilization of labor and material prices now a major consideration of Defense Council.
—By KENDALL K. HOYT

CONTINUED EXPANSION of the defense program, coupled with increasing aid to Great Britain, is beginning to have effects upon the outlook for architects which can now be definitely charted.

Mainly, these two things are happening: in the government field, a sharp curtailment of construction not related to defense is being pushed from every quarter; in private practice, wage and price considerations are demanding new concepts as to the use of construction materials.

Nonmilitary work curtailed

There is no room for doubt that the forthcoming budget for the fiscal year ending June 30, 1942, to be made public early in January, will be sharply cut in all categories not strictly related to the national defense. Since in recent years the Congress has kept very close to the budget estimates in its appropriations, these cuts will probably be retained.

This is particularly so in the construction field. Although Congress has upped such items as farm relief, it

has been economy-minded on public works and housing. From the viewpoint of the Administration, curtailment is necessary not only to conserve funds, materials, and skilled workmen for defense but also to build up a backlog of work which will help take up the slack after the preparedness effort ceases. Later revival of the public works and spending policy as a check to deflation is an important long-range consideration.

Meanwhile, the Federal Government not only is planning to hold back funds for construction next year but is slackening the work on nonmilitary programs under existing appropriations. The Budget Bureau recently took steps to impound unobligated funds for public buildings outside of Washington.

Military construction expanded

Instead of the familiar public buildings, such as post offices, schools, and hospitals, slum-clearance and low-cost housing projects, and the like,

(Continued on page 170)

Rolling Steel DOORS

Typical of the service Mahon Steel Doors are rendering various types of industry, is the installation in the plant of the Pfeiffer Brewing Company, Detroit, illustrated below.



WHATEVER THE DEMAND . . . There's a MAHON Door to Serve

Of the many desirable and exclusive features of Mahon Rolling Steel Doors, flexibility of installation is an important consideration. Mahon Doors and Grilles are giving trouble-free service in all types of industrial and commercial structures—in hospitals, schools and other public buildings—wherever adequate protection from fire and burglary is essential. Installations are available for fire walls, elevator shafts or exterior openings and can be made on the face of the wall or in the door opening. Doors may be both manually and electrically operated and are counterbalanced for easier operation. The expertly engineered interlocking slat construction, of copper bearing, galvanized steel, assures exceptional rigidity and lifetime service with little or no maintenance expense. Mahon engineers will analyze any door problem you may have and make detailed recommendations and cost estimates.

THE R. C. MAHON COMPANY, DETROIT, MICHIGAN

Representatives in Principal Cities

Manufacturers of Rolling Steel Doors and Grilles, Kalamein and Tin Clad Doors, Steel Roof Deck and Cast Iron Roof Sumps



THE MAHON POWER OPERATOR

offers distinct advantages in design and construction. All gears are enclosed in an oil-tight gear box and run in a bath of oil. Power operating unit functions entirely independently of manual operating mechanism and is so engineered that it may be completely removed and the door continued in service by means of the hand-operated auxiliary chain-gear.

MAHON

THE LEGAL SIDE OF ARCHITECTURE

THE RIGHTS AND POWERS OF THE ARCHITECT

By NATHAN YOUNG

THE RIGHTS AND POWERS of the architect described in the general conditions of a contract between owner and contractor may be called the express powers. However, the architect must often perform acts not expressly authorized but reasonably necessary to carry out the intent of the express powers. These additional powers are known as implied powers and may be exercised by the architect as validly as the express powers. What is reasonably necessary must depend upon the circumstances of each case. The case of Schnaier v. Nathan, decided in New York, may serve as an illustration of such a situation. Here, it appears that the contract required the work to be done to the architect's satisfaction. The architect, who was empowered to supervise the construction, had authorized the plumbing contractor to deviate from the plans and specifications in trivial matters. The Court held that in the absence of fraud or collusion with the contractor, the architect had implied authority to consent to such changes.

A problem which the architect must often ponder over is: "What degree of learning, skill, care, and diligence may a client expect of me? Should I undertake to execute a commission do I impliedly represent myself as possessing specialized training and experience? In supervising construction, do I undertake to exercise extraordinary care and diligence?" For answer to these important questions, let us consider the case of Major v. Leary, recently decided in New York, wherein it appears that the plaintiff architect was engaged by the defendant owner to design and supervise the construction of an elaborate country residence. The Court found that there were, as may often happen, some mistakes in the plans and specifications. The Appellate Court, affirming a judgment in favor

of the architect, stated in its opinion in part as follows: "The law does not expect or require absolute perfection, but tests the efficiency of the architect by the rule of ordinary and reasonable skill usually exercised by one of that profession."

In Hubert et al v. Aitken, another leading New York case, it was held that the architect is *not* "bound to spend all his time at a building which is going up under his professional care so that no fraud or negligence can be committed by any of the contractors," but that the architect "is bound only to exercise reasonable care and to use reasonable powers of observation and detection in the supervision of the structure."

So long as the architect acts within the scope of his authority, he binds only the owner. What happens when he exceeds his authority? This problem has two aspects. First, the architect may act in accordance with his express or implied powers, but contrary to secret instructions of the owner. Second, he may assume powers never delegated to him.

As an illustration of the first case, let us assume that the contract authorized the architect to alter the plans and specifications and to order extra work performed, but that the owner, without the contractor's knowledge had secretly instructed the architect not to make changes without first obtaining the owner's consent. Let us further assume that the architect, disregarding the owner's instructions, and without consulting him, orders extras. Manifestly, the owner is bound because the contractor had a right to rely on the terms of the contract. But the architect is liable to the owner for his failure to obey the latter's instructions.

In the second case, the owner is not bound, but the architect is liable to the contractor for misrepresentation of authority, unless the contrac-

tor had been advised of all the facts regarding the architect's authority.

In the matter of Reifsnnyder et al v. Dougherty, decided in Pennsylvania in 1930, it appears that the contractor undertook to construct a church, pursuant to a contract with the defendant, Cardinal Dougherty. The contractor got into financial difficulties, and unpaid sub-contractors threatened to stop work. The parish priest, with knowledge of the architect, told the sub-contractors that there was plenty of money to pay them if they continued to work. They did continue and then sued for payment.

The Court, in denying recovery to the sub-contractors, stated in part as follows: "The knowledge of the architect of the priest's acts would be neither knowledge nor notice to the appellee (defendant). The architect had no authority to increase the liability of the owner; his connection with the contract is fixed by the writing to pass upon the efficiency of the work, labor, and materials; to determine the right of the contractor to receive payment; to interpret the plans and specifications; and such other powers as are specifically given to him by the contract. . . ."

"We have held that an architect could not impose on the principal the additional liability of paying sub-contractors unless he had specific authority to do so."

The right to exercise many quasi-judicial functions places a great responsibility on the shoulders of the architect. For, though he is the owner's agent, and as such must concern himself primarily with his client's welfare, he nevertheless is empowered to make important decisions, which will substantially affect the contractor's rights and are binding on the latter. Oddly enough the Courts have held that capricious and even unreasonable conduct on the part of the architect does not affect the validity of his decisions. To upset the architect's decision, it is necessary to establish fraud on his part, or collusion with the owner.

A Completely Enlarged Concept of Fire Extinguishing Specifications

Put yourself on

CARDOX



THIS DATA FILE
Offered To Put Your
Office in Possession of
the Impressive Facts



CARDOX is a system of instant fire extinguishment by release of CO₂ in great volume—a unique characteristic of this system—"Not pounds, but tons!" These four words summarize what Cardox brought to the techniques of positive fire extinguishment.

The data file offered above tells what Cardox brings, today, to the architect designing and specifying for new industrial construction subject to the particular threats of sabotage by fire. Every co-operation to the architect on large plant construction is offered by the Cardox engineering staff; but first get the essential facts about Cardox so your organization may act on up-to-the-minute knowledge.

The interesting thing about Cardox, you will find, is its wide range of application—giving you the broadest scope for new specifications. Ask your secretary to write us for the Cardox Data File.

A FEW OF THE SIGNIFICANT ADVANTAGES

★
Piping installations tremendously simplified.

★
A single discharge nozzle by high capacity provides ample protection for the average large room.

★
System is engineered for complete fire protection layouts to employ every automatic device and insure extinguishment of any blaze in its incipient stage before extensive damage occurs.

★
Complete freedom from damage by the extinguishing medium.

★
Centralized storage of CO₂ in unlimited quantities (125 Tons is the largest installation to date) for release through any branch of the system—serving all hazards.

★
Cardox Systems easily extended to additional hazards as plant expands.

★
Constant visible indication of liquid CO₂ in storage container... Ready replacement supply through truck delivery service... No dependence on external supply of extinguishing medium (as water supply, fire department, etc.)... Freedom from freezing difficulties.

CARDOX CORPORATION ★ BELL BUILDING, CHICAGO, ILLINOIS

REVIEWS OF CURRENT LITERATURE

Compiled by ELISABETH COIT, AIA

DOMESTIC ARCHITECTURE OF H. T. LINDBERG. With an Introduction by Royal Cortissoz. New York, William Helburn, Inc., 1940. XVI, 310 pp., 11 by 14 3/4 in. Photos, plans, renderings in line and in color. \$15.00

WE ARE FORTUNATE in having assembled in permanent form in a handsome volume about a hundred homes, projects, furniture designs, and other items in the confession of faith of Harrie T. Lindeberg.

For the collection here presented includes, in the work of just a third of a century, houses great and small in a large variety of settings, and reminiscent of all the domestic styles: Colonial and otherwise classical, Tudor and otherwise English, Norman farmhouse and many another French type, and so on, including the non-modernistic modern. At the same time there are no style copies, and there are even no replicas of Lindeberg houses. An individual and suave piquancy runs through the whole, an important ingredient of which seems to be a balanced asymmetry not found in any of the historic styles, and the logical result of solving the client's particular plan requirements for a site often unusual.

Some three score of the plates here presented are known to readers of the RECORD, which seven years ago published an H. T. Lindeberg number, and not long thereafter gave us the two chapters which conclude the present work: "A Return of Reason in Architecture" and "Cellular-Steel Unit Houses." Those articles and the special Lindeberg number included

many of the fine Wenrich and Neilinger renderings which contribute to the beauty and variety of this book.

TOWN PLANNING. By Thomas Sharp. New York, Penguin Books, 1940. 152 pp., 4 1/2 by 7 1/8 in. Illustrated (photos). Paper cover, \$0.25

AN EVERYMAN'S book by a lecturer in town planning at Durham University, this readable, condensed little book is lacking only in having a title not comprehensive enough to cover its scope. The author of "Town and Countryside," a practicing consultant and designer of planning schemes in various parts of England, writes on planning for a civilized background for human life, in which nowadays town, country, and suburbia form a continuous whole. The work assumes that all planning is essentially planning for peace, however war may interrupt. It envisages the eagerness with which the present generation will return to normal life, expecting to find tomorrow's planning policy clear as to objectives and means for attaining them.

This is one of the Pelican Series, weighing a few ounces and containing well-presented matter enough for a large book.

OLD MARBLEHEAD, PORTSMOUTH, N. H. By Samuel Chamberlain. New York, Hastings House, 1940. 73 pp. each. 6 1/4 by 7 1/2 in. Photographs, text. \$1.25 each

THESE TWO camera records in the American Landmarks Series come from the "inquisitive" and "impres-

sionable" lens of Samuel Chamberlain, famed not only as the Artful Dodger of telephone poles in his dramatic photographs of the American scene, but as an established artist in many mediums. The happy conjunction of sound composition and crackling contrasts is no less apparent in his photographs than in his drawings and etchings; and the text, concise, well founded, and pithy, enhances the illustrations. Seventy-three photographs in each volume are augmented by handsome end papers. The little books in this series include also Gloucester and Cape Ann, Historic Salem, Longfellow's Wayside Inn, Historic Boston, Nantucket, Lexington, and Concord.

GUIDE TO MODERN ARCHITECTURE IN THE NORTHEAST STATES. Edited by John McAndrew. New York, Museum of Modern Art, 1940. 126 pp., 5 1/2 by 7 in. Plans, photographs. \$1.00; paper, \$0.25

DESCRIPTIONS of significant modern buildings from the District of Columbia to Maine with date of erection, name of architect, whether they may be viewed and if so when, directions for reaching them, cost, important features.

CURRENT PERIODICAL LITERATURE

Taliesin: Publication of the Taliesin Fellowship. Edited by Frank Lloyd Wright. Spring Green, Wis., The Fellowship. Vol. I, No. 1, Oct., 1940. 40 pp., 8 3/8 by 8 3/8 in. Illustrated. \$0.50 a copy.

TALIESIN is to be published six times a year, and this first number offers a

(Continued on page 178)



From "Domestic Architecture of H. T. Lindeberg"



TRUMAN SPENCER MORGAN 1868-1940

IN MEMORIAM

TRUMAN SPENCER MORGAN, President of the F. W. Dodge Corporation, died Dec. 21 at his home, 1111 Park Avenue, New York City. Seventy-two years old, he had been associated with Dodge 38 years and President since 1920. In his capacity he was identified with the management of ARCHITECTURAL RECORD, Dodge Reports, Sweet's Catalog Files, Dodge Statistical Research Service, Home Owners' Catalog, and *Real Estate Record*.

Born in Rockton, Ill., Mr. Morgan grew up on a farm ten miles from Beloit, Wis. Driving into town on a load of straw for the paper mill, he watched the boys coming and going on the campus of Beloit College and his purpose was fixed to become one of them. By dint of teaching in a country school he put himself through "prep" and matriculated in the College, where he was graduated in 1892 with an A.B. degree.


He had planned a medical career, but drifted into publishing while in college, as reporter and city editor for the Beloit *Daily Citizen*. Printer's ink held fascination for Truman S. Morgan. But perhaps it was a vision of what the next half-century would bring to the building field that turned his steps, after commencement, toward Pittsburgh, center of the steel industry.

Beginning of the building era

For building, in 1892, stood at the beginning of an era. Its importance was becoming recognized with the development of steel and the birth of the skyscraper. ARCHITECTURAL RECORD, symbol of a dawning consciousness, was celebrating its first birthday. In Pittsburgh Mr. Morgan became business manager of *The American Manufacturer and Iron World*; and two years later he acquired *The Journal of Building*, which he published in that city for eight years.

With this pioneering publication as mouthpiece, Mr. Morgan became an arbiter of construction practice and an important figure in the background of building activity. The expanding industry received stimulus and nourishment from *The Journal of Building*. In its columns were promoted continually development and subsequent acceptance of technical advances.

It was while publishing *The Journal of Building* that Mr. Morgan's talents and his authority in the building field came to the attention of Frederick W. Dodge, who was at that time extending his construction news service to cover many states, and his associate, Clinton W. Sweet,



publisher of the ARCHITECTURAL RECORD. In 1902 Mr. Morgan was induced to accept a position as treasurer and manager of the F. W. Dodge Company of Pittsburgh.

ARCHITECTURAL RECORD, when he came to the Dodge organization, was a small folio volume. Its interest lay largely in European architecture, although even then it was beginning to recognize the importance of American design as one of the country's most potent forces. Two years later the RECORD was to comment on the Singer Building of Ernest Flagg, "If the architect cannot dispense with the skyscraper, the next best thing for him to do is really to grapple with it."

Elected president in 1920

There followed for Truman S. Morgan nearly two decades in which, as Pittsburgh manager for F. W. Dodge Company, he watched building come to the full stature of its swift and amazing growth. In recognition of his intimate understanding of the problems of the industry and its needs, present and future, he was called to New York in 1920 as President of the company, which became F. W. Dodge Corporation in 1923.

(Continued on page 34)

(Continued from page 33)

His election was synchronous with great expansion of the industry, as an aftermath of the first World War and the release of epoch-making inventions in transportation, communication, and entertainment. ARCHITECTURAL RECORD was rapidly extending its editorial scope to embrace many new aspects of building progress. Sweet's Catalog File for architects, reflecting the need for a technical information service during the coming years, was to expand its one volume to five. And Dodge Reports Service, in response to increasing demand for reliable market information, was to grow in annual volume of construction reports issued from 20 to 592 million.

Period of innovation

This was a time of innovation. New construction practices loomed large—almost as an answer to the early persuasion of Truman S. Morgan in his *Journal of Building*. Mr. Morgan recognized the necessity for coordinating the various forces that were rapidly asserting themselves within the industry. He saw his convictions substantiated in the rapid, powerful growth of such groups as the American Institute of Architects, Associated General Contractors of America, and Building Congresses.

Speaking in 1923 of the newly formed New York Building Congress, he predicted that "the congress idea will, in some form, ultimately prevail throughout the nation . . ." and that "its code . . . will become the rule of action of an enlightened and prosperous industry." In speeches before many factors throughout the field of construction, Mr. Morgan recommended round-table collaboration among bankers, architects, contractors, mechanics, and laborers.

Delegate to Paris Congress

As a result of his concern with the future of the building industry as a vitalizing force in this country, Mr. Morgan was appointed in 1925 American delegate to the Paris Congress of the International Federation of Building and Public Works. President Hoover named him delegate to the Federation's 1930 Congress in London.

He served as American Vice-President of the Federation, and was made honorary councillor by the governing body. In numerous conferences of industrial leaders with national administrations in Washington, Mr. Morgan took a prominent part. He was selected in 1931 to speak for building and real estate in a series of nationally broadcast talks by outstanding leaders.

Throughout his presidency of the F. W. Dodge Corporation, Mr. Morgan's counsel spurred the progress of ARCHITECTURAL RECORD. He watched with satisfaction as its pages came more and more to reflect his own unflagging interest in technical research, new structural de-

velopments, and a continually wider range of architectural activity that embraced the field of small houses, a subject in which he was particularly interested. "New building methods and improvements of all kinds," he said, "represent advances in the standards of living; and construction, particularly home building, may be considered a measuring rod of progress."

His abiding optimism as to the future of the industry was rooted in his faith in the technical ability and professional position of the architect. He studied closely the evolution of a characteristic American "style," which, fathered by Louis Sullivan, is today rapidly approaching a peak under the impetus of the new technical developments which throughout his life so closely held Mr. Morgan's interest. "Today we lead the world in the character of our architecture," he declared, "both as to its beauty of design and its utility."

Broad interests

Mr. Morgan's chief extra-curricular interest lay in Christ Church, Methodist, New York, of which he was a member and trustee many years. During development of Ralph Adams Cram's design for the church building, dedicated in 1933, Mr. Morgan generously contributed both financially and of his balanced judgment and invaluable experience in building and architecture. Four roundel windows and a large rose window, his gift, were dedicated last November.

His humanitarianism flowed into a genuine liking for people. He could tell a good story, was a humorous and charming dinner partner as well as an able speaker. He enjoyed travel, covering this country many times, and toured Italy, Austria, Germany, and Switzerland with his family. The South he loved, especially Miami and St. Petersburg, where with Mrs. Morgan he spent many winters, and New Orleans. His interest and confidence in the industrial future of the South, as the newest frontier of the America that he had helped to build, was reflected in the fact that during his presidency of the Dodge Corporation were opened the Atlanta, New Orleans, and Dallas offices, covering Texas, Louisiana, Mississippi, eastern Tennessee, North and South Carolina, Georgia, Alabama, and Florida. This expanded the Dodge Report Service to its present coverage of 37 states.

A Trustee of Beloit College, he was a former Chairman of its New York Alumni and a member of the Phi Beta Kappa Society.

Mr. Morgan was a director of the New York City Society of the Methodist Church, and a member of the New York Building Congress and Merchants' Association of New York. A thirty-second degree Mason, his clubs included the Union League, Advertising Club of New York, and Iron City Fishing Club of Canada.

"MAKE NO LITTLE PLANS—"

—Daniel Hudson Burnham

This year ARCHITECTURAL RECORD begins its second half-century of service to the architects and engineers of this country.

During the past 50 years the RECORD has stood constantly for advance — for better architecture, for improvement in all branches of the technical arts, for betterment in the economic structure and practices of the building industry, for a more penetrating understanding of the country's social needs. In times of war and peace, through panics and depressions and during periods of prosperity, the RECORD has been privileged to report the almost miraculous development of this country as reflected in the achievements of architects and engineers. And it is good to know that the magazine has proved a forceful instrument of technical progress and a virile source of inspiration for the development of a truly American idiom of design.

Today the basic purpose of the RECORD remains unchanged. As in the past it stands for advance; and pages of its forthcoming issues will chronicle whatever progressive developments in the art and science of building America's architects and engineers may contribute to the future.

Their contribution, we believe, will be great. One need not be a seer to forecast a challenging opportunity to rebuild in new and better ways; or to foresee appearance of vastly more adequate, economical, and efficient ways of doing so. As the democratic world looks now to American industry for help, so, we believe, will it look for technical leadership in the future. Our own cities, towns, and villages are even now being slowly remade under the pressure of new social and economic forces. As years flow into the past they will undergo a complete metamorphosis, achieved through the skill of American designers with technical means of which today we can only dream.

Architects and engineers face professional opportunities immeasurably greater than those in the past. The RECORD dedicates the beginning of its future half-century to that conviction.

This future, it believes, will be thrilling, vastly important, incomparably great. With America's architects and engineers the RECORD stands on the threshold of a time to stir men's blood. And for that time all of us can "make no little plans".



*Edwin Bergstrom, President of the A.I.A.,
discusses the future of architects, and sees —*

WIDER OPPORTUNITIES FROM INCREASED PR

WAR AND THREATS OF WAR always act as an interruption to the normal pattern of professional activities. Today, with the National Defense program in full swing under stress of an acute emergency, America's architects find themselves affected as profoundly as at any time during their professional lifetime.

The situation is complicated by a number of elements. The vast scope of our defense efforts points the need for a huge number of buildings of all types. The necessity for the utmost speed in constructing them, the various special purposes they are to serve, and even the administrative circumstances under which they are being developed—all these operate, singly and in combination, to disrupt the normal functioning of architectural practice.

Thus, any realistic estimate of professional opportunities for architects must take into account the economic and social turmoil in which we now find ourselves before trends of the future can reasonably be mapped.

Few will question the statement that policies and programs dictated by our present emergency embody potential dangers to the professional practice of architecture as most of us have known it. Yet most would also agree, I hope, with my own conviction that this same emergency may prove to be a period of transition to a professional status embracing a much wider scope of productive action than architects have ever before enjoyed.

We are faced in 1941 with rising prices in the construction field and with a time priority which must be given to defense projects. These factors will tend to act as a brake on private building unless such building is concerned primarily with defense orders for industrial plants or housing to care for workers in those plants. Private capital cannot be counted upon to provide all such needed construction and it will be developed with governmental financing to a large extent.

For the coming year, at least, "defense construction" will largely take the place of the large-scale public work with which we have become familiar and in the main will be responsible for what Dodge Reports anticipate may be the largest amount of public construction on record. It seems probable that the volume of public housing will be far greater than the volume of private housing, even though the latter may be almost as great as in 1940. On the other hand, modernization of commercial buildings and construction of small new ones will probably reflect the increased merchandise sales that will result from the large volume of defense wages and salaries.

To a certain extent all this spells uncertainty for architects. The situation suggests that privately financed industrial buildings, housing for industrial workers, and operations incident to the reconditioning and construction of commercial buildings, should provide architects with their greatest immediate opportunities to carry on their independent

In asking Edwin Bergstrom to give architects a New Year's message on the state of the profession, the RECORD could hardly have chosen a more conscientious or currently better informed person. For months past he has been living in Washington, D. C., working indefatigably with members of the Defense Advisory Commission and planning-bureau executives in an earnest attempt to clarify and better the general position of the profession to which he belongs. His resulting wide contacts with officialdom, an extensive business experience as head of an important firm of architects, and his years of service as a director and ranking officer of the A.I.A. have earned him the right to speak with authority on the present status and future opportunities of architects. His message is a thoughtful, timely document that has a direct and forceful bearing on the personal plans and professional conduct of every architect in the country.

PROFESSIONAL SERVICE



practice while National Defense is still an acute problem. During this period private capital may be loath to undertake building enterprises; for it will probably consider that increased building cost and the certainty of increased taxes coupled with the uncertainty of returns will in combination hardly justify the risks of investment. Yet the profession *must*—and I believe it can—develop projects which will interest private capital if it does not wish to become necessarily dependent on governmental largess for its existence.

The field of the architect in private practice has been, and must be, that of planning projects and designing buildings financed with private capital. Upon their pre-eminent skill and experience in this field architects must now rely if they are to maintain their status as private practitioners. Governmental bureaus and corporate bureaus more and more are assuming the functions of the architectural profession, as they have so largely assumed those of other technical professions. Pressure of these bureaus to retain control over design of all sorts of structures—and of the site-planning inherent therein—is always increased during emergency periods such as that in which we now find ourselves. Such periods of pressure, particularly when they involve a comparative lack of private work, tend to accentuate the metamorphosis of private practitioners to the status of employees.

A widespread change in the status of architects is the *one* immediate and acute danger which today faces the architectural profession. *It must not happen!*

It seems certain to me that the role of architects in private practice will never be extinguished as long as our form of government permits the continuance of private industry and private initiative. Building projects in which design is important will necessarily always involve the services of independent professional architects. Private enterprises not engaged in continuous building operations cannot afford to maintain a designing bureau; and the architect in private practice will continue to find that field a large one.

But the profession may have to revise some elements of its service and offer new ones before it can successfully resist and validly eliminate competition of corporate designing bureaus. The excuse for the existence of such bureaus is that the buildings they create are repetitive in design wherever they are to be located, or that the structures must be planned particularly to house special processes and thus are too technical and complicated for architects to handle successfully.

We, as architects, know that no one is more competent than ourselves to plan structures which will contribute to the efficient development of these procedures and the handling of resultant products; provided we are thoroughly grounded in the production processes we are to house. But we also realize—and the public must be made to realize it also—that this competency applies as much to the design of simple

homes as to the development of hotels or complicated industrial or commercial enterprises.

Industrial buildings—a field in which design bureaus and the industrial constructing engineer are particularly conspicuous—can be handled most successfully by architects if they will develop the business efficiency and technical competency essential to the success of such enterprises. Perhaps because of laxity on our part the independent industrial designer and builder seems rapidly to be seizing opportunities in this field. But there is nothing these individuals can offer that the technically qualified architect could not give. And the architectural profession should not overlook the probability that the field of industrial building design will continue to be a most stable and active one for a long time to come.

None of us need be despondent because certain factors in our present economic and professional situation do not appear to be propitious. Architects will always be needed. They contribute the art of design to the buildings they plan, and they, of all members of the building industry, are the only ones fitted by natural ability and technical training to do so. They are good organizers of building operations and know good construction. They are not inclined to stint their services. I am convinced that the years to come will grant to architects the important place in America's development that their several abilities entitle them to enjoy.

In the years to come, however, the profession must offer much more to its clients than has seemed customarily required heretofore. It will need to have much more exact knowledge of technical processes, of financial procedures, of taxation effects, and of building costs than has been its wont. It must be ably versed in these subjects, for it will be, as it is now, in competition with other professions, and with builders who can discuss comparative costs and relative returns with sureness and appeal. Our profession will find it must deal with business and talk the language of business to solidify its own existence.

It can do all these things without surrendering any of its professional hallmarks. Mastery of design alone will not be sufficient to sustain an architect's professional independence. Mastery of the arts must be *in addition* to all the abilities that characterize the contractor, the constructing engineer, the speculative builder, and every other profession—abilities which enable them to operate as promoters, planners, designers, supervisors, and administrators.

It is not necessary to enter other fields of activity to do this. Real estate, contracting, and financing are fields that belong to others; and recognition of this fact, coupled with a basic understanding of their respective responsibilities, will light the way to true and effective collaboration to the advantage of project, owner, and collaborators alike. Collaboration is important to the architect both theoretically and practically. In the past it has proved its value; and in all phases of building will undoubtedly increase in years to come. One person cannot be pre-eminent or even competent in many fields; and a cordial collaboration of special talents will prove to be the answer to many of the profession's current problems.

Architects must now prepare to assume their increased future responsibilities. They must combine exactness of technical knowledge and of costs, the competency and efficiency of business with their native ability in design. Thus prepared, they will be able to bring together other technical professions with financiers, builders, and labor in a co-operative procedure for every project. Architects can then truly become Co-ordinating Administrators on whom alone owners will depend for consummation of their building projects.

The future holds every prospect favorable to the continuance and the enhanced standing and importance of the architectural profession, if each architect will make himself ready to give the increased services which our changing world requires and will grasp the opportunities which so abundantly lie ahead.

AMERICAN ARCHITECTURE: 1891-1941

PART I

The half-century elapsed since the first issue of ARCHITECTURAL RECORD appeared has been perhaps the most portentous in human history. Certainly, encompassed within this span, lie America's most important years. The beginning of this period saw the disappearance of one frontier — the buffalo retreating before the iron horse, the prairie sod before the gang plow. The end of this period sees the expanding conquest of another set of frontiers — those of science and technology. Between these two termini lies a revolution in habits of thought and action, with the routine of every field of human endeavor greatly, if not entirely, altered.

These two frontiers inevitably had their architectural parallels. The architects of 1891 were, in many respects, more confident than those of today. The classic revival had just burst upon the scene, offering a rationalized system of ornament which one RECORD correspondent "had no hesitation in calling one of the greatest labor-saving inventions of the age . . . Having laid out his building and designated the style, the architect can now take a trip to Europe and leave the detail to the boys."

This optimism went so far in 1897 as to produce the Classic Design and Detail Co., Inc., (Capital \$1,000,000.00). In a prospectus called "You Get The Job, We Do The Rest," this organization pointed out that it was "not only no longer necessary for an architect to design anything . . . but in the detail of architectural work there is no longer any room for designers." Hence, the C. D. & D. Co. was setting up a central plan factory where, "from a small scale pencil sketch of plan and elevation, we work out a complete set of drawings and . . . reproductions of entire buildings (can be) reduced, enlarged or modified as desired."

Such easy optimism was not peculiar to the architecture of the period; it cut across most aspects of American life. But today it appears more fruitful to investigate not so much *what* has happened since that time as *why*. And it should by now be clear that these fifty years can be understood only in terms of the impact of science and technology upon society in general and architecture in particular. How explain the appearance of the skyscraper on the scene except in terms of the cables and motors which made vertical transportation a reality? How understand the broadcasting studio's rapid rise without a corollary understanding of the radio? How design a hospital in ignorance of modern surgery?

To mirror such developments in science and technology and anticipate their architectural effects, has long been the aim of the RECORD. But to summarize the developments of this amazing fifty years is no simple task. So to guarantee a clear perspective we have asked a group of scientists under the chairmanship of Dr. F. G. Fassett, Jr., Editor of the Massachusetts Institute of Technology's *Review*, to survey for us the major contributions of their respective fields to the *means* of building. The second portion of their study — dealing with the effect of science on the *aims* of building — will appear in February.

ARCHITECTURE MADE EASY

NOTICE

Architects everywhere who are interested in the latest and best of the new designs of the "Classic Design and Detail Co." will find that this company has been organized to save the architect the trouble of designing the details of his buildings. The "Classic Design and Detail Co." offers to the architect a complete set of drawings and reproductions of entire buildings (can be) reduced, enlarged or modified as desired. The architect can now take a trip to Europe and leave the detail to the boys.

PROSPECTUS CLASSIC DESIGN & DETAIL CO.

TO THE ARCHITECT: The "Classic Design and Detail Co." is a new organization that has been organized to save the architect the trouble of designing the details of his buildings. The "Classic Design and Detail Co." offers to the architect a complete set of drawings and reproductions of entire buildings (can be) reduced, enlarged or modified as desired. The architect can now take a trip to Europe and leave the detail to the boys.



Drawings are by William E. Haible and B. Leonard Krause, Research Assistants, Bemis Foundation.

"— TO HAVE DEFENDED LOUIS SULLIVAN IN A GENTLE WAY OVER A GENTLE MADEIRA AT THE CLUB —"

CONTRIBUTIONS OF SCIENCE AND TECHNOLOGY TO BUILDING

A SYMPOSIUM BY

LAWRENCE B. ANDERSON
Associate Professor of Architectural Design

CHARLES H. BLAKE
Associate Professor of Zoology

JOHN E. BURCHARD
Director, Albert Farwell Bemis Foundation; Editorial Associate, The Technology Review

FREDERICK G. FASSETT, JR.
Editor, The Technology Review
Associate Professor of English

ERNEST N. GELOTTE
Assistant Professor of Construction

EDWIN R. GILLILAND
Associate Professor of Chemical Engineering

JAMES HOLT
Associate Professor of Mechanical Engineering

PARRY MOON
Associate Professor of Electrical Engineering

PHILIP M. MORSE
Professor of Physics; Editorial Associate, The Technology Review

JOHN WULFF
Associate Professor of Physical Metallurgy

SCIENTIFIC AND ENGINEERING achievements of the last half century have influenced the architecture of that period through far-reaching *general* effects on all society and through *detailed* effects applying specially to the technics of building and of satisfying human needs within the building. Of the two groups, the first—chiefly those induced by the internal combustion motor and the applications of electronics—is the more significant. But these can best be appreciated after the more immediate field has been surveyed; hence we may profitably plunge at once into consideration of the detail.

It may help our orientation if, retaining our knowledge of what has ensued, we step back into the shoes of a mutton-chopped, spatted, clubman architect who in the year 1890 reposed in his comfortable chair, comfortably won. Our man we may imagine to have reached the age of fifty, and to have made the traditional travels and measured drawings abroad. He may be assumed to have been a man of culture and of education, though not of much technical education; even to have taken the dangerously forward-looking view of defending Louis Sullivan in a gentle way over a gentle madeira at the club; to have been somewhat interested in science.

Let us explore this man's mind and his prospects, to see how either was to be concerned over the remaining thirty years of his life (he died ripely in 1920) with what was happening or what he might expect could happen to building.

WE SHOULD PAINT an untrue picture were we to look at this man purely as architect, pundit of style, and arbiter of equipment. He, too, was a man and lived in his day. He was not of a stupid generation, however complacent it may have been. Surely enough has been written about the decade to set the general environmental picture, and we need adduce no specific historical events, no descriptions of the parlor, to set the stage for a direct attack on what might be in the mind of this man as he observed those historical events and sat in that parlor.

Such a man was not very much interested in scientists and their announced theories, though he doubtless had some interest in inventors. On this January 1, 1891, he would probably not have heard of Hertz or have known that the latter had discovered radio waves three years earlier; nor have known of Elihu Thomson and his proposal in 1889 that the waves be used for communication. Even ten years later when Fessenden telephoned by the use of these waves it is doubtful that our architect heard about it, though he may have been mildly interested in Fessenden's first broadcast on Christmas Eve, 1906. What might have been of more interest was the adventure of Clement Ader who in 1890 made a sustained flight in the air of 50 meters, but this must have seemed very silly to our man and so too the appropriation for five years' research made for Ader by the French Government. Kitty Hawk (1903) was still to come, and the flight on that windswept strand probably never impressed him.

It would scarcely have been of interest to him to know that Dr. Carlos Finlay was practising medicine in Havana even if he had been able to foresee the later relations between Finlay and Walter Reed. The discovery of X-rays by Roentgen in 1895 would not have stirred his placid contemplation of the Romanesque nor would the fact that in that year young Rutherford went to work with Sir J. J. Thomson. The Bateson experiments of 1900 and before which brought the earlier known and just rediscovered Mendelism to prominence would also have seemed of no importance, even if understood. That architecture had a strong social reason for being was scarcely a part of this man's philosophy.

Being of a progressive turn of mind, he would have been more interested in some

TO BUILDING DESIGN: 1891-1941

of the applications of earlier science which were beginning to prove sometimes useful. Communication seemed to him one of those fields in which too much was being accomplished. Typewriters, for example, were known and some of his friends had tried to use them in offices. Photographic film had been on the market three years: a dictaphone—a sort of phonograph for two—had appeared in 1890: and in the year he was facing there was to be the first commercial color photography. In 1892 the moving picture came on the scene, based on inventions which were pre-Civil War, but it was not until 1905 that his son-in-law took him to a nickelodeon. Disc records appeared in 1894 to cap a remarkable commercial development of some six years. By 1902 our man was accustomed to using the telegraph. In 1920, the very year our architect died, the first commercial radio broadcast went out over station KDKA, Westinghouse, in Pittsburgh. He never saw a sound picture or a radio photograph. Transportation, too, was changing, but at this very moment less dramatically. By 1900, the trackage of railway lines for the United States was virtually all laid and in that year there were just 8,000 automobiles. But by 1930 there were 26,000,000 of these vehicles with the dramatic expansion coming after development of the multiple disc clutch in 1907 and drawing on railroad steel-fabrication techniques for development of chassis. The auto itself, of course, was known in the year this story begins.

HIS PROFESSIONAL ATTITUDE was conditioned not by his attitude towards society, which was one of indifference, but primarily by what was available to him in the way of materials, structural methods, and amenities. By 1890, many of the

THE ARCHITECT "is likely to be far more severely blamed for a misplaced bell-button, or an inconvenient elevator, or for dark offices . . . than for ill-studied and inartistic treatment of the architectural forms . . ."

"Modern processes of building, moreover, as exemplified in these monstrous many-windowed stacks of offices still further hamper the free expression of artistic ideas. Iron and steel now form a large part of the framework of every important building, and the development of constructive forms in metal has naturally proceeded along the lines of engineering rather than of high art."

October-December 1891

principal discoveries and inventions had indeed been made, but few of them were ready for use. The manufacture of aluminum by electrolysis was developed in 1886, but the metal was costly and almost never appeared in architecture. In 1890, if the architect bought steel, he almost certainly obtained it (86%) from a Bessemer mill. Forty-five years later, only one-tenth as much was made by the Bessemer process, while the open-hearth mills had increased their run from 12% of all to 90%. Perhaps more significant was the domination of iron. In very old times non-ferrous metals had been those of the greatest importance. But our man lived in an iron age. In the period 1884-1924, pig-iron production bore a ratio of 40:1 to non-ferrous production. Improvements in non-ferrous metallurgy, however, have reduced that proportion since 1924 to 14:1, a significant change. Finally, our architect never saw Monel metal, chrome nickel steel, structural aluminum alloys, plastics, wall-board, rubber anti-oxidants, or cellulose varnishes. Nor could he enjoy the use of the industrial X-ray.


With skeletal construction he was somewhat familiar though he preferred load-bearing walls. Up to 1884, he indeed had been one of those who valiantly jousted against the admission of the skeletal form of building, but Le Baron Jenny's Home Insurance Building (1885) and Bradford Lee Gilbert's Tower Building in New York (1889) had somewhat changed his mind. Though Roebling's ropes were being used elsewhere, they had not yet come to make the elevator the catalyst by which buildings could get really high. By 1901, the limits of framed buildings were quite well determined and Joseph K. Frietag, a prominent engineer, could state, "The Park Row Building is the highest office building ever erected and it is doubtful if it will ever be found desirable or profitable to erect other buildings as high as this one." (Park Row, 390 feet; Empire State, 1250 feet).

For concrete the architect also had scant use. Modern methods of making Portland cement were scarcely supplied before 1892 and to the day of his death he preferred brick masonry, stereotomy, and the principles of heavy mill construction to those of frames of steel and ferro-concrete. Of acoustical science he knew nothing. He knew that some rooms were good for some purposes because of their sound effects, and when control of sound was important (and this was not often) he tried to copy those rooms which had worked well. He rarely, if ever, had consciously had to struggle against unduly high sound levels. He paid little attention to ventilation though he was concerned (unnecessarily, it now appears) with carbon dioxide content. Heating systems were as troublesome as they are now, but for different reasons. In his later years he had some difficulty providing enough electric circuits, for how was he to anticipate what would happen following the development of the hot electric coil (flatiron) in 1892? The electric washing machine (1905), electric refrigerator (1917), and later, the complete electrification of the house down to the shaving apparatus, were not things with which he ever seriously had to cope. Gentlemen for whom he worked did not demand all this in their residences. Their main preoccupation was that the bathtub be large enough.

Lighting did interest him somewhat. Edison's first incandescent lamp had become available in 1879, the essential central generating station in 1882. The acetylene light (1892) was perhaps the most intense source available at this time. The gas-filled electric lamp did not come till 1913, and our man died before the appearance of the inside-frosted lamp (1925), though he did see some printing establishments using the mercury vapor lamp developed in 1904-1906.

As to electric power, how could he foresee how ubiquitous it would become? In 1900, the 5-horsepower motor weighed over 700 pounds and took up nearly 20,000 cubic inches of space; now it weighs under 200 pounds and occupies less than 4,400 cubic inches.

On the sanitary side our architect lived a dangerous life. Though canning had been known since Napoleonic days, it was not until 1903 that the tin can was made relatively safe. His family always dreaded tinned goods. He did not expect that his local water could be anything but hard; chlorination of water did not come in until 1908. If he had a headache he was free from the benefit of aspirin (1899) or barbitol derivatives (1903). He would have regarded the irradiation of food (1921-1925) as scandalous had he lived to see it; but he readily tolerated the refining of food then going on, which was later to lead to the necessity for irradiation.



"— THAT THE BATHTUB SHOULD BE LARGE ENOUGH"

I
wan
chro
date
R
tar
othe
elem
elem
N
poss
the
hole
of w
B
map
buil
it (a

TH

M
so fr
expe
devel
not s
gave
than
Sim
made
are n
their
in ver
In
prefa
Mill C
very c
by 17
another
manul
egg st
supply
effect
increa
of the
The
of cem
had de
tions o
Americ

JAN

IT WOULD BE CONVENIENT if we could trace scientific and engineering developments of the past half century as though each contributing event were a separate stream, wandering, perhaps, but behaving inevitably as a tributary. With the forks given due chronological marking, we should finally arrive at the broad river of building whose date is today. But this analogy simply will not apply.

Rather, the work of science in this period ought to be compared to a wood—a tangle of unusual trees with roots which descend and re-emerge joined to those of other trees; with branches which anastomose; so that not only is it never clear which elements furnish the nutriment and which consume, but it is also never clear which elements are those that first arose from the germinated seed.

Nonetheless a closer view is essential. Though the roots cannot be isolated it is possible to make a sort of plot by digging now here, now there, and to pluck from the digging this or that root which one may follow a little way. Thus if enough holes are dug with reasonable spacing over the forest floor, we may gain some idea of what lies beneath.

But the holes must be dug with some plan, and it hence becomes necessary to map ordinates and abscissae for the digging. Let us choose simple axes: one for the building envelope (materials, structure), one for the biological requirements within it (atmosphere, light, sound, sanitation).

THE ENVELOPE: 1. Materials

MODERN BUILDINGS are distinguished by the combination of great scale with lightness of structure, and this fact reveals yet another of the paradoxes which so freely interlard this story: Steel, the material which above all might have been expected to create the release from the weight of older buildings, was already fully developed for structural purposes. But reinforced concrete, the material which was not so well developed, and which was destined to be the material of the half century—gave at its inception promise of return towards the heavy structures of Rome rather than towards arrangements which would rival the structural delicacy of the Gothic.

Since 1925 the addition of 4% to 5% of alloy ingredients to structural steels has made for stronger steel per unit weight. Though steels of vastly better properties are made for other purposes, and though from time to time some enthusiast urges their use for building, the economics of the manufacture militates against it except in very special situations.

In the development of ordinary steel plates used in regular or more often in prefabricated buildings, the continuous strip mill (J. B. Tytus of American Rolling Mill Company, November, 1926) is noteworthy. Rolling of plate itself was of course very old. Lead sheets were rolled by hand as early as 1615 and sheet iron at least by 1728. But the continuous rolling machine with its tremendous capacity was another matter. Whether this was a product of the demand of the automobile manufacturer, or whether its development led to more use, is another of the hen-and-egg stories. Competition forced the building of more mills than were needed to supply the demand, and the battle of strip has been one which is bound to have effect on the building industry sooner or later. Among other things, it notably increased, for a time anyway, the interest of the steel manufacturer in the possibilities of the prefabricated house.

The introduction of reinforced concrete naturally led to interest in the composition of cement and the chemistry of the gel-reaction. Johnston at Swanscombe, in England, had developed fine grinding, clinkering heat, and other technical and chemical perfections of cement as early as 1845; but the true beginning of concrete structures in America may be set at 1892 when modern developments of making Portland cement

IN APRIL-JUNE 1893 THE ARCHITECTURAL RECORD carried an analysis of the cost of brick bearing walls vs. steel framed walls which showed that steel framing was a very expensive luxury which increased dramatically in cost as the height reached towards the towering elevation of 20 stories.

were introduced. Of even greater interest are the careful study of water ratios (Duff Abrams) and of aggregates as to size, shape, and proportion, including the work of John J. Earley and the interesting and newer developments of vibration and of dewatering by vacuum so that today it is possible actually to design a cement mix to produce expected properties.


THE PERIOD has witnessed a slow appreciation by the producers of older materials that times have changed. The transition from wall-bearing to framed structures has required the production of light and durable facing materials. Stone producers, realizing this, have sought with some success to cut their product with more delicacy, being aided by metallurgy through the use of steel shot in grinding. Advances in manufacturing processes have resulted in an increasing number of improved clay products, of which brick is still (at least quantitatively) the leader. Wood producers have given much attention to correction of the defects of a material which otherwise has magnificent properties. Understanding and control of insect destruction has greatly advanced. Of distinct interest are the stressed-skin structures of laminated wood; and the plasticizing of wood with urea.

Another of the ancient materials, glass, has been the subject of much activity in the production of special-purpose glasses of many kinds, infrared-absorbing, ultraviolet-transmitting, tempered plate. Other uses of glass, such as the beautiful fibers which adorn equally a damask of silica or an insulating wool bat, have played their role. But perhaps the principal development of glass technology is in the manufacturing process which has made large sheets available at reasonable prices; the effect of the big pane of glass on contemporary architecture is obvious even to him who runs as he reads. The use of glass as an opaque non-deteriorating exterior surface material should have an important future.

Metals have entered building dramatically in other than structural ways. Window sash, frames, laths, of steel or aluminum, are well known. They were practically unheard of in 1890. Great advances have been made in the manufacture of pipes and fittings of copper, brass, bronze, lead, and steel, and by developments in shaping and forming these metals.

Corrosion has also been subjected to exhaustive research. The patent to Ambrose Monell in 1906 for the reduction of ore to an alloy containing 70% nickel and 30% copper; the chrome nickel stainless steel developments of Strauss and Maurer in 1910-1914; the straight chromium stainless steels of Brearly about the same time; the substitution of chrome plating for nickel plating through the work of Liebreich (1921) and Fink (1926); these are the landmarks.

One of the great metals of the period has been aluminum. The Hall and Heroult patents for its extraction from the ore were known before 1890, but aluminum could not come into its own until great sources of electric power were available. The price of sheets and castings of aluminum came down to a reasonable level, therefore, only after 1900. In 1911, a paper by Wilm in Germany on the aging of aluminum alloys



CAST IRON was hailed by an early **RECORD** as the material par excellence for such elements as the elaborate stairway at right.

suggested their structural use. After this paper, the application of aluminum alloys to many structural parts in and out of building was greatly advanced.

Two other developments of aluminum may be added. Aluminum pigments, processes for the manufacture of which were patented by another Hall and the Hametag organization in Germany, materially changed the technology of paints. The use of aluminum foil was made possible by the development of special rolling mills, yet the introduction of the material for insulation may possibly be attributed to Schmidt (1925) who, from the older reflectivity measurements of Rubens, concluded that it should be extremely efficient.

Other metallic progress includes the development of thin copper sheets through the process of electro-deposition and the development of lead pigment in metallic form to parallel the development of aluminum pigment. It is probable that despite the spectacular nature of these developments in metallurgy as directly applied to building, the greater contributions would be found only by tracing a circuitous path. Reflection might suggest to the reader the indirect impact which may have been felt by building through the development of high-conductivity copper; of contact materials, two million embodiments of which are employed in a central telephone station; of thermostat metals and alloys; and of magnetic alloys and related products.

Finally, one cannot ignore in any treatment of metal technology the growth of welding. So long as welding is employed in building operations primarily only to reduce the noise incident to riveting, it will not serve in its full role. Its real implication is that it brings to steel the advantage of continuity of structure which concrete has always had; and in this advantage the potentials are enormous.

ONE OF THE MOST spectacular developments of the period has occurred in synthetic organic chemistry and especially in the chemistry of the resins generally referred to as plastics. This entire industry may be said to have developed since 1890. Baekeland in 1909 completed processes for making a synthetic resin of phenol and formaldehyde. Since then, hundreds of other resins and plastics have been developed, some thermosetting, some thermoplastic, many with special properties which make them advantageous for certain uses but none with a wider versatility than those of the phenol-formaldehyde type.

The resins appear in small obvious ways in buildings: as insulating materials in electrical equipment, as adhesives in plywood, as laminated counter tops. But their principal use in building is unobtrusive. Gradually they and synthetic esters have been incorporated into paints until today few are blended without the addition of any synthetic resin. In the last fifteen years, resins have been developed as substitutes for the erratic natural resins, even the best of the copals, damars, and shellacs having suffered from this competition. A much wider choice of colors is available in modern paints because in 1890 most pigments were inorganic while today a large number of the coloring materials are derived from synthetic organic dyes.


Wallboards, too, are largely a development of the last twenty years though one special type, plywood, was known to the Egyptians. Our improvement on this old product has been made possible through the development of synthetic-resin binders. No one who has followed the course of domestic architecture of the last ten years can have failed to appreciate how this giant, plywood, has grown. Because the earlier casein-bonded plywoods were by no means popular with the architects on the basis of performance, a combination of efforts at prefabrication, need for economy, and a new technique of manufacture was needed to bring about this growth. The other types of wallboards, synthesized in large part from vegetable fiber bound with gypsum plaster and encased in paper, or of asbestos fiber bound with Portland cement, have been improved in properties.

All told, the architect of today is beset by an embarrassment of riches in materials. He must now have a far more specialized knowledge of the old materials to cope with their new uses; and of the new materials he can hazard no successful guess without a background of fundamental chemistry and physics which has in the past been unnecessary. The problem of selection between the claims of existing materials is no slight one, and not the least of the effects upon the architect which the fifty years have wrought.

"OF BRONZE there are two kinds, the solid cast bronze, and the thin sheet bronze, spun bronze it is called, the first very good and very costly, the second not good for much as they are easily dented by accidental knocks in moving furniture, but much less expensive than the solid. Recently spun bronze has been made, filled up inside with typemetal or something of the sort which I should think might be a good thing.

"There is, too, in the market a gaudy material called electro-plate."

April-June 1894



HE PREFERRED MASONRY,
STEREOTOMY... AND HEAVY
MILL CONSTRUCTION — "

THE ENVELOPE: 2. Structural Analysis

THE EIFFEL TOWER (1889) had set the pattern for quite high structures. The Crystal Palace (1851) with its million square feet of glass had had something to say about large spans with light members. Structural analysis itself needed little modification in order to make the high building possible.

That this was so was due to a very great activity in the century preceding 1890. Although structural engineering is a very old *practical art*, it is in fact a very new *science*.

Beginning with Galileo's inquiry in 1638 into the strength of cantilever, structural analysis benefited by a series of brilliant theorists—Hooke, Mariotte, Varignon, Bernoulli, Euler, Coulomb. In the period 1776-1820 the importance of tests began to be realized and the names of Girard and Young are landmarks; while only slightly later the work of Navier, Cauchy, Poisson, developed the theory of elasticity. Even the work theories of Chapeyron and Saint-Venant were known; as was the work of Rankine on earth pressures; of Ritter on sections; and of Mohr in graphic analysis; while the studies of Müller-Breslau were well begun. The modern theory of statically indeterminate structures had also a foundation of good groundwork by the beginning of our period.

Thus little was necessary from science to permit the analysis of pin-connected steel frames such as were prevalent in the time and, so far as the theoretical design was the only question, to permit the construction of such buildings to great height. Though fundamental changes have been made in some materials, the structural steel of the day was ready to be carried aloft. Yet other contributions were needed to make the high building a reality. Without the metallurgy of the cable and without other work in physics, the high-speed elevator could not exist and without it the high building was impossible. Nor could there be even an imaginary need for such a building until applications of science to transport and communication permitted great congestions of working populations. Development of rolling mills and the standard steel section contributed largely to making such buildings economically possible.

THE PRINCIPAL development of the period has been, then, in the analysis of indeterminate structures, and, so far as building is concerned, this fundamentally marches parallel with the development of structures of reinforced concrete (though welded steel buildings, a more recent development, must rely on the same reasoning).

In 1906, C. A. P. Turner of Minneapolis devised the flat slab type of floor, and the mushroom floor was a new thing to be compared with the floors of the more familiar wood and steel structures. It was inevitable in this rapid expansion that construction should often be in advance of theory, as was notably true in the case of flat slab construction. Since this introduction, several important methods of analysis have been developed, such as the slope deflection method of George Maney about 1915 and its offshoots; moment distribution by Hardy Cross; mechanical analysis by Beggs; elastic analysis by Westergaard; and most recently the theory of limit design as advanced by Vanden Broek and others.

The advantage of flat slab construction was that it gave the architect a clear ceiling with no obstruction to light and ventilation, though this advantage was not always utilized to the utmost. More recently, Molke and Kalinka have discussed the use of extremely thin shells for domes and other wide spans. The dome at St. Peter's (16th century) weighs 10,000 metric tons for a span of about 40 meters, Breslau weighs 6,340 metric tons for a span of about 65 meters, a modern Zeiss-Dywidag dome might weigh 5,000 metric tons for a span of 100 meters.

With these increasing heights and with increasing spans, the problem of loads other than those imposed directly by gravity (wind loads, for example) became more significant. It was through advanced structural analysis that their effect could be studied; then physics made it possible to study strain distributions in complicated sections through the use of photo-elasticity and to study fatigue due to vibrations. A completely new concept as to foundations came through the work on soil mechanics initiated by Terzaghi. Another important development is that of the theory of similitudes and the application of the theory to model analysis. Though model analysis is used most frequently on structures other than buildings (dams, bridges, ships, aircraft), there is no reason why it cannot be applied wherever the problem is sufficiently difficult; such difficulties would normally arise only when there is a distinct departure from tradition in the framework of the building, when the scale is one which far exceeds tradition, or when the loads expected are most unusual.

FINALLY, the designers of aircraft and other mechanical engineers, whose primary concern is not with structure, have on the whole pushed the boundary of analysis much farther than have the structural engineers. It can be argued that their principles offer scant factors of safety, sufficient for the structures with which they deal but inexcusable in structures to which weight is by no means the chief detriment. Yet it seems reasonable to suppose that in time the influence of this pioneering analysis will be felt in building design. It might, for example, today illumine the question of wind loads.

On the whole, the full vigor of the possibilities in modern structural analysis has not been exerted on buildings which have had architectural supervision. There has been a timidity in the use of advanced structures which perhaps stems partly from the old idea that the competent architect could "feel" the proper design, as indeed he could for a load-bearing masonry wall, and a centered stone arch; and partly from the idea that the engineer is to come in and make a building stand up after the plan and especially the façade have been well worked out. Since the advanced engineering forms dictate to some extent the façade and these along very different lines from the rectangularity which remains to man only in his buildings (and which never appears in nature), such an attitude towards engineering would in itself defeat the adoption of these newer methods.

It is no surprise, then, that outstanding examples of the application of modern engineering analysis are to be found principally in buildings where the engineer has been important; and indeed by and large in greater profusion in Europe where the aesthetic sense of the engineer is held in far greater respect by his fellow-builders, the architects, than is yet true in America.

Evidently some building types gain more from the new engineering than can others. Principal achievements already noted are in amusement places, stadia, theaters, arenas; and, to a less degree, in the market, the museum, the work space. Other types can also benefit from the flexibility which is possible only when these structural methods are used in the utmost.

"SHOULD ENAMELED terra cotta prove to be what is claimed for it, if it stands the test of Chicago's severe winters and changeable climate, there can be no possible doubt but what as a material for exterior construction it will be largely used in such cities as are afflicted with a smoky, sooty atmosphere. The idea of being able to wash your building and have it as fresh and clean as it was the day it was put up, must undoubtedly attract people to the use of this material."

January-March 1895



"— THE STOVE REMAINED
THE MOST COMMON DEVICE —"

BIOLOGICAL REQUIREMENTS: 1. The Atmosphere

THOUGH NO ONE would pretend that buildings of 1890 were entirely comfortable in the winter or the summer, it is remarkable how few heating devices of today were unknown then. In 1890, for example, all the types of domestic heating systems were in general use, though the stove remained the most common domestic device and only more expensive homes enjoyed central plants. Controls were in general manual and over- and under-heating were common. Engineering data were largely lacking and design was based almost entirely on experience.

Consider controls, which we are likely to regard as a principal achievement of the past few years. The first low-voltage electric thermostat (bi-metallic) had appeared in 1885; the gradual-acting vapor disc thermostat (forerunner of heating and ventilating controls for large buildings) was invented by William Penn Powers in 1889. Perhaps the single important exception is the mercury tube switch invented in 1920 which made possible the direct control of high voltage equipment such as motors, solenoids, and the like. Since the domestic oil burner, the domestic gas burner, the domestic refrigerator, automatic heating systems, forced ventilating systems, and air-conditioning systems have all been made possible by the simultaneous development of suitable controls, it is evident that a substantial foundation for progress in this direction had already been established.

As in so many other developments, the pioneering work had already been done and a daring architect could experiment with the results much as a man of today might experiment with ultra high frequencies. The accomplishment of the period lay rather in an incredible degree of refinement to make the devices foolproof plus

"**STEAM HEAT** with radiators in the rooms is little used for dwellings, for country houses hardly at all. It seems to have more objectionable points and fewer advantages than any other system."

April-June 1894

the customary change in production techniques, which made it a matter of course that an architect would use them rather than a seven days' wonder that he should dare to try.

Of the principal methods of heating, all were known. Steam, reaching a peak of popularity some years back, has declined in popularity as a result of more public knowledge of the hygiene of heating. Modulating vapor steam systems were available commercially by 1902. Perhaps the outstanding new result is the development, about 1925, of orifice control of steam supply to radiators, leading to many other controls applied to other heating methods as well. The net result is that the heat may be supplied in proportion to heat loss with the outside temperature as the main control, the inside temperature as a modifying control, and a time control as well. All of this finds its principal application in large buildings where substantial economies may be realized.

A practical demonstration of the use of oil in heating was made at the Chicago Exposition in 1892 and it developed rapidly for industrial heating purposes, though the domestic oil burner was not introduced generally until 1919. Metallurgy played a role in the development as heat-resisting steels were needed for some parts; but the most important factors were the remote scientific efforts which centered around the processes of refining petroleum. The use of gas as a domestic heating fuel may be laid to corresponding or even more purely commercial forces. On the other hand, the introduction of silica gel for air conditioning in 1924 made gas the best fuel for reactivation and the advent of the Platen and Munters system of refrigeration in 1922 also made gas the most economical fuel as a source of heat for this refrigeration.

With the single exception of radiant heating, recent interest in which is a result of physiological rather than heat-engineering research, hot-water systems are much the same today as they were in 1890.

Hot-air heating, well known in 1890, later decreased in popularity until the National Warm Air Heating and Ventilating Furnace Research began under Dr. A. C. Willard and A. P. Kratz (at the University of Illinois). The research, which still continues, put the system on a rational basis. For this reason, plus the fact that hot air is best adapted to residence air conditioning, it has rapidly regained popularity since the public became interested in air conditioning. Important contributions to the technic were the addition of forced circulation and air filters about 1924.

PREVIOUS TO 1911, air conditioning was practised generally only in certain types of industry, particularly in textile manufacture where humidification was essential. Previous to 1906, systems were crude and uncontrolled. Stuart W. Cramer, who in 1906 developed a control based on the wet and dry bulb, first introduced to the textile industry in 1907, paved the way toward modern practice.

In 1911 Willis H. Carrier presented a paper to the American Society of Mechanical Engineers setting forth the basic psychrometric data and principles of air conditioning. By 1920, large installations for public comfort had made their appearance. By 1931, unit equipment for small users had come into existence.

Perhaps more progress has been made in cooling buildings than in heating them. Though the Greeks and the Romans had used natural ice and snow for refrigeration, in our year 1890 a warm winter produced a great ice shortage and stimulated the development of artificial ice which up to that time had been considered unhealthful.

But the first mechanical refrigeration had been produced by Dr. William Cullen in 1755; between that time and 1890, aided particularly by Faraday's discoveries of liquefaction and condensation, many of the important developments had been made.

Small mechanical refrigerating apparatus for cooling butcher boxes and household refrigerators came into use during the first World War, but it was not until 1926 that much progress was made. Over 210,000 units were sold in that year. Since that time, the growth has been phenomenal.

Chief progress in heating has, however, been in the increased understanding of physiological needs rather than in devices for fulfilling these needs.

Up to the introduction of forced-circulation hot-air furnaces, for example, the circulation of air in buildings depended either on separate blower systems which

IMPORTANT DEVELOPMENTS in hot water and steam heating may be summarized as follows:

1. Research to put design of system on a rational basis, led by Dr. E. F. Giesecke of Texas A. and M. Experiment Station about 1930.
2. Use of orifices for balancing systems.
3. Forced circulation for small systems which had been used only on large systems prior to 1890.
4. Use of copper tubing in place of iron pipe about 1932 but not yet general.
5. Panel or radiant heating by means of hot-water coils buried in the plaster ceiling or concrete floors. Used for many years in Europe, this has been accepted only slowly by American engineers so that only a few installations have been made in the United States. The interest is increasing.

WHILE MOST OF THE EQUIPMENT for air conditioning was available in 1911, some of the important developments since that time have been:

1. Basic research data on what constitutes comfort and to some extent health by air conditioning—American Society of Heating and Ventilating Engineers and others, 1920 to date.
2. Development of controls for air-conditioning systems for the most part using known basic elements.
3. Development of Freon as a safe refrigerant about 1931 by Kenetic Chemicals, Inc.
4. Development of non-ferrous fin tube surface for blast heating about 1922 and its later application to cooling installations.
5. Silica gel systems for dehumidification about 1924 and later such substances as calcium chloride and lithium chloride.

OUTSTANDING developments in refrigeration have been:

1. Hermetic sealing first used by Johns-Manville on the Audiffren Singrum commercial unit about 1919, and the first household unit by General Electric Company in 1926.
2. Freon as a safe non-toxic, non-corrosive refrigerant about 1931.
3. Improvements to control humidity conditions in boxes about three years ago.
4. The invention by Von Platen and Munters in 1922 of a small hermetically sealed absorption refrigeration unit making household gas refrigeration commercially possible.
5. First commercial use of CO₂ (dry ice) in 1905 in the medical field; about 1925 it was used commercially for refrigeration of ice cream.

circulated cool air or on gravity. The former resulted in local cool drafts and the latter in local hot drafts. The forced-circulation types with thermostatic controls gave good distribution of reasonably warm air. When they are provided with some type of air filter, even a dry cloth tent, there is reduced circulation of dust. The replacement of coal as a fuel by gas or oil has decreased the available dust in houses. Gravity hot-air furnaces commonly draw air continuously from the outside near the ground level or from the cellar, which is just as bad. The earlier types of central heating resulted in very dry buildings, despite various ineffective attempts to mitigate the condition. Recent warm-air systems, for example, make provision for evaporation of water within the furnace where the temperature is high, but to avoid the fogging of windows the humidity is not raised to a really comfortable level.

In 1923, Yaglou pointed out the relation of temperature, relative humidity, and air movement, giving what is called the effective temperature. Most persons are comfortable only between 30% and 70% relative humidity. Hence, in winter in very dry buildings no degree of heat, even 80° or higher, is really comfortable and in summer no cooling will quite succeed if the water is left in the air and the relative humidity rises nearly to saturation.



LAMP SHADES CUT OUT FOR NON-EXISTENT SMOKE AND DRIP PANS FOR NON-EXISTENT WAX.

BIOLOGICAL REQUIREMENTS: 2. Light

THE SUN on a bright day in the temperate zones produces illumination intensity of 10,000 lumens a square foot. On a cloudy day the intensity may be 1,000. One of the principal developments in the science of artificial illumination has been that which has permitted steadily increasing values of illumination. Unlike the situation in heating, practically nothing which now governs artificial illumination was available, even by inference, in 1890.

We might compare the kerosene lamp of 1870 (0.3 lumens per watt) with the

first Edison lamp of 1879 (1.4 lumens per watt, improved by 1890 to 3 lumens per watt), with the fluorescent lamp of today (40 lumens per watt).

The years since 1890 have witnessed a long series of developments in light sources with a steadily increasing amount of light per unit of electric energy for each. The landmarks on this road are perhaps the production of drawn tungsten wire by William D. Coolidge in 1911; the later addition by him and others of thoria and like compounds to control the grain size and thus make possible a non-sagging filament; the development by Irving Langmuir in 1913 of the gas-filled tungsten lamp; and the development of the fluorescent lamp in 1938. Fluorescent lamp development was directed principally to finding suitable phosphors to fluoresce under the ultraviolet radiation. It is notable that since these phosphors made many colors possible, the lamps first caught on in color, and white and daylight lamps were supplied merely to complete the range. However, the demand now is for the daylight and the white lamp. The increased light output of the fluorescent lamp for the same amount of energy is quite comparable with the revolution of 1911 when the tungsten lamp was introduced. Moreover, the new lamp offers for the first time an approximate daylight quality of artificial light; a light also comparable in coldness with that of the much publicized firefly.

Developments in fixtures have scarcely kept pace. To be sure, in 1890 the unadorned gas jet and the unshaded incandescent lamp were the rule. Subsequent periods went to style rather than performance in the design of luminaires and tended clearly to follow tradition set by the candle and the oil lamp. Even today lampshades are carefully cut out for the passage of non-existent smoke and have drip pans to catch non-existent wax.

Since the electric light does not require provision for removal of smoke, can be enclosed in air-tight compartments, and is safely portable because it introduces a negligible fire hazard, the frank realization of these characteristics has resulted in notable installations where the lighting equipment is an integral part of the building structure and the illumination is adequate but unobtrusive.

NO REPORT on the development of building lighting would be complete without mention of the revolutionary change that has taken place in our ideas on lighting requirements. A realization has gradually grown up that sufficient light must be provided so that the given visual task can be performed quickly and easily, and glare and shadows must be minimized. The Illuminating Engineering Society has worked since 1907 in the formulation of rules for the lighting of offices, factories, and schools. Following the I.E.S. recommendation, several states have adopted lighting codes to protect workers from unsatisfactory lighting conditions. The Pennsylvania Code went into effect in 1916. New York, New Jersey, and Wisconsin followed in 1918, and in 1931 thirteen states had specified minimum standards for lighting in factories and other work places.

In 1890, one lumen per square foot (1 "foot-candle") was considered rather good. Today some states require that for fine work at least 8 lumens per square foot be provided, and recommended values are even higher. Many modern drafting rooms, offices, and machine shops provide 40 or 50 lumens per square foot over the entire room, and values of 100 to 1,000 are often used in the local lighting of work requiring the discrimination of the finest detail, while operating rooms may have 1,500 to 4,000 lumens per square foot.

The artificial lighting of 1890 was doomed to inadequacy by the ineffective light sources and by the high cost of electric energy. The natural lighting of buildings, however, was hampered in no such way, yet it is an interesting fact that the daylight illumination of buildings at that time was almost as bad as the artificial illumination. Since about 1910, factory buildings have been much improved by the use of large glass areas and by the generous application of white paint inside. Saw-tooth roofs and other special constructions have further improved the quantity and uniformity of daylight illumination. Special diffusing glasses reduce the annoying heating effect while allowing most of the visible rays to pass unaltered.

A citizen of the modern world finds bad illumination too high a price to pay for some designer's preference as to the appearance of a façade.




"THE ARRANGEMENT of electric lights in an office building, and of the wiring for them, is generally the last thing in connection with the design to receive attention from the architect, and it is frequently the case that no thought is given to the disposition of the wires until after the contract is let and the construction of the building well under way.

... alternating current "is but rarely found in office building practice.

... "in the matter of distribution of lights in an office building there is but little to be said. Where the floor area is divided up into small offices, the lights should be placed with due reference to the probable location of desks and other office furniture. In small rooms, except those occupied by doctors and similar professions, ceiling outlets are not as useful as wall brackets. In rooms of considerable floor space . . . the most ideal light is one which is diffused from small clusters of two or three lights each, distributed uniformly on the ceiling. If this is carried to an extreme, however, where the ceilings are low, it will give one the feeling of not being able to get away from the glare of light . . . a very good illumination is often obtained by rings of lights arranged about the columns and carefully worked into the ornamentation.

"In a large open space with not very high ceilings, one sixteen-candle-power lamp to seventy square feet of floor space is fairly good lighting . . . while fifty to sixty square feet per light may be considered an average."

October-December 1896



"— THE KLAXON, THE BRAKE
SQUEAK, THE HORN WHICH
PLAYS ANNIE LAURIE."

BIOLOGICAL REQUIREMENTS: 3. Sound

MAJOR DEVELOPMENTS in the science of sound fall in the category of general controlling influences later to be discussed. The studies of auditorium acoustics cannot be regarded as a major scientific development. Nonetheless, the transition from the situation where an acoustically correct auditorium was an accident to one where an acoustically incorrect auditorium is inexcusable has occurred in the period under review. Since the word auditorium has a meaning which has often been belied by rooms actually contrived by architects, this is evidently a progression of some importance.

In 1895, Wallace Sabine, an instructor at Harvard University, was asked to see what he could do to improve hearing in the auditorium of the Fogg Art Museum. It might have taken him less time had he tried merely to patch up the room in question; but, because he had a scientific mind, he preferred to attack the problem as a whole and to derive a solution applicable to other auditoriums as well.

This work of Sabine had little application until 1910 or 1915. Since that time, several companies have begun developing acoustic absorbents for improving the properties of existing rooms. This period of development witnessed a good deal of juggling and misinterpretation of results, but it now happily is almost over. In the past ten years great advances have been made in auditorium acoustics, both as to knowledge of the methods of improving design of room shape and as to materials which can be used as sound-absorbers.

Indeed, with proper design, including design of form and of materials to be used, an auditorium may be tailor-made before it is built. It can be designed to be best for a single speaker with the auditorium on the average half full, or to be best

for a
have
to un
Le C
Leagu
castin
scienc
set of
quite
applic
phone
to da
can v
on th
cut n

T
proto
Lauri
sound
wheel
ventil
scrato
write
loude
statio
where

All
value
thing
one c
if pro
those
detrin

For
of ac
ment
dwell

Mo
advan
becom
insul
struc
use i
noise
cond
corre

For
and
as ap
advan
hosp
them
chan
sleep
the n
hear
whic

for a symphony orchestra with a normally full audience, and so forth. Architects have more realization of this fact than they once did, though many still seem loath to undertake the relatively simple job of learning the fundamentals of acoustics. Le Corbusier made such an analysis for his proposed Hall for the Palace of the League of Nations. More recently, Merkelbach and Karsten, who built the broadcasting station at Hilversum, Holland, one of the most distinguished applications of science to architecture, went farther. After designing a room to be good under one set of conditions, they provided flexible parts which also made it very good under quite different conditions. This sort of thinking evidently represents a far better application of science to architecture than that which says "we can put in a microphone and a loudspeaker" for surely, no matter what the improvements in electronics to date, no speaker who has ever heard his own voice over a public-address system can want to hear it again unless he be a veritable Casper Milquetoast. The strain on the audience is of a similar sort. It is far better to use the results of science cut near the roots than picked as a fruit from the end of a limb.

THE VERY SCIENCE which brought the wonders of the new communication brought also the terrors of noise. In 1890, the clack of the horses' hoofs was a timid prototype of the backfire, the klaxon, the brake squeak, the horn which plays Annie Laurie. In 1890, the horse cars came to a rest on a light-gage track with seldom a sound wave to distress the atmosphere, while now the heavy cars, seldom rubber-wheeled, rumble on the tracks and roar around the curves of the elevated, and the ventilating systems of the subway whistle through the gratings. In the office the scratch of the pen in the ledgers has been replaced by the staccato of countless typewriters only by courtesy called noiseless. Human speech itself, it appears, has become louder. And at night in summer in the Bronx the blare of seventeen different radio stations received on 100,000 sets reflects from the brick walls of close-packed dwellings where once the cheerful cricket chirped his chirp.

All this new noise has brought with it some attention to noise scale. The decibel values once established have become of importance in many fields. Among other things they measure noise. Among the decibelian gradations, significantly, there is one called the "threshold of pain." Far below this there are intensity levels which if prolonged can create at least mild insanity, while at even lower levels, well below those frequently met in any modern city, the effect has been demonstrated to be detrimental to efficient work.

For every ill it produces, science customarily finds an antidote. So the science of acoustics has also been marshaled to stop noise. With the new acoustic materials mentioned above it is now possible to quiet office rooms, building lobbies, and dwellings to reduce annoyance and fatiguing noise.

Moreover, in the past five years, materials have been developed and theories advanced for the insulation of rooms from outside noises. As air conditioning becomes more and more prevalent, this insulation can be made more effective. Good insulation depends upon attention to a large number of details in design of the structure and the use of newly developed wall materials and lining materials for use in the ventilation ducts. In this way it is possible to reduce to a minimum the noise coming from the outside and to silence completely the fan noise from air-conditioning units, though the latter is but another example of forcing science to correct one of the difficulties in itself raised by science.

For public purposes, soundproofing has achieved the greatest value in hospitals; and this is but another example of the extent to which major advances in science, as applied to buildings, have been demonstrated most clearly in juxtaposition with advancing medical science. This is not an unnatural thing since it is precisely in a hospital that man needs most the shielding from the difficulties of today's urban life, themselves all a product of science. Its next most logical extension will be to sleeping chambers for the increasing number whose work and whose environment inhibit sleep and yet whose bodies demand it. Another possibility lies, of course, in improving the morale of the civilian populations who cower in deep shelters. If they cannot hear the bombs they may once again induce in themselves the state of complacency which first made the bombs possible.



"— THE WHOLE THING IS
WRONG, MANIFESTLY AND
ADMITTEDLY A MISTAKE —"

BIOLOGICAL REQUIREMENTS: 4. Sanitation

"QUITE THE MOST IMPORTANT of the recent improvements in house drainage consists of carrying the main drain pipe all the way to the top of the house and out through the roof. That this is an improvement everybody is agreed and it is easy to see how it is so. It affords an opportunity for the bacteria-laden exhalations from sewer or cesspool to escape by an easy path . . .

"The all porcelain bath, costing a trifle of \$300 with carved marble claw feet, at \$75 apiece, such as I have put into very costly jobs of plumbing are not quite available for the ordinary house. No more is the aluminium bath, the latest thing out, in trade slang, and costing about as much as the porcelain.

"Sewers are bad enough; our whole system of water carriage of refuse, ending by depositing it in the bed of lake or sea, may be destined to fertilize continents that shall hereafter rise to be inhabited by our descendants ten thousand years from now, but it is certainly not adapted to benefit ourselves now in the slightest degree. The whole thing is radically wrong, manifestly and admittedly a mistake, yet so tied to us by custom, by legislation, by easy availability of appliances, that it would be a task inconceivable to rid ourselves of it."

April-June 1894

GREATER AVAILABILITY of domestic bathing facilities has resulted from improved methods of manufacture and consequent decrease in cost during our period. In addition to aesthetic advantages, this advance has had some part in the reduction of pediculosity, and it serves to illustrate an indirect effect of technological advance on architecture. The essential features of sanitation systems—water supply and waste disposal—are largely community affairs and beyond the scope of the individual building; and the actual appliances are ancient and have not undergone essential change in the last half century. Yet expansion of municipal services and refinement and cheapening of appliances have worked on architecture, through facilitating life in communal dwellings. The many-storied apartment house might well be an impossibility if water supply depended on individual storage tanks and unreliable pipes; or if waste disposal were a matter still of short-run sewers. Greater compactness of installations, made possible by engineering design, has contributed economically to the apartment house and the hotel. Much the same, by the way, should be said of cooking and refrigerating appliances. Gas or electric cooking, leading to freedom from coal storage and transport, and from ash disposal, is a requisite of the modern multifamily building. The compact working-space kitchen which this cooking and automatic refrigeration allow is likewise a factor of economy in such structures.

The major improvement in waste disposal during our period has been the chemical closet (1912) which makes indoor facilities possible where sewerage does not exist and cesspools or septic tanks are impractical—an improvement of distinct importance in view of the fact that in spite of expansion of municipal services only 60% of the population of the United States in 1934 lived in dwellings connected to municipal sewerage systems.

Of interest in connection with sanitation, too, is the development of water softening, which in 1890 was carried out only in large-scale municipal plants. Hard waters caused several difficulties in house construction, reducing the effective diameter of pipes and cutting down water flow by the deposit of scale, particularly in hot-water systems where higher temperatures increased deposition. Larger amounts of soap were required in hard waters, in order to extract the hardness factors before sudsing action could be obtained. This combination of soap and the chemicals causing hardness formed a scum that deposited in clothes being laundered, or adhered to plumbing

fixtures, necessitating frequent cleaning. Development by Gans in 1905 of artificial zeolites—solid substances through which water can be passed, giving up during passage the metal ions that cause hardness—opened the way to domestic water-softening installations. Resins of the bakelite type were found by Adams and Holms (1935) to be more rapid in action and more stable in use than the zeolites. Other resins are available which remove the acid ions, so that today by a combination of two of these resins as treating agents, it is possible to obtain water equal to or better than most distilled water. Estimates have it that for a family of five the annual saving in soap that can be obtained by such a process will average from about \$20 in New England to as much as \$130 in north central states such as Illinois and Iowa.

THE IMPACT OF science and technology on architecture during the past half century has been expressed in many and diverse ways, of which those here surveyed appear primary. Their over-all effect has been to simplify performance of the functions of existence but to render more complex the act of living. They have thus increased the delicacy and the difficulty of the architect's work, placing on him greater and greater responsibility for wide knowledge and judicious choice. At the same time they have vastly enhanced his opportunities. Best testimony to the wealth offered him by science and technology, and to the resource and adventurous versatility with which he may have employed that wealth, is everywhere around us.

"**WATER CLOSETS** should not be flushed by means of valves from the water-supply pipe for domestic use. There should be a separate supply for the water-closet cisterns . . .

"Cisterns capable of holding from three to four gallons of water, placed 8 to 10 feet or more above the closet seat."


July-September 1891

AMERICAN ARCHITECTURE: 1891-1941

The foregoing survey of the contributions of science and technology to architecture serves as a necessary background to understanding the buildings which appear on subsequent pages. But however basic these forces may be there are other—and no less important—factors which operate to make American architecture today so different from that of fifty years ago. More than the mere availability of a host of new equipments and materials separates the two frontiers. Throughout the rich diversity of contemporary building—regardless of type, style or size—runs a new concept of the purpose of architecture—that buildings are for life today, not monuments tomorrow.

It would be wrong to assume that the buildings herewith presented are selected as representing all of, or even the best in, each type. The effort has been merely to select new, representative and hitherto unpublished projects. But it would be even worse to assume that all American building reaches the levels indicated here. On the contrary, the biggest job lies still ahead—that of rebuilding all America.

Credits for all photographs
in following pages (58-136)
appear on page 164.




1891-1941 Typical of the many luxurious metropolitan hotels which had already caught the imagination of American architects, the Waldorf was viewed by an early RECORD as being of "very considerable interest. The central feature... is a picturesque and attractive design, in which some Italian detail does not interfere with the general expression of homeliness and quaintness which characterizes the German Renaissance." Of the roof: "To set the gabled front of a three-story North German dwelling boldly above the cornice of a huge nine-story schloss... was a bold device quite justified by its results." In the decades which followed, the RECORD was to chronicle many changes of perhaps greater importance in the design of hotels; but the most significant has been their specialization into a dozen or more sub-types. Some representative examples are shown herewith, beginning with Miami's spectacular new skyline (right) where, according to Dr. Homer Hoyt, 41 separate resort hotels are abuilding simultaneously.



HOTELS






JAN


HOTELS




GORDON KAUFMANN AND PAUL WILLIAMS, ASSOCIATED ARCHITECTS; DOROTHY DRAPER, DECORATOR; ARROWHEAD SPRINGS HOTEL, CALIFORNIA.

Located in the Sierra Madre Mountains, not far from Los Angeles, this splendid resort hotel and spa, a contemporary version of a specialized hotel type that was well known back in the '90s, consists of 150 rooms, single or en suite, and 10 bungalows of from 3 to 5 rooms each. Mineral springs and curative muds are the basis of an extensive bath and treatment building connected with the hotel proper. Other facilities include a little theater, shops, an 18-hole golf course, tennis courts, swimming pool, and provisions for all manner of outdoor sports. The rooms of one whole wing of the hotel are equipped with triangular outdoor sitting decks that command a view of the mountains.





SWIMMING POOL



ELEVATOR LOBBY



COCKTAIL LOUNGE



TYPICAL BEDROOM



FOYER



DINING ROOM



LIVING ROOM



EXTERIOR, STEVENS HOTEL



LIVING ROOM

HOTELS

*** SKIDMORE, OWINGS & MERRILL, ARCHITECTS: REMODELED SUITES IN STEVENS HOTEL, CHICAGO.** Part of a long-range program of modernization and conversion of small hotel rooms into suites, based on obtaining useful spaces rather than rooms. Since the rooms overlook Lake Michigan, large sections of the walls were glazed to take full advantage of the view.

**To be treated more extensively in a later issue.*






BUILT-IN BOOKCASE AND DESK



LIBRARY






BEDROOM



BEFORE MODERNIZATION

HAROLD SPITZNAGEL, ARCHITECT; ALEXANDER C. RINDSKOPF, COLLABORATOR: CARPENTER HOTEL, SIOUX FALLS, S. D. A modernization job which involved resurfacing the first-floor exterior with porcelain, and remodeling the lobby and adjoining first-floor rooms. In remodeling, the coffee shop was moved up from the rear, where it had proved a losing venture, to the front of the

HOTELS



ALEXAN-
DR: CAR-
A mod-
surfacing
ain, and
ing first-
ffee shop
re it had
nt of the

hotel; it now operates at a profit. Cigar stand and coffee shop require only one cashier, as the counter is continuous; an accordion door shuts off the coffee shop after hours, when only the cigar stand is operated. For economy, the original marble wainscot was retained in the lobby; columns were furred out, and surfaced with plywood.

APARTMENTS

1891-1941 "That an eight-story apartment house could become a truly positive addition to the attractiveness of (Central Park)," comments an early *RECORD*, "was an attainment which the architect could scarcely have ventured to promise himself. Yet in the Dakota this complete success has been attained." A building type that rapidly increased in importance in the new century and received proportionately greater space in the *RECORD*, the apartment building is today a dwelling structure that is familiar in all cities of the country. As it has grown in numbers, it has also become a highly specialized field of practice. Two of the largest recently completed houses are shown here. On the following pages is a variety of other work in this category that indicates the wide range of design specialization.



The Dakota Apartment House, New York City;
Henry J. Hardenbergh, Architect



ABOVE: Aaron Colish, Architect:
2601 Parkway Apartments, Philadelphia.

ON FACING PAGE: Albert Mayer, Architect; Julian Whittlesey, Associate: Apartments on Central Park, New York City

e
l-
s
t
n
n
r
a
e
a
st
-
st

le-
ty





BEDROOM



CIRCULAR STAIR at top floor landing (above) and stairwell from landing (right).



GAR
SAN
San
stair
giving
stair
decor
idly

JAN




GARDNER A. DAILEY, ARCHITECT: DUPLEX APARTMENT IN SAN FRANCISCO, CALIF. Central feature in this duplex on San Francisco's famed Telegraph Hill is a handsome spiral stairway continuous through three floors. Added space is given the top floor landing by a mirrored wall facing the stair. Large glass areas make the view of the Bay an important decorative feature in all major rooms. Trim and detail, rigidly subordinated; color, kept to large uninterrupted areas.

APARTMENTS

APARTMENTS

HUNTINGTON, JONES & HUNTER, ARCHITECTS: HUNTINGTON APARTMENTS, BOULDER, COLO. Twelve apartments, plus janitor's quarters, garages for five cars, and communal roof deck, basement recreation and laundry rooms are included in this new project. All vertical circulation is efficiently handled by grouping each four units around a central stair running continuously from cellar to roof. Construction is of hollow tile, furred on inside; soundproofing consists of double sets of joists with blanket insulation between for horizontal divisions, while vertical party walls have staggered joists and blanket insulation. Heating and cooling are supplied from a central system but each apartment has an autonomous distribution. Lighting throughout the apartments is fluorescent recessed.



TYPICAL STAIR








LIVING ROOM



DINING ROOM

APARTMENTS




WILLIAM E. FOSTER, ARCHITECT: SHANGRI-LA APARTMENTS, SANTA MONICA, CALIF. Apartment house of 62 dwelling units: 11 two-room units, 49 three-room apartments, 2 large pent-houses. Exterior galleries take the place of interior hallways; all apartments have cross ventilation; only entrance halls, bathrooms and kitchens face galleries. So that all living rooms could share an ocean view, the side-street wing of the building was set at an angle. Below the garden court is a garage for 62 cars. The structure is of reinforced concrete.


4
6

NGRI-LA
A. Apart-
two-room
ge pent-
ce of in-
re cross
throoms
all living
the side-
n angle.
62 cars.
ete.

CORD



FROM STREET



FROM GARDEN SIDE (garage under)

JANUARY 1941

APARTMENTS



TYPICAL GARDEN TERRACE

WILLIAM WILSON WURSTER, ARCHITECT; HELEN VAN PELT, LANDSCAPING:
SIBBETT APARTMENTS, SAN FRANCISCO, CALIF. Local topography and street pattern lead logically to the stepped-back plan of this small apartment house. Main objects were privacy, garden, and fireplace in each unit. View is to north, with gardens along south and east; brow of hill protects structure from prevailing west winds. Large roof deck at top is for use of all tenants and is thoroughly soundproofed to protect the apartment below.



STREET FRONT




ROOF DECK



LIVING ROOM




BEDROOM



TYPICAL UNIT PLAN, showing organization of main rooms to exploit view. Staggered garden terraces make each unit a "first floor".

"Fairly roomy establishments of 17 or 19 rooms each" (below). At right, Elyton Village, USHA housing project, Birmingham, Ala.; D. O. Whildin, Architect.



MULTI-FAMILY HOUSING

1891-1941 Multi-family housing projects — of the type, size and rental levels now being built throughout the country by both government and private agencies—are the product of urban congestion such as early RECORDS could not imagine. Only in the last decade has the large-scale housing project come to be recognized as the chief means of clearing the unpublished slums of the '90's.

HOUSING




ONE OF USHA'S MOST AMBITIOUS PROJECTS: PITTSBURGH, PA.



EACH DOT MARKS A USHA PROJECT

USHA

UNKNOWN IN 1891, the publicly owned, low-rent, mass-housing project has become an important and characteristic feature of American life. Perhaps the most important single building type in the building field, the actual construction of housing has had to parallel new techniques in law, financing, land acquisition, design, construction, and management. Growing maturity in these techniques is marked by the number of the projects, by steadily falling unit costs, by satisfied tenants, and by increasing flexibility in plan, construction, and style to meet regional variations in topography, climate, and tradition. To date, the United States Housing Authority and its predecessor have to their credit approximately 190,000 units finished, under construction, or under contract.




low-rent,
important
life. Per-
g type in
of hous-
s in law,
struction,
in these
the pro-
satisfied
in plan,
variations
To date,
and its
oximately
ction, or




FHA

TALBOTT WILSON & IRWIN MORRIS, ARCHITECTS: CHILTON COURT APARTMENTS, HOUSTON, TEX. These eight row houses of typical plan, located on an interior lot, are staggered to provide each unit with four exposures and isolate as many as possible from a busy street. Because of soil conditions, buildings float on 6-in. concrete slab braced with integral grid of 10-in. beams 6 ft. in each direction. Construction is brick veneer on 6-in. studs. A bank of eight garages protects the rear of the property.



TALBOTT WILSON AND IRWIN MORRIS, ARCHITECTS (continued)



Unit plans are typical, providing living-dining room and kitchen on the first floor; two bedrooms and bath on the second floor.

2-FAMILY HOUSES



Four residences, New York City;
Clinton & Russell, Architects

1891-1941 *Although a statistically important type, then as now, no exact counterpart of the modern two-family house was reported by the early RECORD. However, on a similar point, the RECORD in 1897 called attention to "several dwellings made to look like one large and imposing structure. One of the best of these groups... is so arranged as to resemble a simple and well-designed college or seminary." Typical modern solutions appear herewith.*



2-FAMILY HOUSES



DOOR TO BALCONY



BUILT-IN DESK, BEDROOM

RICHARD J. NEUTRA, ARCHITECT: DUPLEX FOR MR. HARRY KOBLOCK, LOS ANGELES, CALIF.
 Designed for a very steep site with a view; bachelor quarters on lower floor; apartment for a couple above. Both living rooms open out onto terraces. Construction is of unit-type timber chassis with continuous diagonal bracing against lateral shocks. Exterior finish is of cement plaster; all sash are of steel.



UPPER FLOOR




LOWER FLOOR



L
16 x
20 x

OAK
20 x


JAN



GEORGE B. BRIGHAM, ARCHITECT: TWO-APARTMENT HOUSE FOR MRS. A. E. GREENE, ANN ARBOR, MICH.

"Two houses under one roof;" upper apartment occupied by owner; lower, by the architect and his family. A fireproof house built of cinder cement block, painted white. Space over garage is glazed and screened as a year-round living deck. Basement space under bedrooms serves as hobby room.






MARIO CORBETT, ARCHITECT: DUPLEX FOR MISS ELIZABETH MAFFEI, SOUTH SAN FRANCISCO, CALIF. Planned for a corner site, the house contains two small dwelling units, one with two bedrooms; the other, with one. Each has complete privacy: a sound-deadening partition separates the two areas; entrance doors and garages face different streets. In each case an impression of spaciousness results from making the dining area an ell of the living room. The building is of frame construction, surfaced in cement plaster; built-up roof.



ENTRANCE TO SMALLER APARTMENT


2-FAMILY HOUSES



ENTRANCE TO LARGER APARTMENT



CORNER WINDOW, DINING AREA



AN ENTRANCE DOOR

HOUSES




1891-1941 The RECORD had admitted as early as 1894 that "it is not possible for every building to be beautiful, or even pretty. The best we can do esthetically" was to insist that "each object should, as perfectly as possible, express its nature by its appearance." Though there is still room for discussion of this point, the fact remains that contemporary houses—by their clarity of organization and directness of expression—are heeding this prescient dictum of the early RECORD. James Lord Brown was the architect of the elaborate country house shown at left.





CLARENCE W. W. MAYHEW, ARCHITECT: RESIDENCE FOR MR. AND MRS. WM. P. MORGAN, MARIN COUNTY, CALIF. Designed for a couple with one servant, this hillside house is organized so as to give all main rooms access to a magnificent view. At the same time, these rooms also have access to a garden protected from the wind. By placing the house fairly close to the road, landscape maintenance is reduced to a minimum—important consideration in a dry climate. Construction is frame, with redwood siding and cedar-shingled roof.



ENCLOSED GARDEN
(from garage passage)






ENTRANCE HALL (right)
LIVING ROOM (below)



HOUSES

GEORGE FRED KECK, ARCHITECT: A "SOLAR HOUSE" FOR HOWARD M. SLOAN, GLENVIEW, ILLINOIS. Perhaps the first house in the country to make extensive use of the sun as an element in its heating system, this solar house opens up a whole new field of potentials. In the design of the house, the proper orientation for optimum insolation was carefully studied, and the size, placement, and arrangement of fenestration is a direct result. In fact the entire plan layout is determined by this factor; all rooms face south, and their wall areas on this exposure are largely of glass. To gain solar penetration in the dining room, which occurs at the back of a projecting porch, a clerestory window was introduced.






GEORGE FRED KECK, ARCHITECT (continued)




DINING ROOM SHOWING CLERESTORY



LIVING ROOM. View toward garden



DINING ROOM



WIND


HAR
HOU
are s
mou
hand
tirel
race
a dr
the s
priv
a sh

JA

HOUSES



WINDOW WALL OF THE HOUSE, facing the view




LIVING AREA



DINING AREA

HARWELL HAMILTON HARRIS, DESIGNER: HARRIS HOUSE, LOS ANGELES, CALIF. All main living rooms are so arranged that they overlook a diversified view of mountains in the background and a small lake near at hand. The wall of this side of the house is almost entirely of windows and glazed doors opening onto a terrace. The general living-dining area may be divided by a draw curtain. Garage and service wing, placed on the street side, serve, in effect, as a sound-break for the private living quarters. Location of the garage forms a sheltered garden, bordering the entrance passageway.



HOUSES



**GARDNER A. DAILEY, ARCHITECT: COMBINED
RESIDENCE AND OFFICE FOR DR. AND MRS.
BERNHARD BERLINER, SAN FRANCISCO, CALIF.**

Built on a typical residential lot, the house is but 31 ft. 4 in. in width. Separate entrances lead to the living quarters and the office-study area. For added privacy and quiet, this consultation office is equipped with double sash, double doors, and double insulation. The house is of frame construction, surfaced with tongue-and-groove redwood. Roof is of composition, with an aluminum-painted mineral surfacing cap sheet. The exterior walls are natural-finished redwood; trim and entrance recess are painted cream-white color.





REAR VIEW. (Tree is a casuarina cunninghami.)



LIVING ROOM, toward front of house





LIVING ROOM, showing dining area and garden window

HOUSES



ALDEN B. DOW, ARCHITECT: GEORGE GREENE RESIDENCE, MIDLAND, MICH. The striking photograph above is a detail of the living-room window treatment. A bold handling of unconventional angles and planes, characteristic of much of Mr. Dow's work, both emphasizes and dramatizes special features of the plan and brings interior design and exterior landscaping into close harmony. In this case, the series of windows front directly on a garden pool. Further photographs and the floor plans appear over page.

ALDEN B. DOW, ARCHITECT (continued)




THE GENEROUS LIVING AREA, arranged around the fireplace and sawtooth bay window, is the focal center of the house. At one end, in a 90° angle formed by outside walls, stairs descend from the entrance hall. In the parallel angle at the far end of the room is the dining area, with its own garden-view window and a door to a dining terrace. A passageway behind the central stairs leads to a large game room for informal entertaining. On the second floor is an unusually commodious master bedroom suite, with a study, completely isolated for utmost privacy.




ONE OF THE TERRACES



LIVING-ROOM WINDOW





LIVING ROOM, toward dining area



LIVING ROOM, toward entrance stairs

HOUSES



OSCAR FISHER, DESIGNER: RESIDENCE FOR MR. AND MRS. ANDREW T. STANTON IN RIVERDALE, N. J. An unusually open plan in a small house of traditional exterior designed as a permanent residence for two persons. The Z-shaped living space divides into living, dining, and study areas without the use of partitions. As the grade slopes downward from the front wall, there are two full stories at rear; garage, recreation room, and heater room are thus provided under the main floor. Construction is wood frame on concrete foundation. Plywood is extensively used, except for roof, exterior walls, and floors. Interior walls are of plywood, in various veneers. Lighting is fluorescent.



HALL




LIVING ROOM. View toward study area



LIVING ROOM. General view

ANDREW
in a small
dence for
ning, and
es down-
; garage,
the main
ywood is
Interior
orescent.




HOUSES

**EDOUARD J. MUTRUX AND WILLIAM A. BERNOUDY, DESIGNERS:
RESIDENCE FOR DR. AND MRS. HUDSON TALBOT, IN ST. LOUIS, MO.**

A one-story, brick residence whose design directly expresses climatic needs. Entrance is on the north side; here windows are sparingly used. The south wall has a generous amount of window area—both fixed and movable. Wide overhanging eaves reduce glare in summer, but are designed to admit winter sunlight. Above the cantilevered canopy is a continuous band clerestory windows, through which supplementary light is admitted. The large room in east wing is a playroom for a small nursery school operated by Mrs. Talbot. Its location is such that there is no conflict with living routine. Ceilings and other walls are of plaster, with wood trim. The house is heated by pipe coils laid under the concrete floor from which heat is radiated to the rooms.



DETAIL OF CANOPY on south side.



ENTRANCE DETAIL, north side.



LIVING ROOM. View from dining room




LIVING ROOM



KITCHEN



HOUSES




DONALD DWIGHT WILLIAMS, ARCHITECT: RESIDENCE FOR MR. AND MRS. D. D. WILLIAMS, SEATTLE, WASH. A compactly planned, two-bedroom house on a single floor. Construction cost was pared by inclusion of a general utility room, centrally located at the rear, in place of a basement. This room serves as both heater room and laundry. The exterior is surfaced in cedar; trim is blue green.



LIVING ROOM



BEDROOM



M
T
S
h
te
vi
de
vi
an
in
ke
bu

ENT

JAN

HOUSES

RICHARD A. MORSE AND ARTHUR T. BROWN, ARCHITECTS: RESIDENCE FOR MARGARET, COUNTESS OF SUFFOLK, NEAR TUCSON, ARIZ. Located in the foothills of the Catalina Mountains, this house, for winter residence, takes full advantage of the surrounding views. Considerable wall area in all main rooms is devoted to windows which command far-flung desert views. For outdoor living, there are covered porches and roof decks. The exterior walls and interior bearing walls are of brick. On the interior, trim was kept to a minimum, and a generous use was made of built-in fittings—cabinets, bookcases, window seats.



ENTRANCE DETAIL



WEST SIDE. Angle formed by library and master bedroom. Right: dining-room bay.



SECOND FLOOR



FIRST FLOOR



LIVING ROOM



DINING ROOM



BEDROOM

HOUSES



OUTDOOR FIREPLACE

SEWALL SMITH, ARCHITECT: RESIDENCE OF MR. AND MRS. ROY MASON, BATAVIA, N. Y. The artist's desire for a secluded studio plus the need for space for display of his paintings were basic design considerations. Arrangement of rooms in a broad L-shape plan, with the service area occupying the heel of the L, made possible the long entrance hall which serves as both hall and water-color gallery. The garage is connected to the house proper by a flagged, covered passage, providing an outdoor sitting loggia. In the forecourt is an outdoor fireplace with a stair that winds around the large chimney up to the studio.






HOUSES

***J. R. DAVIDSON, DESIGNER: TWIN RANCH HOUSES FOR THE MAURICE BERKSON FAMILY, ENCINO, CALIF.** A pair of houses, one for the parents, one for married children, on a six-acre ranch site. The houses share recreational facilities, such as the swimming pool.

**To be treated more extensively in a later issue.*



COMMERCIAL



Louis Sullivan, Architect

1891-1941 One of the great pioneer architects in the commercial field was Louis Sullivan. Reporting on his building (left) for Schlesinger and Mayer (now Carson Pirie and Scott) in Chicago, an early *RECORD* comments: "It is a logical solution of the commercial building . . . the latest and best achievement produced in this country." Today's commercial job requires detailed knowledge of diversified merchandising principles. The scope of the problem is indicated in examples on following pages.



Department stores by William Henley Deitrick, Architect, (above) and Williams and Grimes — Albert R. Williams, Architects (right).


COMMERCIAL



TWENTIETH-STREET FACADE



ENTRANCE after remodeling



BEFORE MODERNIZATION

SHOPS


MILLER, MARTIN & LEWIS, ARCHITECTS AND ENGINEERS: MODERNIZATION OF THE FRANK NELSON BUILDING, BIRMINGHAM, ALA. Formerly the First National Bank Building, the Frank Nelson Building is near the center of Birmingham's business and shopping districts. The ground-floor construction was stripped to the steel frame, and old offices were replaced with 10 modern shops. While each is laid out to meet individual requirements, all conform sufficiently to present unified street facades. The main entrance lobby is surfaced with coral marble; the floor is terrazzo. Uninterrupted show cases at either side of the lobby display merchandise of the shops that adjoin. The entire exterior of the building was cleaned and painted. Cost of improvements and renovations amounted to \$150,000.



ELEVATOR LOBBY




SECOND AVENUE, NORTH




MAIN LOBBY

COMMERCIAL



GENERAL

RAYMOND LOEWY, DESIGNER:
MACY'S OF SYRACUSE, SYRACUSE, N. Y. A remodeled store in which display technique is of paramount interest. Large plate-glass panels are used on the display cases in the arcade, with heavy glass doors set at an angle to the street. This arrangement permits a clear view of the special sales counter and the entire store. At night, a curtain, drawn behind the counter, makes the whole area a display window.



FURS

PAUL BRY, DESIGNER: BARBARA FUR SHOP IN NEW YORK CITY.

A small shop designed for the display of furs to wholesale buyers. Main considerations were to provide an effective setting against which models could show the merchandise, and a decorative, comfortable place for viewing displays. The dais at the back of the shop is raised slightly above floor level. A dressing room is provided behind curtains at one side.



NER:
YRA-
ore in
is of
plate-
e dis-
with
angle
ement
e spe-
entire
rawn
s the
ndow.

COMMERCIAL



COSMETICS

MORRIS SANDERS, ARCHITECT:
COSMETIC SHOP FOR TOUR-
NEUR, INC., BOSTON, MASS. An
8-ft.-wide shop for display and
sales. Mirrors used continuously
along one side of the shop in-
crease the apparent size of the
room and also provide a look-
ing-glass for customers.



ACCESSORIES

MORRIS LAPIDUS, ARCHITECT
FOR ROSS-FRANKEL, INC.: RAIN-
BOW STORE, BROOKLYN, N. Y. A
women's accessory shop. In
illuminating the store, a distinc-
tion was made between general
lighting, for which incandescent
fixtures are used, and merchan-
dise lighting which employs
fluorescent fixtures. Colors used
are coral and powder blue, on
an off-white background.

EQUIPMENT

WALTER DORWIN TEAGUE, DESIGNER: MIMEOGRAPH SHOP, IN CHICAGO, ILL. A showroom in which the objects are displayed against a simple and restrained background of neutral-color wallboard. Machines are set up for testing by customers.



FURNITURE

GILBERT ROHDE, DESIGNER: HERMAN MILLER SHOWROOM IN MERCHANDISE MART, CHICAGO, ILL. Curved wall surfaces and irregular openings in partitions contribute to the effectiveness of this wholesale display area. A variety of materials was used on walls: walnut plywood, quilted patent leather, and wall paper.




COMMERCIAL




FLOWERS

TIMOTHY F. PFLUEGER, ARCHITECT: ROSSI FLOWER SHOP IN SAN FRANCISCO, CALIF. Large areas of plate glass on the facade make the entire interior of the shop visible from the street and provide plenty of natural light.



SHOES


MORRIS LAPIDUS, ARCHITECT FOR ROSS-FRANKEL, INC.: FORSYTHE SHOE STORE IN LOUISVILLE, KY. Exterior is of black structural glass with bronze trim. The large showcase is used to dramatize the merchandise; the small one offers a close-up view, at spectators' eye level, of the merchandise. General lighting, incandescent; display lighting, fluorescent.



DRUGS

SEBASTIAN J. TAURIELLO, ARCHITECT: WRIGHT DRUG STORE, IN TONAWANDA, N. Y. Ease of operation and maintenance were prime requisites in this plan; a "flow sheet" was used in studying the arrangement. The solution is a compact design which does not appear overcrowded with a capacity stock, nor empty with minimum stock. Fluorescent lighting is used for wall merchandise; incandescent for counter displays.





NIGHT CLUB

ANTON REFREGIER, MURALIST; ROBERT CRONBACH, SCULPTOR: CAFÉ SOCIETY, NEW YORK CITY. One of the most highly specialized of all architectural problems is that of designing the background for a night club, since each club has a special "atmosphere" which constitutes its main attraction. Using the premises of a former club, with practically no structural alterations, the artists have succeeded in creating for the owners of this famous New York café the brilliant and satiric atmosphere desired. Dominant features are the two arced murals and the suspended sheet-aluminum sculpture in main dining room. The color scheme of the entire club is taken from the murals—pinkish browns, greys, and blacks.




TEA ROOM


SKIDMORE, OWINGS & MERRILL, ARCHITECTS: TEAROOM IN L. S. AYRES & CO., INDIANAPOLIS, IND. Part of a larger program of store-wide modernization by the same architects, this new tearoom was designed to provide attractive surroundings for moderate-priced meals. Of interest in both plan and construction are the serpentine counters and simplified chairs.



COMMERCIAL



COMMERCIAL




GENERAL DISPLAY


ROBERT HELLER, DESIGNER: ESQUIRE'S CHRISTMAS FAIR, ROCKEFELLER CENTER, NEW YORK CITY. A dramatic seasonal display of products advertised in Esquire Magazine. Arranged for easy passage of crowds of visitors, the Fair serves as a glamorous showcase for shoppers who like to look before they buy. Though none of the objects is sold on the site, prices and source names are clearly marked. Flow lines on the plan (above) show the course that visitors follow. Objects at the right of the ramp are seen both at eye level and below floor level, either over the rail or through the glass balustrade.



EXTERIOR



DISPLAY ALONG RAMP, glass panel balustrade




SAW-TOOTH DISPLAY CASES ("A" in plan). Legend describing objects appears on return face of each adjoining case.

COMMERCIAL

WAREHOUSE

RICHARD SUNDELEAF, ARCHITECT: WAREHOUSE FOR WOODBURY & CO., PORTLAND, ORE. The unusual wall system employed here resulted from the owners' desire for an attractive exterior appearance at moderate cost. Windows are of standard construction and are continuous around entire building, with largest glass area at top for best interior lighting. Roof is framed with wood trusses, three to a row of 196 ft. and spaced 22 ft. 6 in. o.c.




DETAIL, TYPICAL WALL



ENTRANCE FRONT



INTERIOR




DELIVERIES BY
ROLLER SKATE

LAUNDRY


EMMONS H. WOOLWINE AND JOHN HARWOOD, ARCHITECTS:
RAINBOW LAUNDRY, NASHVILLE, TENN. A new "cash-and-carry" plant for a motorized clientele, this new laundry's design is based on exhaustive studies with laundry-machinery manufacturers and experienced laundry personnel in order to determine the routing of the bundle from the time it is received at the plant until it is delivered to the customer.

Construction is steel frame with solid brick masonry walls; veneer is of structural glass and glass block. Ground floors are concrete and wood on concrete; mezzanine floors are plank on bar joist construction. Built-up roof with metal skylights is equipped with ventilators and heat-absorbing glass.


The plan as executed contemplates an ultimate increase of 100% in area allotted to the laundry processing space. This production area will be supplemented by increasing the present bundle room to double its size by dividing its present height into two stories; parking facilities will likewise be increased by extending concrete parking area along north face of building.




MANAGER'S OFFICE



FIRST FLOOR




MEZZANINE FLOOR





PROCESS ROOM


FLOW CHART: During rush hour, bundles are placed in streamlined carts in which they are stored until receiving drops off. They are then carted to an electrically operated inclined conveyor which carries them to mezzanine floor. Here they are assorted, marked, and dropped through automatically operated hatches to the process room where they are routed directly through washers, dryers, ironers, etc. to the bundle room. Here they are stored alphabetically. Loud-speaker system from the outside together with the assistance of bundle clerks on roller skates insures almost immediate delivery to the customer. Open space under the administration office acts as a shelter for incoming bundles and for bundle boys in wet weather. The administration office is so placed and designed as to afford an unobstructed view of both present and future parking areas, while the clear-glass partition in the foyer off the administration office commands a view of the entire plant. The bundle room is likewise visible from the clerical office so that with a minimum of steps all functions of the plant may be readily observed by the management.



ONE OF THE WASHERS

COMMERCIAL





AUTO SALES

**C. B. TROEDSSON, ARCHITECT: STUDEBAKER
AUTO SALES BUILDING FOR DAVID J.
BRICKER, INC., NORTH HOLLYWOOD, CALIF.**

The problem was to provide sales areas for both new and used cars and yet to unify these two departments. Because the local climate permits the frank use of open space, the whole corner was opened up. Distinction between indoors and outdoors is minimized, both by the planning and by the use of color. An aid to visibility of displays is the slanting glass area in the main display room; the angle is such that reflections from the street are avoided.





MOTOR-CAR SALESROOM

COMMERCIAL

SALESROOM AND SERVICE STATION

WALTER DORWIN TEAGUE, DESIGNER. Designed for New York City, the salesroom (above) is a reconstruction of the first floor of an existing office building. A main sales floor area provides for display of various models, while mezzanine balconies are used for accessories. The service station (below) is one of many built from a standard structural system and basic plan.



TYPICAL SERVICE STATION

"The c
here bu
grace a
and the
it, and t
and don
one of t
and pict
Mott H
Roberts


RAILROAD STATIONS




1891-1941 By the time the *RECORD* appeared, the American railway system was being rapidly completed; and the design of its passenger terminals was the subject of lively discussion, even for that gargantuan era. "A station is a difficult problem to treat without doing violence to its conditions," said an early *RECORD* in its critique of the station shown at left. "Almost every architect who has tried to do anything with it has been forced to introduce at least a clock tower to give some dominating feature to the design." Recent years have seen only a few metropolitan terminals rebuilt—retaining the clock if not the tower—of which the Union Terminal in Los Angeles, Calif., shown below, is largest and newest.

"The clock tower appears here but . . . the front has grace as well as strength, and the roof that surmounts it, and the tower that unites and dominates the whole, is one of the most harmonious and picturesque groupings." Mott Haven Station; R. H. Robertson was architect.





TRAIN SHEDS




J. H. CHRISTIE, H. L. GILMAN, R. J. WIRTH, ARCHITECTS; DONALD B. AND JOHN PARKINSON, CONSULTING ARCHITECTS: UNION PASSENGER TERMINAL, LOS ANGELES, CALIFORNIA. Providing for present and future needs of one of America's fastest growing cities, the new Terminal is designed to provide for the freest possible movement of incoming and outgoing passengers, baggage, and mail. Important to achieving this flow are the unusually large parking areas, and the separation of taxi, private car, and truck traffic. Typical of climate-conscious Los Angeles are large patio waiting rooms.

RAILROAD STATIONS



MAIN WAITING ROOM



GENERAL VIEW showing parking area in foreground



LAS VEGAS, NEV. Station for Union Pacific Railroad. H. L. Gogerty, Architect

RAILROAD STATIONS

TYPICAL of the kind of branch station now being built are these two—one in the far west, the other in the middle west. Their design shows a greater freedom of expression with more reliance on the basic consideration of the function of such a building. Both buildings are planned for efficient use.



LA CROSSE, WIS. Station for the Burlington Road. Holabird and Root, Architects

FACTORY DESIGN

Very naturally the words "national defense" come to mind in any treatise on manufacturing plants. When we examine the requirements of the defense program as it applies to factory construction, expansion, or remodeling, we find the factors which have always existed, intensified, and with added emphasis on speed.

For it seems at present as if we still have time for sound planning; that there is not yet — and, God willing, there may never be — need for the frantic scramble to produce which marks the last-ditch effort. This does not imply that our attitude, even as factory designers, should be the "butter-before-guns" state of mind which seems to have characterized certain countries.

On the contrary, it implies that we must plan coherently, so that, if the emergency increases, we can complete the transition from peace-time to war-time economy with the least possible waste. And, particularly if we are to augment our democratic strength, two facts become apparent: our new plants must be useful in peace as well as in times of stress (for instance, to point an extreme example, cannot the locker room of peace-time be designed for easy conversion into an air-raid shelter?); and we need many types of factories which may not seem to be a part of the defense program (food and clothing plants, and quarters for industries which process or produce necessities we can no longer import — for instance, tin and tin plate). To build otherwise will weaken, not strengthen us, in the long run.

To the designer this offers a challenge to produce good buildings quickly. "Good" work means work based on reliable industry preplanning; work which retains its usefulness when the emergency ceases to exist; work which, in a rising market, is not excessively costly; work which, being soundly conceived and honestly executed, results in truly good architecture.

Particularly for the benefit of architects who are comparatively inexperienced in the industrial field, there is included in this study a brief survey of requirements for industrial practice, as contrasted with other types of design. Leaders in the field outline structural and technical advances. There is a practical discussion of the effect of anti-sabotage, anti-air-raid planning on plant design, which emphasizes the fact that such considerations should have peace-time usefulness.

In this latter connection, two recent occurrences are worth reporting. An emigré German architect of note informed us that, in the early 1930's, he designed a workers' housing group of which one or two features led the tenants to wonder. Why were certain doors of peculiar construction? The doors answered all the purposes of what was, at least on the surface, a peaceful mode of life. Half an hour after war was declared, those doors, and the entire building, were gas-proof and bomb-resistant.

The other item concerns the Federal Bureau of Investigation. Through The Associated Business Papers, we are informed that J. Edgar Hoover, Director of the FBI, is ready to supply authoritative data on how to combat espionage and sabotage to industrial concerns upon written request of an executive official. In passing on word of these incidents we do more than repeat gossip. Such reports — and they are only two of many — emphasize to the most conservative among us the present urgent need for speed, and the increased demand for careful, economical planning.

— The Editors.

A BUILDING TYPES STUDY



INDUSTRIAL PRACTICE DISCIPLINES THE ARCHITECT

By Frederick J. Woodbridge, AIA, of Evans, Moore & Woodbridge

ARCHITECTS who undertake the design of factories are faced with considerations different in many respects from those to which they have been accustomed. These differences are perhaps more in degree than in kind, for the same fundamental principles apply to all types of architecture. In the industrial field they are simplified, are more clear-cut and uncompromising than in most others. Here function is actually the predominant factor, followed closely by economy. No esthetic consideration can prevail unless it is completely consonant with these other factors. This is a matter not arguable, especially with industrial clients. Such a concept is really very wholesome. The type of discipline involved might very well improve almost any practitioner of our art.

NOT A ONE-MAN JOB

There is no magic which precludes the undertaking of industrial work by any competent architect. Unless, however, he has had special experience and possesses a comprehensive organization, he may find himself in difficulties if he ventures alone. He should arrange to work in close co-operation with competent engineers, structural and mechanical, and this before he begins rather than after. He must also be prepared to do quite accurate estimating and business-like accounting and managing. With this external equipment, what he needs most is a great store of common sense and open-mindedness, because industrial architecture demands complete freedom from canons and prejudices which often govern other types of design.

Factory design is just the opposite of magic. There is no necessity of knowing all about line production or manufacturing processes. Most plant managers have very definite ideas on these subjects. The architect's job is to listen, question intelligently, and interpret the requirements practically. Generally speaking, he must provide a convenient entrance for raw materials, a convenient egress for the finished product, and the greatest possible flexibility in between. This ordinarily involves much greater spans and wider column spacing than are usual in other types of building. Albert Kahn states that every column absorbs at least 8 or 9 sq. ft. of floor space. Clear heights to under sides of beams or bottom chords of trusses are also of supreme importance. So is provision for crane runways and other types of shop transportation. Ample lighting, locker and toilet facilities, and other arrangements for the comfort and efficiency of workers seem too obvious to mention. Yet it cannot be too often emphasized that these very practical matters must take precedence over any artistic considerations if the job is to be successful.

INDUSTRIAL DESIGN OFFERS A CHALLENGE TO EVERY ARCHITECT

Similarly, economics take precedence over esthetics. It is vastly important to know what types of construction are actually best and cheapest for any particular case. Here the help of engineers and contractors is invaluable, because costs vary greatly and the availability of materials vitally affects the picture. This latter factor is particularly important at present. Due to other demands for steel it is difficult if not impossible to get certain sizes and weights of members. Obviously, such a factor affects design—might even eliminate steel altogether. This is perhaps the most dramatic instance of the effect of availability of materials. It is by no means the only one.

The industrial client cannot be put off with guesses about costs. He wants to know how much so many thousand square feet of space will cost him; and the given price must be pretty well all-inclusive. The architect must have precise information about the cost of every element of construction. It is also more important than ever that the architect's estimates be reliable. The industrialist is thoroughly a business man—his plant must pay. He cannot, therefore, afford to be misled, and he should not be urged to spend money on any purely architectural fancy. The architect who does so probably will not last long in the industrial field. On the other hand, it is highly desirable to keep the owner informed of all economies and advantages achieved. Once the client gains confidence from a demonstration of practical competence, the architect will undoubtedly be allowed a nearly free hand on the aspects of the problem nearest his artistic heart.

Before he wins this, however, he must prove himself in another respect: in good management, and in skill in expediting both his own work and that of construction. The practice of consuming quantities of time in studying, often desirable in other fields, is out of place in industrial architecture. Speed, and quick, unerring decisions, are vital. Promptness and precise fulfilling of promises are also essential. In short, the bad habits of an easy-going practice, to which many of us fall prey, cannot be tolerated.

It must be recognized that all these warnings and demands are really applicable to the practice of architecture in general and are not peculiar to the industrial field. It is important to emphasize them because in industrial work the necessity of heeding them is crystal clear. On the other hand, it must not be supposed that these practical requirements leave no scope for design. In this field form does follow function. As a matter of fact, the very size of factory buildings is a challenge. Their long lines and their masses, when kept simple and well proportioned, are beautiful. Architecture is here reduced to fundamentals. The opportunities are not to be despised.

It is not possible to give some "Open Sesame" which will bring the riches of the industrial field to every architect, nor can a complete compendium of advice be offered here. What has been attempted is to show first that here is an opportunity and an interesting one; that there is nothing inherent in the problem which a good architect cannot master. The second point is that common sense and practical competence are necessary even more than in other fields; that the assistance of experienced engineers is vital. In this connection the most complete co-operation with the owner and contractor is a *sine qua non*. Finally, the design of manufacturing plants can produce fine architecture on a scale to which most of us in the last few years have unfortunately been all too unaccustomed. It is a discipline and a challenge which architects would do well to meet.

**ARE STRUCTURAL MATERIALS
AVAILABLE?**

COSTS — COSTS — COSTS!

**HERE TIME IS REALLY
OF THE ESSENCE—**

DESIGN?

—AND ALL THIS MEANS:

Photos courtesy Ferro-Enamel Corp.




Conveyor takes finished ware to assembly line



Table tops are dipped




Air-conditioned spray booth



Sprayed tops travel to furnaces




Entrance to spray room



"FLOW" LINE FITS TYPICAL STRUCTURE


ADDITIONS and alterations make the Davison Enamel Company's porcelain enamel shop one of the outstanding installations in the country. Structure is typical of many process plants. Use of heated fresh air in some parts, air conditioning in others, and fluorescent light in inspection areas aids precision.




Milling machines require continuously open space



Suspended conveyors add to truss load




Research laboratory



Furnace-charging area needs special flooring and foundations

EXPANSION CAN BE PLANNED IN ADVANCE

THE PLANT of the Rustless Iron and Steel Corporation has been enlarged in accord with a policy inaugurated in 1935. Various parts of the process required special structural considerations; in the co-ordinated expansion program, all have been provided to produce a unified result.



Photographic Service Co.

Photos courtesy "The Austin Co."

Above:
the Cl
the fra
install
At rig
where

RECENT TRENDS AID THE FACTORY DESIGNER


On these and the following pages some of America's prominent factory designers report briefly on trends and techniques in factory design—on principles which have changed design and construction methods radically in the last few years. First of these is a short summation of today's problems by ALBERT S. LOW, Vice-President and Chief Engineer, The Austin Company.

EMERGENCY AND ACCUMULATED NEEDS

IN THE WIDE RANGE of building activity required for the national defense program, the two phases which have a truly constructive bearing upon our future as a nation are in the fields of civilian housing and industrial plants.

While much of the housing and many plants will be expedients for the emergency, the accumulated need of many years has centered the attention of men responsible for community planning and industrial development upon projects of lasting value. They are converting defense dollars into basic assets of sound economic value—assets whose self-liquidating character can only be assured by efficient construction of buildings which will insure maximum efficiency in use.

Industry's problem is to provide, speedily, the production facilities which may be required to meet emergency demands—always wary of any over-expansion which could be avoided by a fuller utilization of existing or projected plants.



Above and at left, three interiors of a 34,000-sq.-ft. addition to the Cleveland Punch and Shear Works, Austin-designed, of which the frame is entirely welded. Note provisions for heavy machine installations. Crane aisle spans 55 ft.; low side aisles, 50 ft. At right, interior of a "windowless" plant, also Austin-designed, where complete control of atmosphere aids precise manufacturing.



Jones

In this situation, windowless or controlled-conditions plants provide uniform working conditions for multiple-shift operation and have the inherent lightproof qualities needed for "blacking out" a plant, and are consequently gaining increased acceptance. The desirability of operations under completely controlled atmospheric and lighting conditions has been established by the experience of several companies engaged in the manufacture of aircraft engines, cutting tools, and other precision equipment. Their experiences point the way toward realization of maximum output from the limited available supply of skilled men and production equipment vital to the whole defense program.

The commercial development of fluorescent lighting, the perfection of automatic air-conditioning equipment, and the improvements in general ventilation, insulation, and acoustical controls have made this type of plant a timely and practical solution to the challenges which confront many industries.


All industries which depend upon high personal efficiency, modern equipment, and private investment funds for successful operation and continued growth are bound to face increased personnel, mechanical, and financial problems created by the stress of the times. Such problems should be minimized if they guide their expansion programs along whatever channels offer, with the least expense, the advantages which are part and parcel of controlled-conditions plants.

CONTROL OF PLANT CONDITIONS

INDUSTRY'S PROBLEMS INCREASE





GLASS WALLS ON STEEL FRAME DAYLIGHT A FACTORY: ALBERT KAHN, INC., ARCHITECTS



Wide spans, emphasized in the tremendous center bay, permit utmost freedom in layout of plant processes; shifts in production flow can be made without restraint. Notice the suspended directional unit heaters.

Right, machines placed so operators receive full benefit of natural light. Below, interior is illuminated at night by blended fluorescent and incandescent light.





Addressograph-Multigraph plant, Cleveland, Ohio; H. K. Ferguson Co., designers and builders

NEW TECHNIQUES MEET CHANGED CONDITIONS ECONOMICALLY

By H. K. FERGUSON, President, The H. K. Ferguson Co.

ONE-STORY PLANTS IN THE COUNTRY

PROBABLY THE MOST important single development in factory designing in recent years is the continuing tendency toward large areas of one-story floor space in outlying locations. Some contributing reasons for this trend are:

(a) **The manufacturer's desire for large clear areas**, unobstructed by columns, partition walls, stairs, elevators, etc. Such space readily houses a proper "flow sheet" arrangement of equipment. It also facilitates later changes in production layouts, as required by research, new products, availability of improved and higher-speed machinery, and varying needs for raw and finished storage. Improved possibilities for transportation, supervision, and inspection, in single-story buildings, with clear floor space, are also very helpful.

(b) **The first cost and subsequent taxes** on centrally located industrial properties and plants are usually high. Buildings designed to carry heavy floor loads, high in the air, also cost more than one-story structures where such loads are carried directly on the ground.

(c) **The constantly improving ability of labor to come longer distances** from home to work, due to the increased use of small automobiles for group transportation, has lessened the need for central plant locations. This emphasizes the need for large parking areas, usually available only in outlying districts. The absence of traffic congestion, improved railroad and truck facilities, and plenty of room for future expansion are all additional factors influencing manufacturers toward sizeable sites, near large cities.

Various improvements in factory designs, materials, and construction have appeared in the last few years, some of which are as follows:

(a) **New structural steel shapes and techniques** use the material required to much better advantage; the use of shop and field welding for structural steel for factory buildings has materially reduced weight, cost, and appearance, and often improved sturdiness, as compared to riveting.

(b) **Maintenance costs** are being reduced by better paints and putties. Also by improved floor materials; and gypsum plank, or other permanent and non-combustible materials for roofs, instead of matched lumber, and improved fixtures for plumbing and other facilities are all very useful.

(c) **The fluorescent type of electric lighting**, while still quite expensive, is taking an important place in factory illumination.


Fluorescent lighting has worked in particularly well with the new types of windowless factory buildings, which are, of necessity, air conditioned, and provided with automatic temperature, and sometimes, humidity controls. Such plants are particularly useful for three-shift operation, for the reason that they provide uniform working conditions on all shifts. Where two- or three-shift operation is regularly practicable, the added first cost of such plants is more than offset by the intensified use of machinery and plant.

There is still, however, in many instances a continuing prejudice on the part of labor against working in walled-in areas, where no daylight or outside air are directly available. The present tendency is toward the use of windowless buildings for certain operations, rather than entire factories.

Other buildings are frequently provided with roof insulation, actinic or other heat-resisting glass, good ventilation, and similar improvements, to provide better working conditions at much less cost.

The defense program has again put special emphasis on speed. To any manufacturer, standardization and speed are closely related. In consequence, there is a renewed interest in the better types of standardized one-story industrial buildings, which are available for quick completion. Such structures are easily dressed up with attractive exterior architectural treatment, or to conform to adjoining existing plant buildings. They are ordinarily delivered, ready to occupy, in 60 working days.

Interiors of Ferguson-designed plants demonstrate new trends. Below, Addressograph-Multigraph plant; right, National Cash Register Co., Toronto, Can.



NEW TECHNIQUES

WITH WINDOWS, OR WITHOUT?

PREFABRICATION FOR DEFENSE



★ **DIVCO-TWIN TRUCK COMPANY:** Total steel tonnage reduced by cantilevered framing


4 FACTORIES DESIGNED BY SMITH, HINCHMAN & GRYLLS


All four of these projects are examples of the designers' ingenuity in overcoming structural difficulties. In every case, the object was to achieve a maximum of economy consistent with sound construction and manufacturing requirements.

★ **DIVCO-TWIN TRUCK PLANT:** Bays are 40 by 50 ft. The 50-ft. dimension is spanned with a 21-in. girder, the other with 12-in. purlins. Girders in high bays cantilever over columns and carry hangers which pick up girders in low bays. This has the effect of giving continuity over columns, thereby greatly reducing moments in 50-ft. girders, especially positive moments. Purlins also cantilever over girders and are spliced about 7 ft. 6 in. from girder center line. This greatly reduces the moment for which purlins had to be designed. By these means, steel was reduced to 8.2 lbs. per sq. ft. (total tonnage, including door frames, girts, sash framing, mezzanine floors for toilet rooms, crane girders, trolley-beam supports, unit-heater supports, etc.)


★ **BUNDY TUBING PLANT:** Considerable thought was given to the desirability of reducing the amount of glass usually provided in such buildings. It was decided to omit all monitors and skylights and provide instead a line of sash 6 ft. 10 $\frac{3}{4}$ in. high around the outside of the building. Below this sash, a masonry wall was used, and above, corrugated asbestos-cement board with insulation backing. This produced a substantial saving in cost of the building's shell. Cost of the lighting installation was not increased—possibly slightly reduced. The building was not air conditioned; to compensate for monitor ventilation, a blast system was used for heating the central part of the building, and arrangements made so that fresh air from the outside could be taken and distributed throughout the building when desired. Elimination of moni-

★ **BUNDY TUBING COMPANY:** Omission of monitors produces savings.





★ **SOSS MANUFACTURING COMPANY:** Cantilevered framing plus roof-hung equipment






★ **CARBOLOY, INC.,** division of GENERAL ELECTRIC COMPANY: All-welded steel framing

tors and glass area substantially reduced heat loss, and thereby produced an important saving in heating cost which will occur year after year. More current will be used for lighting, but not as much more as would at first be expected because modern lighting is very efficient; and even when a great deal of glass is provided, the lights will be found burning a good deal of the time because of dirty windows, dark days, etc.

★ **SOSS PLANT:** Framing is similar to that used in the Divco-Twin Truck plant, but because of special shafting and motor supports hung from the roof framing, the tonnage was considerably heavier.

★ **CARBOLOY PLANT:** This new plant is an all-welded job, one of the largest of this type in Detroit. It contains about 500 tons of structural steel.





MILITARY CONSIDERATIONS may alter city and factory planning. Structures widely scattered, or in lines, form poor targets.

PREPARATION FOR FACTORY A. R. P. EXPANDS PE

DODGE THE BLOW OR RIDE WITH IT

PERFECT ARMOR against modern projectiles is not a possibility. Not only is construction of impenetrable hoods over cities, factories, even houses, uneconomical; as fast as armor becomes "bombproof," projectiles capable of penetrating it are developed. The architect can best compete with the armament technician in fields where the technician is powerless: by intelligent planning the factory designer can reduce the probability of direct hits; by proper design he can minimize damage when hits occur.

New considerations include layout of buildings on the plot, and design of individual buildings toward the end of localizing damage when it occurs. An intelligent plan also includes, from its very inception, facilities for protection of employees, usually by means of shelters, at least by means of emergency exits. And, since some damage can be expected, facilities for quick, easy repairs are essential.

To achieve a reasonable degree of security we have to take into account stresses which, though similar to those

now recognized as design factors, react in strange, almost unexplored fashion: terrific pressures resulting from explosions; suction, opposite in action to recognized forces and almost unmeasurable; earth tremors, which introduce new impact loads into foundation design; new live and dead loads, superimposed on normal loads, and caused by impact and accumulation of falling debris; and torsion, cantilever action, and distorted bending moments, initiated by partial collapse of a structure. And, though poison gas may not now be used, it would be folly to neglect precautions against it.


CONTRADICTIONS IN PRINCIPLES

Many apparent contradictions confront the architect who attempts a building program which recognizes these new factors. A plant whose buildings are widely dispersed will sustain relatively few direct hits. When exterior considerations cause a congestion of factory buildings, the chances of direct hits become greater.



European experience indicates an exactly opposite method of procedure for congested buildings than for dispersed buildings. In the one case, structural damage

Paradoxically, peace-time principles can be successfully applied to anti-sabotage, anti-air raid design. From arrangement of buildings to design of doors which may ultimately have to be gasproof, new devices, new structural methods, new stresses have to be considered. So much is true; but we must utilize our experience in research, design, and construction in finding solutions to these new problems. Thus only can uneconomical construction be avoided.

KONRAD F. WITTMAN, Architect, who discussed the effects of war on city and factory planning in the September 1940 RECORD, here analyzes changes in factory design which result from protective planning, and outlines practical procedures.



EXPLOSION-INDUCED PRESSURE approaches in violence the force of impact of heavy, rapidly moving solids.



... The poor target suffers fewer direct hits, and requires different precautions against damage, than the good target.

ENDS PEACE-TIME PRACTICE TO NEW FIELDS

from direct hits, or other *internal explosions*, can best be minimized by providing a strong frame and a flimsy envelope. In the other, damage from adjacent hits, or *external explosions*, is best combatted by more nearly uniformly strong construction. When a plant is obviously of primary military importance, it is best to apply to its design procedures suitable for congested buildings, since every attempt will be made to achieve direct hits. However, when anti-aircraft provisions are adequate to force raiding airplanes to great heights, precautions suitable for dispersed buildings are most satisfactory.



The foregoing principles derive from another, which may be stated as follows: *The force exerted by expanding gases and air pressure is in proportion to the strength of the resisting surfaces. An explosion confined by strong masonry is tremendously increased in violence because it is so confined.* An explosion in a narrow court is much more vehement than the same burst in an open street. This principle is recognized by designers of cereal processing plants, grain elevators, and other structures where there is danger from explosive dust. "Explosion" sash have been developed to provide low-resistance lines of escape for expanding gas, and so to reduce pressure against remaining obstacles.

PROTECTION FROM INTERNAL EXPLOSIONS


Observations of explosions of many types prove this thesis: The more window panes are blown out, the less damage is done to structure and equipment by internal explosions. Destructive force is decreased by increasing the number of windows and doors.

A structural frame of steel or reinforced concrete, with light curtain walls and large window openings, is eminently satisfactory for buildings which, due to uncontrollable circumstances, are congested in comparatively small areas. The roof can provide another such "safety-valve." Sometimes it is far better to permit the roof to be blown off rather than cause damage to valuable machinery or to the building's structural frame. In such a case, the roof is anchored as lightly as possible, or may, like exterior walls, consist of a strong frame and light filler panels.


New, standardized materials: Under these conditions an ideal material for window glazing could be blown out without breakage, and wall—possibly roof—panels are preferably so standardized that their immediate replacement from stock offers no problems. (Continued on page 152)



... and by collapse of damaged parts.



FACTORY A.R.P. (continued)



IN MULTI-STORY PLANTS, collapse of part of building can destroy heavy equipment as effectively as bombing unless it has independent foundations.

Windows: Present types of glazing materials all react like other known products. Glass breaks. Wire glass breaks like ordinary glass, though in larger fragments. Glass block reacts like solid masonry. Some type of weather-resistant, non-brittle, transparent plastic may be developed to meet all requirements; however, such materials remain in the laboratory stage at present.

PROTECTION FROM EXTERNAL EXPLOSIONS

To resist the shock of an explosion outside a building, the entire structure, walls, floors and roof, as well as frame, must possess strength; wall openings have to be reduced in size and number.

These provisions hold true particularly for explosions in the vicinity of a building, but not immediately adjacent. The greatest destruction is caused by debris which damages expensive machinery, disrupts plant processes, and takes lives. Window glass is broken inward by concussion; interior finish and decorations fall as a result of violent shaking; roofs are torn off by the vacuum which an explosion induces on the lee side of the structure. If the windows themselves cannot be made small, they can be divided into small panes. The roof needs secure anchorage.

Explosions immediately adjacent to a building can best be offset by a strong structural frame with strong, rather than light, curtain walls. Experience with earthquake-resistant construction is valuable here. The curtain walls

require more secure attachment to the frame than is necessary in the case of internal explosions.

For both near-by and distant external explosions, windows can be protected with temporary or permanent shutters to resist the first shock. Further considerations include protection for roofs and reinforcing of floors against flying splinters, shell fragments, debris; design of protective doors, usually steel, for resistance to distortion and for easy operation under all conditions. Sandbags do not offer the best protection, since flying sand may prove more devastating to machinery and equipment than a few shell fragments would be. For the same reason, an elastic type of pavement, which breaks into large pieces, is more satisfactory than paving made up of numerous small units; because the latter may become a shower of missiles as destructive as shrapnel.


Vacuum: Precautions against exterior forces on one side of a building will not always prove satisfactory on the other. The characteristic suction, induced by the vacuum left behind obstructions in the path of expanding gases, reacts oppositely to recognized structural forces. Secure anchorage of wall members, of casings at openings, and of roofs; and elimination of all projections which may afford leverage for the force, are the principal means of avoiding excessive damage.

NEW TECHNICAL REQUIREMENTS


Modern technical and manufacturing requirements are so complex that each case has to be studied independently. Very often the designer has to accept greater vulnerability rather than encumber the manufacturing process with an uneconomical layout (for instance, when the process requires compact arrangement of buildings). However, many details and operations can be rendered less vulnerable without disrupting production flow. To insure continuous operation under all conditions, a check has to be made of every line of traffic, all supply lines, all buildings and every detail of each building, under the assumption that damage may be sustained from direct hits, bullets or splinters, or, at the very least, air pressure. Some of the most vulnerable spots are as follows:

Exits: Are exits so protected that falling debris cannot block them?


(Continued on page 154)







STORAGE OF LIQUIDS, whether water, caustics, chemicals, or inflammable material, offers a serious problem. Hoods indicated at right are proof against light projectiles only; construction to receive them can serve in peacetime as protection against normal hazards.





AIR-RAID SHELTER DESIGN




PEACE-TIME LOCKER ROOMS can become war-time air-raid shelters. Above, diagram indicates satisfactory location for locker-room-shelter, with emergency exits removed from plant building to prevent their being blocked as a result of explosions. At right, three types of sub-grade shelters. When chances of direct hits are good, entrances from plant are best located near exterior factory walls (top scheme). When explosions are most likely to occur outside plant, center entrance (bottom) is best.




TYPICAL SHELTER has two basic parts: gas lock, and shelter proper. It has been found most satisfactory to limit capacity of one unit to 50 persons. At right is scheme for multiple unit shelter for 200 persons; in all diagrams, B indicates bombproof door, G, gasproof door. Below, "dos" and "don'ts" which may save lives.






DANGEROUS PRACTICE IN SHELTER DESIGN



SAFE PRACTICE IN SHELTER DESIGN



FACTORY A.R.P. (concluded)



GASPROOF AND BOMBPROOF DOORS have to be extremely simple in design, to insure their operation even though damaged, and to facilitate repairs. Doors set in normal reveals are unsatisfactory. All doors operate from within. Interior door has curb at sill; gasket seals opening.

Spacing of buildings: Can collapse of a wall damage an adjacent structure, or block a street?

Employee safety: Has every precaution been taken to prevent employees from being injured by debris?


Supply lines: What happens when electric power is disrupted? Are electrical fire hazards eliminated? Are supplemental power lines available? Are steam piping, and other supply and process lines, protected? If damaged, are they located and identified in such a way as to facilitate repairs? Are supplemental sources available?

Sprinkler system: Is the water supply for sprinklers protected? A supply tank on the roof is an excellent target; can another location be found?

Fire prevention: What means are provided for checking fires if the water main is destroyed?

Sewers: Are they adequately protected? Are sewers for air-raid shelters independent of others? Vulnerability of sewers concerns Londoners more than destruction of houses.

Repairs: Are all the small, intricate details of the structure—for instance, doors and door latches, hinges, sash operators—of the simplest possible design? If at all complicated, their repair will be extremely difficult. Are doors applied to the face of a wall, rather than set in reveals where explosions may jam them tight? Are all parts of the structure of types which can be replaced with local materials, by local workmen? Many ingenious, complicated products cannot be obtained in an emergency.



SIMPLE MEANS of protecting the areaway of a sub-grade window

AIR-RAID SHELTERS

Air-raid shelter requirements have been modified to a great degree in the light of today's European experience. They require some further adaptation to fit into American economy.

In the first place, shelters were originally designed as temporary refuges. Today's air raids last hours, even whole nights. Obviously, more is needed in the way of accommodations than was first contemplated, even though the accommodations satisfy only the primitive needs: physical safety; pure air and water; medical care; toiletting, feeding, sleeping; communication.

On the other hand, grandiose shelter-towers, each to protect 1,000 persons or more, reflect an unwise enthusiasm for monumental construction. Not only would such medieval fortresses be uneconomical; they might also endanger morale by their presence.

Underground shelters have many advantages over surface shelters. Both types may be so designed as to have peace-time usefulness; the underground shelter, among other things, is less visible and therefore is a poorer target; it is more quiet; it may have several feet of earth fill over it for additional protection.

Peace-time use: Particularly in factories, every shelter should be designed for some use in peace time, preferably for a use similar to its war-time purpose. And the change from the uses of peace to those of war has to be accompanied by a minimum of alteration. In the average plant, the combination of employees' entrance, locker rooms, and stairs is entirely satisfactory for shelter use, provided overcrowding is eliminated. The two types of functions are similar; natural light is not mandatory for either; every man has his assigned locker space; constant use assures their instant readiness in emergency.

A typical unit shelter is illustrated herewith. Individual units preferably accommodate no more than 50 persons; larger numbers are accommodated by providing more units. It is particularly important that emergency exits be protected from collapsing walls, bursting tanks, and proximity of inflammable materials. Easy accessibility is also essential to prevent delays and confusion.

THERMAL EXPANSION—FACTORY BUILDINGS

ARCHITECTURAL RECORD
TIME-SAVER
STANDARDS
JANUARY 1941

Data on this sheet were obtained from reports of the British Building Research Station, from other publications, and from current engineering practice. Material was prepared by Jule Robert von Sternberg, Architect.

THERMAL EXPANSION

Two types of temperature variation induce movement in a factory structure. First of these is the slow, seasonal change from winter to summer; second, relatively rapid fluctuations which take effect within a few hours. Design of almost any industrial building involves consideration of both. In ordinary buildings, the more rapid fluctuations are most likely to cause damage.

Fortunately, concrete and medium steel have similar coefficients of expansion. Masonry has the advantage of being able to take up movement in its joints. Where buffers must be provided between stressed materials, expansion joints, properly protected against wear and weather, usually suffice.

EXPANSION JOINTS

Where such a building—or one of its parts—is restrained from moving by the pressure of an adjoining building, or other mass, provision must be made to take up the thrust. Expansion joints, therefore, normally occur between new and old buildings; between a wing of a building over 150 ft. long and the main body of the structure.

Movement also takes place between

parts of the same structure exposed to different temperatures. Ordinarily, roofs become much hotter, and expand more, than walls, especially shaded walls. To prevent damage, roofs are frequently ringed with expansion joints. In addition, the roof structure, particularly if it is rigid, may be large enough to require a transecting expansion joint; one which passes through the roof, walls, and sometimes lower floors. Such transecting expansion joints vary in size and design with the size and construction of the building, and location of the joint.

In monolithic reinforced concrete buildings, expansion joints should completely divide the structure, cutting roof, walls, and floors completely. Joints are sometimes provided 100 ft. on centers. Usual practice is to space them every 200 ft. By using longitudinal reinforcing, buildings up to 300 ft. in length have been successfully constructed without expansion joints.

Steel-framed buildings: Practice varies in the steel-framed building with curtain walls. Although expansion joints that completely divide the buildings are also used in this type, 200 to 250 ft. o. c., many successful slab-roofed buildings have been constructed with expansion joints in roofs and top-floor walls only, stopping at the top floor line. The expanding roof slab moves faster and farther than do the walls. Flexibility of the top-floor steel columns is relied upon to yield to the thrust set up by the roof

slab, completely absorbing it and preventing its transmission to lower stories. Movement of masonry in lower floors is taken up in individual joints, and is further restrained by the steel framing.

Solid masonry buildings: Free-standing solid masonry buildings usually require joints about 100 ft. on centers. With an average winter-summer temperature differential of about 100° Fahrenheit, a masonry wall will expand about 0.4 in. in every 100 ft. of length. Expansion joints at 100 ft. intervals must be approximately ½ in. wide, and are easily concealed in the average mortar joint.


PROVISIONS AT GRADE

Provision needs to be made for the building equipped with transecting expansion joints to slip on its foundation. In the case of solid masonry buildings, the mortar joint between concrete foundation and masonry wall is found a satisfactory slipping surface. Monolithic buildings, however, require slip joints between the walls and foundation to permit movement of the superstructure. The foundation, being buried in the ground, with little temperature differential to influence it, is not affected by temperature fluctuations of the air.


SPECIAL BUILDING TYPES

Structures in which there are maintained unusually low summer temperatures, as in breweries and cold-storage warehouses, must allow for much greater expansion than other factory types.

DAMAGE RESULTS FROM THERMAL MOVEMENT WHEN NATURAL MOVEMENT OF PARTS IS RESTRAINED



MEANS OF PREVENTING DAMAGE DUE TO THERMAL MOVEMENT



THERMAL EXPANSION JOINTS—FACTORY BUILDINGS

COEFFICIENTS OF LINEAR EXPANSION (In inches per degree)

METALS, ALLOYS	
aluminum, wrought	.0000128
brass	.0000104
bronze	.0000101
copper	.0000093
gray cast iron	.0000059
steel, hard	.0000073
steel, medium	.0000067
steel, soft	.0000061
STONE, MASONRY	
ashlar masonry	.0000035
brick masonry	.0000031
cement, Portland	.0000059
concrete	.0000079
concrete masonry	.0000067
granite	.0000047
limestone	.0000044
marble	.0000056
plaster	.0000092
rubble masonry	.0000035
sandstone	.0000061
slate	.0000058
TIMBER, parallel to fiber	
fir	.0000021
maple	.0000036
oak	.0000027
pine	.0000030
TIMBER, transverse	
fir	.000032
maple	.000027
oak	.000030
pine	.000019

Note: Average winter-summer temperature range is 100° F.

EXPANSION JOINTS ARE NEEDED:

1. WHERE A LONG LOW STRUCTURE ABUTS A RIGID MASS.
2. AT ENDS OF A LOW STRUCTURE BETWEEN TWO HEAVY MASSES AND AT APPROPRIATE INTERVALS—USUALLY EVERY 150 FEET.
3. WHEN A NEW BUILDING ADJOINS AN EXISTING BUILDING.
4. IN FREE STANDING BUILDINGS, THROUGH EXPANSION JOINTS ARE REQUIRED AT INTERVALS OF APPROXIMATELY 200 FT.
5. WHEN INTERIOR AND EXTERIOR TEMPERATURE DIFFERENTIALS ARE EXCESSIVE, AS IN A COLD STORAGE BUILDING.

FUNCTIONS:

MUST PROVIDE FOR MAXIMUM THERMAL-INDUCED MOVEMENT LIKELY TO BE ENCOUNTERED.
[WIDTH OF JOINT "A" = SPAN (INCHES) X 100 (AVERAGE WINTER-SUMMER TEMP. DIFF.) X α (COEFFICIENT OF EXPANSION OF THE MATERIAL)]

BUILT-UP ROOF
MUST EXCLUDE THE WEATHER IF EXPOSED





COVER PLATE
MUST PROVIDE FOR TRAFFIC, IF USED IN A FLOOR.

MUST BE CONCEALED IF IT IMPAIRS APPEARANCE.







TYPICAL EXPANSION JOINTS:

NOTE: DRAWINGS NOT TO SCALE





ROOFS



WALLS



FLOORS



FACTORY TOILETS AND LOCKER ROOMS

Data in this Time-Saver Standards sheet offer means of determining numbers of fixtures, clearances, and areas for factory toilets and locker rooms. Information was prepared by Jule Robert von Sternberg, Architect, from Labor Code provisions and from current practice.

Factory sanitary facilities are of several general types. Most important is the "change" room (hereafter called "locker room"). This may consist of a locker room proper, containing lavatories, lockers, and showers, plus a separate toilet room. Showers are sometimes in a separate room. Requirements vary from industry to industry, from factory to factory. In a compact, one-building plant, one pair of locker rooms is ordinarily provided close to the employees' entrance. In plants which occupy several buildings, locker rooms are usually provided in each main unit. Occasionally they may be in a separate building.

Whatever the general location, locker rooms have to be as close to the job as possible. However, they must not interfere with plant operation. They are often in an adjoining "tower" building; sometimes on a mezzanine above the working floor.

Architectural finish: Walls, floor, ceiling have to resist penetration of water and water-borne dirt; ceilings are often acoustically treated; floors have to stand up under heavy traffic, soap and water, acid and alkali; every piece of equipment has to withstand punishment.

Ventilation: Windows are not vital toilet equipment. Artificial light and forced ventilation are often substituted; usually to advantage, for they permit close control of light and air. Number of air changes varies from 10 to 20 per hour.

Lighting: Illumination has to be at a high enough level to promote cleanliness and employee comfort. In general, 6 to 8 lumens per sq. ft. are provided. Lights are placed to give direct illumination to lockers, lavatories, and occasionally showers. Lighting in toilets is placed to discourage reading.

Size varies with industry requirements. A general rule is: the dirtier and hotter the work, the greater the demand for showers and lavatories.

Least standardized are lockers. Type usually recommended is the individual locker 12 in. wide, 18 in. deep, 72 in. high, with a built-in lock. A number of smaller-sized lockers are used, however. Some manufacturers (of jewelry, etc.) do not install lockers for fear employees will secrete company property in them. These require that all clothing be hung in the open where it can be watched.

Arrangement: The locker room is preferably laid out so traffic flows with least confusion. Toilets, lockers, showers, lavatories have to be selected and arranged so the entire working force can use them in the shortest time. To achieve this, consideration must be given to relative usefulness of each type of equipment, numbers of shifts and of men per shift, work habits of men, and relationship of factory work areas and parking areas to locker room.

Expansion: Because no modern factory is designed to remain fixed in form and function for its lifetime, locker rooms, whenever possible, should have provision for expansion.

Other types of toilets: toilet facilities must be provided for workers at convenient intervals: i.e., so the average worker need walk only 100 to 125 ft. to a toilet. In areas where only a very few men work, distance may be increased to 200 ft.—an outside limit. These secondary toilets contain water closets, urinals, and lavatories.

A separately housed toilet may be provided in the yard if a large number of men are employed in it. If not, yard workers use boiler-house or plant toilets.

Toilets are also provided for office workers and visitors in the administration building. These are similar to office building provisions.

Women's rest rooms adjoin women's toilets. These must conform to local codes, and usually contain space for a couch and reclining chairs. It is also customary to provide women's showers with private dressing booths.

MINIMUM FIXTURE REQUIREMENTS

(N. Y. State Labor Code)

No. of MEN	Water Closets	Urinals	No. of WOMEN	Water Closets	No. MEN or WOMEN	Wash Basins
1-9	1	0	1-15	1	1-20	1
10-15	1	1	16-35	2	21-40	2
16-40	2	1	36-55	3	41-60	3
41-55	2	2	56-80	4	61-80	4
56-80	3	2	81-110	5	81-100	5
81-100	4	2	111-150	6	101-125	6
101-150	4	3	151-190	7	126-150	7
151-160	5	3	191-240	8	151-175	8
161-190	5	4	241-270	9	176-200	9
191-220	6	4	271-300	10	201-225	10
221-270	6	5	301-330	11	226-250	11
271-280	7	5	331-360	12	251-275	12
281-300	7	6	361-390	13	276-300	13
301-340	8	6	391-420	14	301-325	14
341-360	8	7	421-450	15	326-350	15
361-390	9	7	451-480	16	351-375	16
391-400	10	7	481-510	17	376-400	17
401-450	10	8	511-540	18	401-425	18
451-460	11	8	541-570	19	426-450	19
461-480	11	9	571-600	20	451-475	20
481-520	12	9	601-630	21	476-500	21
521-540	12	10	631-660	22	501-525	22
541-570	13	10	661-690	23	526-550	23
571-580	14	10	691-720	24	551-575	24
581-630	14	11	721-750	25	576-600	25
631-640	15	11	751-780	26	601-625	26
641-660	15	12	781-810	27	626-650	27
661-700	16	12	811-840	28	651-675	28
701-720	16	13	841-870	29	676-700	29
721-750	17	13	871-900	30	701-725	30
751-760	18	13	901-930	31	726-750	31
761-810	18	14	931-960	32	751-775	32
811-820	19	14	961-990	33	776-800	33
821-840	19	15	991-1020	34	801-825	34
841-880	20	15			826-850	35
881-900	20	16			851-875	36
901-930	21	16			876-900	37
931-940	22	16			901-925	38
941-990	22	17			926-950	39
991-1000	23	17			951-975	40
					976-1000	41


WASH FOUNTAINS REQUIRED

Number of Fixtures	Persons Accommodated By:			
	54" CIRCULAR (8 each)	54" SEMI-CIRCULAR (4 each)	36" CIRCULAR (5 each)	36" SEMI-CIRCULAR (3 each)
1	1-175	1-80	1-100	1-60
2	176-375	81-175	101-225	61-125
3	376-575	176-275	226-350	126-200
4	576-775	276-375	351-475	201-275
5	776-975	376-475	476-600	276-350
6	976-1175	476-575	601-725	351-425
7		576-675	726-850	426-500
8		676-775	851-975	501-575
9		776-875	976-1100	576-650
10		876-975		651-725
11		976-1075		726-800
12				801-875
13				876-950
14				951-1025

Courtesy Lockwood-Greene Engineers, Inc.


FACTORY TOILETS AND LOCKER ROOMS

LAVATORIES




INDIVIDUAL
FIXTURE
TYPE

EXCEPT AS NOTED
SCALE 1/4" = 1'-0"




WALL-HUNG
TROUGH




ISLAND-TYPE
TROUGH

SEMI-
CIRCULAR




CIRCULAR




CIRCULAR FOUNTAINS


SHOWERS



GANG SHOWERS



STALL SHOWERS




WOMEN'S (DRESSING
BOOTHS INCLUDED)




CIRCULAR SHOWERS


LOCKERS




SINGLE TIER



MULTI-TIER



SINGLE TIER, INTEGRAL BENCHES




MULTI-TIER, INTEGRAL BENCHES

TYPICAL MINIMUM TOILET CLEARANCES

(NEW YORK STATE LABOR CODE)

SCALE OF PLAN 1/8" = 1'-0"




COURTESY LOCKWOOD-GREENE ENGINEERS, INC.


WOMEN'S DRESSING ROOMS REQUIRED AREAS			
PERSONS	SQ. FT.	PERSONS	SQ. FT.
0-4	NONE	300	640
5-10*	60	400	840
25	90	500	1040
50	140	600	1240
75	190	700	1440
100	240	800	1640
150	340	900	1840
200	440	1000	2040

* BASED ON 2 SQ. FT. ADDITIONAL PER
EACH ADDITIONAL PERSON OVER TEN
(NEW YORK STATE LABOR CODE)


THESE FLOORS DOUBLE AS WINDOWS



FACTS ABOUT OPEN STEEL GRATING



SELF-CLEANING. Open Steel Gratings do not accumulate dust, dirt, grease, oil or moisture. Their construction makes them virtually self-cleaning.



ECONOMICALLY INSTALLED. Every section of Open Steel Grating is built to the requirements of the individual job. This factory layout insures speedy installation and perfect fit.


ONE of the primary functions of Open Steel Grating floors and steps is to admit air and light to the areas above or below their surface. No other flooring material performs both these functions in a manner as efficient. Not only does this strong, rigid flooring provide free circulation of air and escape of fumes, gases and heat, but it also admits light.

Open Steel Grating is permanent and durable. Because of its open construction, it does not accumulate dust, dirt, grease, oil or moisture. When used

for outside walks it will not collect ice, snow or water. It is factory fabricated from a combination of structural members rigidly connected by riveting, welding or interlocking.

Open Steel Gratings are built to the requirements of the individual job, insuring fast and economical installation and a perfect fit. For more detailed information on this strong, non-slip, rigid flooring that admits the passage of air and light, write today for the free booklet shown below.

OPEN STEEL FLOORING INSTITUTE, INC.



LIGHT WEIGHT. Every pound of material is used, with maximum efficiency to carry or distribute loads—meaning less dead weight, lighter supports, reduced erection costs.



NON-SLIP SAFETY. Open Steel Gratings cannot accumulate skid-inducing substances—provide an even, non-slipping, stumble-proof surface.



OPEN STEEL FLOORING INSTITUTE, Inc.
Dept. AR-141

American Bank Building,
Pittsburgh, Pennsylvania

Send me, without obligation, your new booklet, "New Ideas in Functional Floor Design."

Name.....

Address.....

City..... State.....

NEWS OF MATERIALS AND EQUIPMENT



Figure 1



Figure 2




Figure 3

Corrugated Enamel Sheathing

A CORRUGATED ENAMEL sheathing is said to combine the advantages of formed roofing and siding with the corrosion-resistance, smooth surface, and color of porcelain enamel, and should be especially adaptable to industrial structures. The sheathing may be applied on steel or wood framing, solid roof decks or side wall surfaces; is finished, including edges and bolt holes, with white porcelain enamel inside and a range of colors outside. It employs a new type of lock joint to assure weather-tightness

without chipped enamel. Sheets, machine-punched for fastening to a structure, are 24 in. wide after interlocking and come in standard lengths from 5 to 10 ft. Porcelain Enamel Steels, Inc., Cleveland, Ohio. (See figure 1.)

Natural Lighting System

A NEW SYSTEM of illumination that produces a daylight effect, announced recently, should have important applications in various fields from art galleries to industry. The outdoor light effect is gained by a special combination of incandescent and fluorescent lamps, which shine through a ceiling of heat-treated, water-white glass. Adjustment of lamp angles and special lenses control the highlighting of certain areas as desired. The system is in use in the Carnegie Institute Gallery in Pittsburgh. Westinghouse Electric & Manufacturing Co., Pittsburgh, Pa. (See figure 2.)

Range and Heater in One

ROCK-BOTTOM heating-cooking cost for low-rent housing projects is the purpose of Anthracite Industries Laboratories in developing, with USHA, a combination hot-water heating boiler and cooking range, with water back, that burns coal. It is expected that the unit, not yet in commercial production, will heat a six-room house and can be produced for \$125 or less. The heater is designed to be placed against the kitchen wall, with one flue for cooking and heating fires, and pipes to radiators in the other rooms. It will be insulated to prevent overheating of the kitchen. The finish is white enamel and chromium. Anthracite Industries Laboratories, Primos, Pa. (See figure 3.)

Mantles for Fluorescent Lights

A NEW PRODUCT which utilizes spun glass to reduce the glare of fluores-

(Continued on page 162)


An Industrial Expert

speaks of

OIL BURNING SYSTEMS

Nathaniel A. Owings, of the firm of Skidmore, Owings and Merrill, of Chicago and New York, is a well known architect who played an active role in the development of both the New York and Chicago World Fairs. He has done outstanding work in the industrial field for such concerns as Swift & Co. and Kimberly-Clark Corporation, and recently specified and installed a battery of Petro Burners in the Little Traverse Hospital in Petoskey, Michigan. Concerning oil burning systems he says:

"Architects and heating engineers have for some time recognized the advantages of oil burning systems for industrial plants. Especially in our defense program where unfailing production is vital, I believe that oil systems result in absolute dependability, efficiency and low operating costs. Where I have used the Petro Oil Burning System I have been gratified by excellent results and full company service."



Petro's four decades of specialized oil burning experience is reflected in the compactly efficient design of today's burners, one of which is illustrated.

This is an Automatic model for preheated No. 6 fuel oil, with modulating motor. Incorporating Petro's Thermal Viscosity System for correct and constant oil temperatures, this burner is automatic on even "cold" starting, stopping, and fire modulation to meet, instantly, variations in firing conditions while operating.

Such accurate, instrument-controlled, wholly automatic firing is not only labor-saving, but insures maximum delivered heat-value from the fuel under all normal firing conditions.

CAPACITIES: to 145 gal. per hr.—487 boiler h.p.—68,000 sq. ft steam E.D.R.

Petro Industrial Burners for Automatic operation with preheated No. 6 oil, or with No. 5 or lighter oils, are available in eight sizes, Models W-2½ to W-9 inclusive. Each burner is a self contained assembly of motor, fan, pump, rotary cup atomizer and interlocked air and oil adjustments, except W-9 which requires separate pump.

In the use of preheated No. 6 oil, the Petro Thermal Viscosity System is an integral part of a Petro installation,

insuring reliability of operation and fuel economy.

Semi Automatic and Manually controlled Model W Burners and "Mechanical" type units are also available to meet circumstances which do not require automatic operation.

To the Architect in domestic building, Petro offers a complete line of burners for use with existing heating plants and complete oil fired boilers and winter air conditioners.

Petro's Engineering Division will gladly answer questions. The Petro Industrial Equipment Catalog will be sent promptly on request.



PETRO
Cuts Steam Costs



PETROLEUM HEAT & POWER COMPANY

STAMFORD

—Makers of good Oil Burning Equipment since 1903—

CONNECTICUT

NEWS OF MATERIALS AND EQUIPMENT

(Continued from page 160)

cent lighting has recently been perfected. Composed of glass fibers arranged in layers of varying thickness between two sheets of transparent plastic, the product is available either in tubes which fit over standard fluorescent lights as a kind of mantle,

or in pliable, easily cut sheets. The sheets, which may be had in sizes up to 60 by 30 in., are adaptable to construction of shades for standard fluorescent lighting fixtures and also for panels designed as a covering for recessed fluorescent lighting installations. Because the fibers are obtain-

able in a range of colors, the product lends itself to a variety of decorative effects. Light Conditioning Company, 6 E. 45th Street, New York City.

Heat and Cold in One Package

A NEW WINDOW-TYPE room cooler is said to be the first to provide heat also, by reverse cycle refrigeration. In summer the refrigerant coil extracts heat from the room air and discharges it outdoors. Dial operation reverses the flow of the refrigerant gas, causing the condenser, exposed to the outdoors, to collect heat which passes to the inside coil and into the room. The unit fits an ordinary window and plugs into an electric outlet. It is not intended to supplant central heating, but to provide between-season warmth as well as ventilation, which operates independently of the heat-cooling mechanism. The conditioner has a capacity of 6,000 cooling units an hour and a heating capacity of 7,500 heating units an hour and up, depending on outside temperature. Operating cost is compared to that of an ordinary electric heater. Westinghouse Electric & Mfg. Co., Mansfield, Ohio.

"Core Feed" Electric Erasing Machine

SPEED AND CONVENIENCE in making erasures, in the drafting room and other departments, are promised by a new electric erasing machine, in which a 7-in. cylindrical rubber core can be fed down a tubular armature shaft as it wears out, and tightened by a chuck. Operation, which is said to be quiet, is controlled by a sliding button that fits under the index finger. A hinged ring in the lightweight aluminum motor housing permits the machine to be hung on a hook on drafting board, desk, or wall. Charles Bruning Co., Inc., 100 Reade St., New York City.

Quiet is Requested

SOUNDPROOFING has been added as a standard feature of a well-known line of architectural metal trim, which should make the product particularly acceptable in hospitals, libraries, schools, and other public buildings. The manufacturer applies to the back, unexposed surfaces of the trim a special sound-absorbent material

(Continued on page 164)



● Today women are fast coming to see that the *right* sink is **FORMED IRON**—many of them with the advice of *knowing* architects.

They like the graceful styling; the exceptionally high-luster porcelain enamel with its great ease of cleaning; the variety of colors; and the acid-resisting feature at no extra cost.

Then, when these new-day fixtures are porcelain enameled on ARMCO Ingot Iron, the story is

complete. For twenty-seven years the good qualities of this "world's standard porcelain enameling iron" have been nationally advertised to millions of American women—and men.

Formed Iron Plumbing Ware (formed, not cast) is an interesting new possibility for architects—sinks, lavatories, bathtubs, laundry tubs, all. Just send a postal card for complete information. The American Rolling Mill Company, 51 Curtis Street, Middletown, Ohio.



Sink fittings made of ARMCO Stainless Steel are bright, solid metal throughout. With no plating to wear off, they give lifetime satisfaction.



IMPERISHABLE PRINCIPLES

1905



No. 9136 F

The bottom half of this ball is ground glass with beautifully cut stars, the upper half is made with Pagoda Prisms, combining the "useful and artistic."


Illustrated Catalog sent on request

Holophane Glass Co.
Sales Dept.
227 Fulton Street, New York

Left: Reproduction of ad from Architectural Record, July, 1905

1941

Below: Photo of present-day Holophane In-Bilt Controlens Installation



Broadcasting studios of station KXV, Los Angeles, Cal. Architect William Lescaze, N. Y. C.

Photo courtesy C. B. S.

IN 1905—Holophane was a consistent user of the advertising columns of the Architectural Record (witness ad, above, left). The passing years have crowded this "useful and artistic" design into obsolescence. But the same sound lighting principles which justified the use of Holophane units by the architectural profession still persevere. . . .

SINCE ITS INCEPTION 42 years ago, Holophane has pioneered in lighting products of scientific design and precision construction. . . . Because the basic structural material of Holophane equipment is imperishable crystal prismatic glass, these units are impervious to ordinary depreciation from time and use. The ultimate application of Holophane equipment is a result of the sound experienced counsel which has been at the service of the architect and engineer for almost two generations.

THE ARCHITECTURAL ACCEPTABILITY of Holophane equipment is engendered by its unique ability to become an integral part of the interior architectural design. . . . "In-Bilt" lighting was first made available by Holophane through its Controlenses. No single development in latter-day lighting history has

been of comparable significance. Holophane "In-Bilt" Controlenses, for incandescent and fluorescent lamps, have been adopted by practically all fields of construction. Outstanding among these are Broadcasting Studios, Department Stores, Public Edifices, Airports, Schools and Recreational Institutes. It is significant that these are all essentially "Architects' Jobs".

HOLOPHANE WILL CONTINUE to design and manufacture controlled scientific lighting equipment which answers the severest requirements for efficient function and sound architectural design. . . . And offers the architectural profession every cooperation available through its design and engineering departments.

Holophane

COMPANY, INC.

Lighting Authorities—Since 1898

342 MADISON AVE.
NEW YORK CITY

THE HOLOPHANE CO. LTD.
385 Yonge St., Toronto, Canada

NEWS OF MATERIALS AND EQUIPMENT

(Continued from page 162)

which, it is claimed, eliminates both reverberation and sound transmission. Laboratory tests showed a 55% reduction in sound volumes under impact and a 73% reduction in sound decay time, which should be enough to muffle the sound of door and window slamming, or other accidental blows. Milcor Steel Company, Milwaukee, Wis.

Workable, Flexible Wallboard

A NEW ASBESTOS-CEMENT wallboard is announced with the important characteristic, according to the manufacturer, of withstanding nailing, sawing, hammering, and perforating without cracking or splitting. Also claimed for the product is a flexibility that makes it possible to curve it around 4-ft. radii without breaking. Rot-proof quality and high resistance to fire, rodents, termites, and vermin are given as advantages of the board when used in walls and ceilings. Es-


pecially recommended for bathrooms and kitchens for its adaptability to painting, repainting, or papering. Manufactured in sheets 3/16 in., 1/4 in., and 3/8 in. thick; 48 by 48 in. and 48 by 96 in.; or scored in 4-by-4-in. squares to represent tile. The Philip Carey Co., Lockland, Ohio.

Rust Protection for Steel Windows

PERMANENT rust protection for steel sash parts embedded in masonry walls is provided by a new asphalt-impregnated cotton envelope. The envelope is applied (by means of a brushed-on liquid bonder) over the edges of the steel sash which are to be concealed in the wall. A V-shaped recess in the envelope permits expansion and other slight movement of the sash and prevents bulging of the sash due to lintel deflection or normal building settlement. The use of this seal, the manufacturer reports, will protect hidden portions of steel sash indefinitely. Seal-O-Sash Company, 48 Herkimer Pl., Brooklyn, N. Y.

PHOTOGRAPHERS' CREDITS— pp. 58-136

58, 59:	Ernest Graham
60-63:	Maynard L. Parker
64-65:	Hedrich-Blessing; Kaufman & Fabry Co.
66-67:	Hedrich-Blessing
69:	St. Thomas
70-71:	Roger Sturtevant
72-73:	Roy C. Hyskell
74-75:	Julius Shulman, courtesy Portland Cement Association
76-78:	Roger Sturtevant
79:	G. E. Kidder-Smith
80:	McLaughlin Air Service; G. E. Kidder-Smith; U.S.H.A. (photo and map)
81:	Sigurd Fischer
82:	Paul Peters
83-84:	Julius Shulman
85:	Ivory Photo; Elmer L. Astleford
86-90:	Roger Sturtevant
91-93:	Hedrich-Blessing
94-95:	Fred R. Dapprich
96-98:	Roger Sturtevant
99-101:	Elmer L. Astleford
102-103:	Rodney McCay Morgan, Courtesy U.S. Plywood
107:	Roger Sturtevant
108-110:	Maynard L. Parker
112:	Julius Shulman
113:	Joseph W. Molitor; Gabriel Moulin
114-115:	Jimmy Wilson Studios; A. C. Kelly
116:	Lindsley and Wood
118:	Benj. Morse; Robert M. Damora
119:	Hedrich-Blessing
120:	Gabriel Moulin; Royal Photo Co.
121:	Ronald Morrisette
122-123:	Libsahn Ehrenberg; Vories Fisher
124:	Worsinger
126:	Columbia Commercial Studio, Inc.
127-129:	St. Thomas
130-131:	Fred R. Dapprich
132:	Robert M. Damora
133-135:	Courtesy Southern Pacific Railroad
136:	Union Pacific Railroad; The Burlington Road



*In Your Plans
for '41*

The coming year is a year of industrial expansion. Architects will be called upon to specify time-saving equipment, for production must be speeded and delays cut to a minimum. Halsey Taylor Drinking Fountains earn the right to primary consideration when planning the drinking water system. They are the choice of industrial buyers everywhere, for office or plant, for they combine features of positive sanitation with maximum convenience and economy. Write for detailed information on wall and pedestal fountains of all types as well as electric or ice coolers.

THE HALSEY W. TAYLOR CO., • WARREN, O.


Halsey Taylor
DRINKING FOUNTAINS

No. 4-A

TYPHONITE ELDORADO PENCILS



17 DEGREES, like 17 parallel lines . . .



...THEY NEVER MEET!

Never will you pick up a Dixon's Typhonite Eldorado stamped "2H" and find that it is a "3H" or an "H" in performance. Like parallel lines, the 17 degrees of Typhonite Eldorado never meet. Such uniformity is possible only because Eldorado leads are made from Typhonite particles that are minute twins. Each particle is minute in size, and each is the same size.

To achieve this perfection Dixon creates a new form of graphite in a typhoon of superheated steam. This new form is called Typhonite and the Typhonite process is exclusive with Dixon.

But uniformity is not all you should ask of a drawing pencil. Its lead must be strong and dense and smooth. Test Typhonite Eldorado for these qualities. And make the tests tough.

To test for strength, sharpen a Typhonite Eldorado to the finest point. To convince yourself that Dixon's Typhonite Eldorado pencils are smooth and opaque even in the hardest degrees, test the H degrees. Make these tests and know that there is no other pencil like Dixon's Typhonite Eldorado.

Your dealer carries Dixon's Typhonite Eldorado.

Pencil Sales Department 225-J1

JOSEPH DIXON CRUCIBLE COMPANY, JERSEY CITY, N. J.

SERVICE BUILDINGS CUT HEATING COSTS \$2,000 IN ONE YEAR

Webster Moderator Systems Give
Baltimore Buildings Balanced
Heating for 20 P.C. Less

BETTER WORKING CONDITIONS

Maintain Desired Temperatures
in Offices, Shops That Were
Formerly Hard to Heat

STEAM SUPPLY IS CONTROLLED

Baltimore, Md.—Heating costs in the maintenance and main engineering buildings of the Consolidated Gas Electric Light & Power Co. were reduced 20 per cent, or approximately \$2,000.00, in the first season after completion of a Webster Heating Modernization Program.


A Webster Moderator System and related auxiliary controls were installed at the Front and Monument Street buildings in 1938. Prior to the installation, it was difficult to maintain uniform temperatures in these buildings.



Maintenance and Main Engineering Buildings, Consolidated Gas Electric Light & Power Co., Baltimore, Md. Front Street Building, above; Monument Street Building, at right.

After the Webster Moderator System was placed in operation, the extreme fluctuations in building temperatures were eliminated. Buildings are now much more comfortable and working conditions have been greatly improved. The installation of the control equipment has proved to be a good investment.





There is a total of 66,500 square feet of installed equivalent direct radiation in the group of buildings.



LOW HEATING COST

GET THIS BOOK... Read the fact stories about economy and comfort in the heating of 144 buildings. No exaggerated claims. No promises. Just 64 pages of heating results. Ask for "Performance Facts."

WARREN WEBSTER & CO., Camden, N. J.
Pioneers of the Vacuum System of Steam Heating
Representatives in 65 principal U. S. Cities—Est. 1888



Photos at bottom courtesy Page Fence Assn.

LOOKING OVER FENCES

By JULE ROBERT VON STERNBERG

"GOOD FENCES MAKE good neighbors," said New England's Robert Frost in his poem, "Mending Wall."

The subtle shading of that truistic line suggests the hedgerows of England, the serpentine walls of Tom Jefferson, and the woven wire fences of modern America. Each is good in its own way; each has made many good neighbors.

The quality of that goodness has almost always been the concern of architects. We say "almost always," because the first fence—like the first house—was doubtless built by an engineer. He gave it structure and direction. From then on, the architect gave it form, color, and usefulness.

This trinity of virtues, however, is not always equally disposed. Rather,

one tends to outweigh the others, as first form, then use, then color predominates. As a result, most fences fall into two groups: protective and decorative.

The protective fence is utilitarian; its chief aim: to define a boundary. In this respect, it may be intended to keep cows in a pasture, or fifth columnists out of a factory compound.

It may be built for permanence—like the Great Wall of China—or it may be more ephemeral—like snow fences that rise and fall with the season. It may be transparent, translucent, or opaque. It may, like a good rabbit fence, extend underground as well as overground. Or, just as con-

(Continued on page 168)



EVERY SIZE
EVERY SHAPE

rolled by Bethlehem

No mills in America roll a more complete line of structurals than Bethlehem's. Bethlehem covers the entire field with wide-flange shapes from 8 in. to 36 in., standard shapes from 3 in. to 24 in. and light sections from 4 in. to 12 in. In addition, Bethlehem produces angles, zeeks, channels, car building, shipbuilding and miscellaneous shapes in all sizes.

BETHLEHEM STEEL COMPANY



(Continued from page 166)

trarily, it may dangle in the air, hundreds of feet above the earth, to ward off enemy aircraft.

Such is the protective fence. The decorative fence caters largely to our love of sentiment. Although useless in the engineer's scheme of usefulness, every age has cherished the

right to employ it as an architectural flourish—as witness the Regency roof parapet, the Victorian crenelation, and our own suburban speculative builder's split-rail fence, setting off his Cape Cod cottage.

Application of an aesthetic philosophy to the design of fences requires merely the balancing of the same

voids, solids, colors, and patterns that are involved in any architectural design. But while the design of a building, for example, reflects the nature of its plan, the personality of its inner use, the fence is an aesthetic diplomat which must harmonize with both inner and outer buildings and their environment. It holds the family of building and environment together, strengthening and embellishing them both, presenting cultural tone in its detail, strength in its structure and pattern, and direction in its use. If properly designed, it must be at once a gateway to the core of a building, yet seem simply a partition in the world of its environment.

Some fences, of course, may combine both architectural precision and natural casualness. Stone and rail fences come quickly to mind in this respect. They can run over hillocks, up and down, without losing the rhythm of their patterning. The more formal masonry fence, however, designed to recall the planar beauty of the structure it serves, must usually be cut and stepped to form a series of sleek, well-ordered terraces. Trailing the problem of land conformation is the problem of color. Although many are painted, few fences are ever colored. Yet application of color may convert a conventional chain-link fence, for example, into a dazzling beauty; may make it conform better with the building within it. Color can emphasize the real beauty of a fence—or conceal its plainness.

Strangely enough one rarely thinks of fences in terms of use. Rather they have been classified by pattern or material: picket, lattice, faggot, board, slat, rail, stone, iron, wire, or brick. This is convention so that choice is frequently made without thinking of the basic architectural problems involved. Perhaps by considering fences in a new light as important elements of architectural design with wide potentials of adaptability, new and more apt solutions may emerge to the problem of protection—solutions clothed in colorful new beauty, sleekly patterned and rich in modern usefulness.

Ever see a TERRAZZO INTERIOR?



● Fifth Avenue Hospital addition, New York City. Architects, Reinhard & Hofmeister.

IN the hospital interior shown above, not only the floor, but also the border, base, wainscot, wall surface, and stairway are Terrazzo. You see it everywhere but in the ceiling.

Terrazzo, one of the world's oldest floor finishes, is proving its versatility in modern design and construction in hospitals and almost every other type of building. Its color and design possibilities are unlimited. It thrives on pounding and actually improves with wear. It eliminates replacements and cuts upkeep to almost nothing.

Are you modernizing, building an addition, or erecting a new structure? Specify Terrazzo for enduring beauty, amazing durability, and lasting economy. For detailed information on Terrazzo, see Sweet's Catalog, or write today to the National Terrazzo and Mosaic Association, 1420 New York Ave., N. W., Washington, D. C.

5 Reasons for Using Terrazzo

1. ECONOMY. Initial cost *plus* no repairs...no replacement...minimum upkeep over a period of years, for Terrazzo equals—usually is less than—initial cost *plus* repairs...and replacements...and higher upkeep for other types of floors.

2. COMFORT. Finished Terrazzo is easy to walk on. It is less slippery than any waxed surface. Furthermore, Terrazzo can save you enough money to acousticate your ceiling, thus giving you a very low noise level.

3. CLEANLINESS. Terrazzo can be sealed so as to be practically non-absorbent. Its smooth, jointless surface cleans easily...can harbor no accumulation of macroscopic or microscopic germs. It is aseptic.

4. COLOR AND DESIGN. Terrazzo has warmth and beauty. You may specify any design you wish—pictorial or geometric—in virtually any combination of colors.


5. DEPENDABLE INSTALLATION. This Association's objective is to see that your Terrazzo installations turn out exactly as you want them. Write us today for complete information on the above points or see our advertisement in Sweet's Catalog for basic technical data.

THE NATIONAL TERRAZZO AND MOSAIC ASSOCIATION

ANOTHER OUTSTANDING HOUSING PROJECT

ENJOYS HEAT BY

FITZGIBBONS STEEL BOILERS



MULFORD HOUSING PROJECT THE MUNICIPAL HOUSING AUTHORITY CITY OF YONKERS, N. Y.

Architects:

Louis F. Thorn Wm. P. Katz, Inc.

Frank A. Carr

Wm. W. Schwartz, P.E.

Consulting Engineer: Chauncey Matlock

Heating Contractor: A. B. Barr & Co.

General Contractor: Psaty & Fuhrman, Inc.

Boilers:

4 RM 425 R.Z.U. Fitzgibbons Boilers 42,500
sq. ft. Steam Rating each Oil Burning.



MULFORD HOUSING PROJECT

at Yonkers, N. Y. recently opened for occupancy, represents an interesting example of intelligent modern planning, successfully carried out. It is designed to provide moderate cost homes for 552 families, with the maximum of air, light, and recreation facilities. An important element of upkeep cost is heating, and the care with which this factor was considered is shown by the selection of four Fitzgibbons Steel Boilers of R-Z-U type, oil fired, to supply the 170,000 sq. ft. of steam rating which the project requires.

An unusual circumstance is the location of the central heating plant housing the boilers, at the highest point on the grounds approximately 80 feet above the lowest apartment building. Condensate return is effected by pumps.

As in various other large housing projects in or near metropolitan areas, Fitzgibbons steel boilers are developing the required radiation with most satisfactory overall economy.

The Fitzgibbons R-Z-U Catalog will give you some reasons why architects and heating contractors entrust their reputations to these boilers. Write for a copy.

Fitzgibbons Boiler Company, Inc.

101 PARK AVENUE, NEW YORK CITY

Branches and Representatives in Principal Cities

FITZGIBBONS for **STEEL BOILER ECONOMY**
ON LARGE JOBS and SMALL

TRENDS IN BRIEF

WASHINGTON NEWS ON DEFENSE

(Continued from page 20)

the focus will be on cantonments, defense housing projects, supply depots, and airports. Even highway work, which normally brings new building on the routes improved, will be fo-

cused on strategic roads and bridges.

Reports of delay in defense housing are evidence of the need for employment of local architects who are familiar with conditions and can cut corners far faster in their own home towns than can the desk men operat-

ing from Washington. There appears, however, to be little place for private architects in the programs now authorized, so that their participation on any large scale will await the launching of further programs by the new Congress insofar as strictly Federal undertakings are concerned.

On the cantonment work, the Navy projects are well advanced due to good advance planning. Most of the stories as to delay concern Army jobs which are so far behind that the first conscription contingents have had to be reduced in many areas through lack of barracks for the men. Industrial defense housing stands about as we reported it last month and is not so seriously in arrears since the production program itself is behind. Of 35,000 housing units allocated, contracts have been let for 28,000, most of which are under construction.

No progress has been made over the past month in the recognition of private architects in the defense housing work. As a whole, the defense structure has been awaiting the changes at top, made recently with the appointment of a super-board of Knudsen, Hillman, Stimson, and Knox. Such down-the-line changes as may affect construction activities will of course await the settlement of the major problems before Mr. Knudsen.

One sideline change was the appointment of Stewart McDonald as Deputy Federal Loan Administrator to assist Jesse Jones. Abner Ferguson, next in line at FHA, succeeds him as Federal Housing Administrator. But no basic change in FHA policy is indicated from this shift.


Plant expansions

Where the private architect really will function is in the new plant expansions in defense industries. But, although the new defense-British aid program contemplates a huge construction effort, the work is not likely to materialize for some weeks.

For example, it is obvious that new aircraft plants and assembly units will be necessary. Yet plans are in a high state of flux. Top officials state that it is not yet known how many new factories will be required. Even the big government assembly plants are not under way.

Main reason is that the first job is to organize efficiently the production

(Continued on page 172)

The above detail shows stool No. 302 with trim No. 305 used as a splayed jamb.

WHEN you choose Knapp Products for interior trim, you are combining these essentials of modern construction: Beauty . . . Utility . . . and Economy.

The graceful contours of Knapp window trim and stools — the simplicity and durability of Knapp base — the practical and decorative value of Knapp chair rails — give an interior the attractiveness and permanence you seek in your design.

Knapp Metal Trim is fireproof, vermin-proof, and is not subject to warping or decay. It is truly the modern trim for today's modern construction. We would like to send you a complete set of full sized details of all Knapp trim for your files. Write for them today.

FOR FURTHER INFORMATION



The leadership of Knapp metal trim was attained through 30 years of manufacturing and supplying this complete line:

Window and door trim • window stools • baseboards • chair rails • blackboard trim and chalk trough • picture moulds • corner bead • grounds • screeds • and many other kindred products.

KNAPP METAL TRIM
KNAPP BROS. • MANUFACTURING CO.
GENERAL OFFICES • JOLIET, ILLINOIS



If it isn't plate glass and it isn't window glass...

WHAT IS IT?


You can't call this new Lustraglass a window glass *because* that "distorting waviness" which is characteristic of all window glass has been almost entirely removed. On the other hand, Lustraglass *does* sell at window glass prices. Look at a sample. See its beautiful jewel-like luster and "whiteness of metal." Notice its relative freedom from that greenish cast common to other glass used for regular glazing. Remember that it transmits ultra-violet rays of sunlight and demonstrates amazing tensile strength. Compare these definite advantages of this improved Lustraglass with those of any glass at any price and give us *your own* opinion of how we should classify it.

AMERICAN WINDOW GLASS CO.

PITTSBURGH, PA.

Manufacturers of Plexite, the safer safety glass; Lustrablu and Lustragold for ornamental uses; Crystal Sheet, Chipped and Special Glass for industrial purposes.

THE SHADOWGRAPH TELLS THE STORY by amplifying distortion and defects 20 times



(1) This is high quality cylinder drawn window glass. The bent and twisted lines shown by the shadowgraph testing device indicate the presence of considerable distortion. This glass became obsolete in 1928.



(2) Here is what most manufacturers offer today as top quality window glass... Made by the sheet drawn process, it shows a characteristic distortion in the waviness of the black lines.



(3) Now look at this "shadowgraphed" sample of the new Lustraglass. Obviously an important improvement. The lines are straight, showing relatively perfect vision—relative freedom from distortion.

● Write for the new Windowgraph Slide Rule Chart and a sample of the new Lustraglass. Examine both—then tell us what you think.



THIS NEW TYPE OF
LUSTRAGLASS
The Ultra-Violet Ray Sheet Glass

LOOKS LIKE PLATE GLASS—SELLS AT WINDOW GLASS PRICES

TRENDS IN BRIEF

WASHINGTON NEWS ON DEFENSE

(Continued from page 170)

facilities of the country as they now stand toward a free flow of supplies, especially as concerns the many subcontractors, brought under the Prior-

ities Board by Executive order last month, and the suppliers of the contractors and subcontractors. Full operation of present plants will minimize the need for new facilities in basic industries while the demand for expansion is more in specialized lines

such as the aircraft industry.

A new field of some promise is in airport building construction. The Civil Aeronautics Administrator has allocated his first \$40,000,000 among some 200 widely scattered projects. Improvements to the landing fields are done by CAA while the administration buildings, shops, and hangars are financed by the municipalities or agencies which own the airports.

A minor Federal development in the past month is the construction of standard post offices at Army posts to take care of the conscripts' needs.

Building material prices


Defense Commissioner Leon Henderson is keeping a watchful eye on prices of all materials involved in the defense construction program, with the close co-operation of the government construction agencies. Little tendency toward price rises has been observed except in the case of lumber. Most materials and items of equipment—including bath tubs, furnaces, etc.—are being purchased in large lots, often at prices substantially below the prevailing level.

In the case of lumber, officials trace the price rises and the local shortages in some areas to what they consider the failure of the industry to maintain adequate stocks. In 1929, it is pointed out, 10 billion feet of lumber were in stock for a volume of 30 billion feet for the year. On December 1, stocks totaled approximately 6¾ billion feet and the year's business is estimated at 28½ billion.

Officials are studying every possible means to use other materials in Federal building to prevent a further shortage and price rise in lumber. Prices are such that, in some Southern areas, bids for brick houses are cheaper than for frame construction. In a midwestern area, steel is found cheaper. Use of substitutes such as gypsum board and the like is contemplated in Federal practice. Officials would not be averse to similar specifications by private architects in order to conserve the available supply of lumber.

Although lumber prices have settled back to some extent and may reach a more stable level now that most of the cantonment material has been bought, Mr. Henderson recently

(Continued on page 174)



IN DETROIT...it's Solder and Cotton!

IN JACKSONVILLE...Tobacco Dust!

In your plant it may be lead dust, silica sand, papers or sawdust—or maybe just plain dirt that slows up production, injures the product, produces rejects and lost output. Probably even now it is costing you more to "clean" your plant than it would to really clean it with a Spencer Vacuum Cleaning System.


A survey of 440 plants using Spencer Vacuum on areas varying from a single department to a million square feet shows that it is universally used for walls, ceilings and pipes, as well as floors and that the cleaning is frequently done during working hours. In addition it is used to clean machinery, raw material, packages, finished goods, and to reclaim valuable scrap materials.

You can write a Spencer System off with its savings in two or three years. It is built to last a lifetime. Many of them have been in service for a quarter century.

Write for this New Book on
INDUSTRIAL CLEANING

See how others clean large areas at low cost and save in production and maintenance because Spencer does the jobs that cannot be done by other methods.

ASK FOR BULLETIN 120-AR



SPENCER CENTRAL AND PORTABLE
HARTFORD VACUUM CLEANING SYSTEMS
THE SPENCER TURBINE COMPANY, HARTFORD, CONN.

Armstrong Tire & Rubber Co.'s Natchez (Miss.) plant includes a 160 x 760-ft. factory, office building and power plant. Architectural Concrete exterior walls; reinforced concrete Z-D barrel shell roof with 40 x 50-ft. clear bays. Roberts & Schaefer Co., Chicago, engineers. J. T. Canizaro, Jackson, Miss., architect.



Industry endorses **CONCRETE** for economy, firesafety, appearance




Architectural concrete offers a unique combination of advantages for industrial and defense buildings:

- **SPEEDY** construction; contractors are setting constantly faster time schedules in completing concrete buildings. Concrete jobs proceed all winter.
- **ECONOMY** in first cost and maintenance.
- **ADAPTABILITY** to any requirements of occupancy; for example long, clear interior spans are easily provided.
- **FIRESAFETY**—concrete can't burn; supports heavy loads even at high temperatures.
- **WEAR RESISTANCE** for heavy-duty floors and ramps.
- **RIGIDITY** to dampen vibration and resist shocks.
- **GOOD APPEARANCE**—Architectural concrete has won national recognition as a means of giving outstanding architectural distinction to factories and buildings of all kinds. Walls are cast integrally with frame, floors and roof in one time and money saving material.

Warehouse for Woodbury & Company, dealers in industrial supplies and heavy hardware, Portland, Oregon. Richard Sundeleaf, architect. Wegman & Sons, contractors.

(Below) Engine test house, Pratt & Whitney Aircraft Division of United Aircraft Corporation, East Hartford, Conn. Albert Kahn, Detroit, architect. R. G. Bent Co., Hartford, contractor.



Building Owners: Materials for concrete are easily available in abundance. Competent architects, engineers and contractors experienced in concrete are at your command. Your architect or engineer can give you detailed facts about concrete.

Write for illustrated booklet, "*Concrete for Industrial Buildings*," (free in the U.S. or Canada) or ask one of our engineers to call. See Sweet's Catalog.

PORTLAND CEMENT ASSOCIATION

Dept. A1-8, 33 W. Grand Ave., Chicago, Ill.

A national organization to improve and extend the uses of concrete...through scientific research and engineering field work

TRENDS IN BRIEF

WASHINGTON NEWS ON DEFENSE

(Continued from page 172)

issued the following warning: "The lumber industry itself has much to lose in too high a price since markets lost to substitutes take years to regain, and high prices have always

had the effect of encouraging substitutes."

Effect of high labor costs

Also bearing toward changes in architects' specifications in all types of construction is the high cost of labor. Thus far, there has been no

really serious labor problem in the construction phases of the defense program as concerns strikes and the availability of men, although skilled workers and foremen are hard to get in some areas. Heavy overtime payments for work on Saturdays, Sundays, and after hours, however, have been a mounting factor in costs.

Sidney Hillman, placed on the new Defense Council to give labor a voice in the program, is seeking to keep the labor situation in hand by arbitration rather than by new legislation. He is organizing a series of committees, first for major industries such as shipbuilding and aviation. The construction industry doubtless will have its special boards, both national and regional, to curtail strikes and jurisdictional disputes.

But the general policy of the administration is to keep wages up while holding prices down so that there will be a stimulus to our domestic economy through heavy consumer purchasing power at the same time the defense program goes forward.

While this policy will tend to keep private construction going through the defense effort, unlike the World War period wherein all nonmilitary building activities were greatly curtailed, it also places a premium on labor-saving materials and methods.

T.N.E.C. findings

Careful thought has been given to this subject in the housing monograph of the Temporary National Economic Committee, written by Peter A. Stone, Coordinator of Construction Studies. The final report of the committee is pending and efforts are expected in the next Congress to put its findings into effect.

Pointing out that it is not feasible to reduce wages, the report recommends a broad program of industrial research, aimed toward low-cost materials and methods, with especial emphasis on the development of a new material of proper weight, strength, durability, insulation, and other qualities to reduce the number of layers required in the walls of present buildings. Scientific management, standardization of materials, dimensions, and building codes, and the discouragement of restrictive practices by the Justice Department are further recommended.



How these
Fedders Data Books
are making the job easier for
Architects and Engineers...

You will find that their working data has been compiled, charted, arranged and indexed to short cut figuring time. They are accurate, practical, readable and convenient to use.

Exclusive, copyrighted Time Saver Charts eliminate involved computations and reduce figuring time of heating coils to minutes instead of hours.

When you see and use this set of Fedders Data Books you will automatically sense that the products which they cover are naturally as well designed as the books themselves.

Fedders heating and air conditioning products meet a wide variety of industrial and commercial requirements.

Ask the Fedders representative in your locality for a set of these data books for your personal use—or mail the handy coupon right now.

FEDDERS MANUFACTURING CO., Inc.
Air Conditioning Division
93 Tonawanda St. Buffalo, N. Y.

Kindly send me the Data Books checked below.

☐ Unit Heater Catalog 573
☐ Type K Heating Catalog AC 601
☐ Unit Cooler Catalog AC 300
☐ Unit Air Conditioner Catalog AC 202
☐ Cooling Coil Catalog 392
☐ Type K Time Saver Charts AC 602

Name
Concern
Street
City State

IN THIS BOOK IS THE ANSWER TO

Profitable Air Conditioning for Architects



25 YEARS EXPERIENCE
is summed up in this
handsome brochure.
Be sure you see it!

Today more than ever before, architects are providing for sound economic operation and for *future* utility in their plans. Whether the job be home or office building, store, factory, or theatre—air conditioning is part of it.

Architects know that air conditioning can solve problems of design and engineering . . . problems of cost and upkeep, rentals, mortgages, amortization . . .

That is why they turn to Carrier to help them plan permanent performance, satisfaction and economy

in air conditioning installations. For Carrier knows the engineering *and* the profit angles . . . the problems of air conditioning in every type of building—and can help you solve them.

Big Savings Over Former Costs

Creating comfort that pays a profit has been Carrier's business for more than 25 years. Today, because of its pioneering and its experience in whipping every kind of air conditioning problem, Carrier can offer you air conditioning to *fit your needs*; factory perfected; quickly installed;

lower than ever in cost; higher than ever in dependability, economy and profitable comfort.

Find Out How Your Clients Can Profit

The complete story of Carrier Air Conditioning, the activities and achievements of more than a quarter century, form the exciting contents of a new brochure just off the press. It's a story you'll want to know . . . a story that shows the way many industries and businesses have profited with Carrier Air Conditioning. Your Carrier Representative will be glad to show you how your clients can profit too. Call him.

AIR CONDITIONING'S
FIRST NAME



CARRIER CORPORATION
"Weather Makers to the World"
SYRACUSE, NEW YORK
(In Canada, 30 Bloor St. West, Toronto, Ontario)

Desk A28

Yes, have your Carrier representative show me the record of Carrier achievement and how it can mean more profits.

NAME.....
ADDRESS.....
CITY.....

REVIEWS OF CURRENT LITERATURE

(Continued from page 24)

striking format, a novel page arrangement liberally—and literally—rubricated to emphasize the editorials, and a subject almost poignantly interesting: the city of the future as exemplified in Broadacre City. The topic will be further developed in the sec-

ond number to be devoted to the life and activities of the Taliesin Fellowship and "in effect a description of a working model (the only one in the world) of an Organic Life for an Organic Architecture."

The present number might be described as handling that subject in

reverse, namely, an organic architecture for an organic life, as illustrated in the model now on display in New York; which shows "four square miles of a typical countryside in the temperate zone, developed on the acre as a unit and accommodating some 1400 families."

In nine or ten articles are set forth in principle, with somewhat less precise counsel on how they may be practically achieved. Broadacre's civic ideals. These include: no institutes, no petty officialdom, no politicians, no academicians. No poles, no wires in sight, no lighting fixtures, no visible lamps. No tenant, no landlord, no regimentation except in affairs of government. No traffic problem, no slum, no scum.

Technical Code — Precalculated. By Henry Aronson. Artisan, Chicago, 1940, Nov., pp. 33-35, 114; Dec., pp. 38-43, 107. Charts

INCREASING numbers of local ordinances incorporate wholly or in part the National Warm Air Heating and Air Conditioning Association's Technical Code, yet many contractors hesitate to adopt it because of the time required to figure a job by its use. These articles are the first of a series of six planned to show ways and means of shortening the time required to apply the Code without eliminating any of the essentials.

Panel Heating with Warm Well Water. By Ernest Weber. Heating, Piping, and Air Conditioning, New York, Dec., 1940, pp. 714-715. Illustrated.

DESCRIPTION of panel heating of a garage at Klamath Falls, Ore., which has underground lakes of warm water. The "heating plant" is a 3-in. pipe extending 450 ft. into the well, with a 2-in. return pipe enclosed in a 4-in. insulated cover pipe, and a motorized pump for circulation.

Construction and Operation of Fluorescent Lamps. By Dean M. Warren. Power, New York, Nov., 1940, pp. 74-76. Illustrated.

THE POWER factor, stroboscopic effect, flicker, and radio interference of fluorescent lighting are explained by Mr. Warren of the General Electric Company. Tables on the flicker of lamps on 60-cycle circuits and on the tube radiation of radio waves are useful to architects.



Beautiful... Modern... Adaptable... Durable—AZROCK Tile easily claims these qualifications. And these pictures of the AZROCK installation in a modern tourist court amply illustrate what we mean. Here is beauty in a modern setting; adaptability too, for AZROCK is at home here as everywhere—in offices, homes, restaurants, stores and public buildings of

all types. As for durability, the many installations still in use after years of service attest to AZROCK'S ability "to take it" under constant and hard traffic.

AZROCK has two important, exclusive features: It is micro-cut, assuring a close, sanitary, easy-to-clean floor; an integral wax finish applied to AZROCK during manufacture simplifies polishing, adds to life of tile.

And AZROCK's gentle resiliency means a floor comfortable to walk on, quiet. A variety of colors and sizes for any pattern or design.

AZROCK

TRADE MARK REG. U.S. PAT. OFF.
Manufactured by

Uvalde Rock Asphalt Co.
(In Business Since 1912)

General Offices: San Antonio, Texas;
Mines: Blewett, Texas; AZROCK
Plant: Houston, Texas; Distributing
Contractors: principal cities of U. S. A.

